Rubin Observatory

Vera C. Rubin Observatory
Data Management

LSST Data Management Acceptance Test Specification

L.P. Guy, W.M. Wood-Vasey, E. Bellm, J.F. Bosch, M. Butler,
J.L. Carlin, H.-F. Chiang, G. Comoretto, G.P. Dubois-Felsmann,
M. Gower, M.L. Graham, R. Gruendl, K.S. Krughoff, K.-T. Lim,
R.H. Lupton, F. Mueller, C. Slater, J.D. Swinbank

LDM-639

Latest Revision: 2020-10-12

Abstract

This document describes the detailed acceptance test specification for the LSST Data Management System.

Change Record

Version	Date	Description	Owner name
1.0	2019-02-07	Document first approved release. Approved on RFC-495.	L. Guy
2.0	2019-07-29	Add test cases for all Priority 1a requirements. Approved in RFC-622.	Document: J. Carlin; Approver: W. O'Mullane
2.1	2020-02-17	Consolidated test cases for DMTR-201 test activity. Approved in RFC-669.	J. Carlin
2.2	2020-08-21	Merge test specifications LDM-534, LDM-534, LDM-538, LDM-538. Update author list. RFC-721	L. Guy

Document curator: Leanne Guy

Document source location: `https://github.com/lsst/ldm-639` from Jira

Version from source repository: 56be085

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

iii

Rubin Observatory

Contents

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

Rubin Observatory

**DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

xvi

Rubin Observatory

Rubin Observatory

LSST Data Management Acceptance Test Specification

1   Introduction

This document specifies the acceptance test procedures for the LSST Data Management System. It is a living document that is updated as new functionality is delivered and acceptance testing proceeds. A full description of the LSST Data Management System is provided in the Data Management System Design document, LDM-148 with the science requirements detailed in the LSST Science Requirements Document LPM-17.

1.1   Objectives

This document builds on the description of LSST Data Management's approach to testing as described in LDM-503 to describe the detailed test cases that will be performed to verify the Data Management System.

It provides test designs, test cases and procedures for the tests, and the corresponding pass-/fail criteria for each test.

1.2   Scope

This document provides the acceptance test plan for the Data Management System (DMS), as described by the Data Management System Requirements in LSE-61.

Rubin Observatory

1.3 Applicable Documents

LPM-17   LSST Science Requirements Document
LDM-148   LSST Data Management System Design
LDM-294   LSST DM Organization & Management
LDM-503   LSST DM Test Plan
LSE-61   LSST DM Subsystem Requirements
LSE-163   LSST Data Products Definition Document
LDM-151   LSST DM Science Pipelines Design
LSE-180   Level 2 Photometric Calibration for the LSST Survey
LSE-30   LSST Observatory System Specifications

1.4 References

[1] **[LSE-30]**, Claver, C.F., The LSST Systems Engineering Integrated Project Team, 2018, *Observatory System Specifications (OSS)*, LSE-30, URL `https://ls.st/LSE-30`

[2] **[LSE-61]**, Dubois-Felsmann, G., Jenness, T., 2018, *LSST Data Management Subsystem Requirements*, LSE-61, URL `https://ls.st/LSE-61`

[3] **[LDM-554]**, Dubois-Felsmann, G., Ciardi, D., Mueller, F., Economou, F., 2018, *Science Platform Requirements*, LDM-554, URL `https://ls.st/LDM-554`

[4] **[LPM-17]**, Ivezić, Ž., The LSST Science Collaboration, 2018, *LSST Science Requirements Document*, LPM-17, URL `https://ls.st/LPM-17`

[5] **[LSE-131]**, Jacoby, S., Emmons, B., Selvy, B., 2017, *Interface between Data Management and Education and Public Outreach*, LSE-131, URL `https://ls.st/LSE-131`

[6] **[LSE-180]**, Jones, L., 2013, *Level 2 Photometric Calibration for the LSST Survey*, LSE-180, URL `https://ls.st/LSE-180`

[7] **[LSE-163]**, Jurić, M., et al., 2017, *LSST Data Products Definition Document*, LSE-163, URL `https://ls.st/LSE-163`

[8] **[LDM-142]**, Kantor, J., 2017, *Network Sizing Model*, LDM-142, URL `https://ls.st/LDM-142`

Rubin Observatory

[9] **[LSE-400]**, Lim, K.T., 2019, *Header Service Interface*, LSE-400, URL `https://lse-400.lsst.io`

[10] **[LDM-148]**, Lim, K.T., Bosch, J., Dubois-Felsmann, G., et al., 2018, *Data Management System Design*, LDM-148, URL `https://ls.st/LDM-148`

[11] **[LDM-552]**, Mueller, F., 2017, *Qserv Software Test Specification*, LDM-552, URL `https://ls.st/LDM-552`

[12] **[LDM-294]**, O'Mullane, W., Swinbank, J., Jurić, M., DMLT, 2018, *Data Management Organization and Management*, LDM-294, URL `https://ls.st/LDM-294`

[13] **[LDM-503]**, O'Mullane, W., Swinbank, J., Jurić, M., Economou, F., 2018, *Data Management Test Plan*, LDM-503, URL `https://ls.st/LDM-503`

[14] **[LDM-151]**, Swinbank, J.D., et al., 2017, *Data Management Science Pipelines Design*, LDM-151, URL `https://ls.st/LDM-151`

1.5 Acronyms

Acronym	Description
AP	Alerts Production
C	Specific programming language (also called ANSI-C)
CPP	C++ Programming language
DAC	Data Access Center
DB	DataBase
DBB	Data BackBone
DM	Data Management
DMCCB	DM Change Control Board
DMS	Data Management Sub-system
DR	Data Release
DRP	Data Release Production
EFD	Engineering Facilities Database
IT	Integration Test
IVOA	International Virtual-Observatory Alliance
K	Kelvin; SI unit of temperature
LAN	Local Area Network

LDM	LSST Data Management (handle for controlled documents)
LPM	LSST Project Management (Document Handle)
LSE	LSST Systems Engineering (Document Handle)
LSP	LSST Science Platform
LSST	Large Synoptic Survey Telescope
M	Mega; SI units prefix for 1E6
MOPS	Moving Object Pipeline System
OCS	Observatory Control System
PDAC	Prototype Data Access Center
S	Strip (CCD chip along-scan coordinate identifier in focal plane)
SODA	SCOS ORATOS Distributed Access
SQL	Structured Query Language
STS	System Test Specification
W	Watt; SI unit of power
p	pico; SI units prefix for 1E-12

2   Approach

This document describes the acceptance tests for the Data Management System, with a focus on whether the data products, functionality and services satisfy the requirements described in LSE-61.

The requirements from LSE-61 are extracted into the Jira "LSST Verification and Validation" Project, managed through the Jira Test Management Plugin system. Each LSE-61 requirement leads to a "LSST Verification and Validation" (LVV) Element. Each LVV Element comprises one or more more Test Cases. Each Test Case describes a Test Script to be executed, the coverage, pre-conditions, configuration, test results, and other details as specified by LDM-503. Test Scripts may have common set up and analysis steps. The Jira system allows for these steps to be shared by other Test Scripts. This improves clarity and consistency across all Test Cases.

In this document, each Test Case is listed here with the LVV Element it tests, a summary of the Test Items exercised by the Test Case, and the detailed steps to be executed by the Test Case. Shared steps between Test Scripts have been explicitly written out to appear fully in each Test Case.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

4

2.1   Features to be tested

All top-level requirements for the LSST Data Management System described in LSE-61 are to be tested, including

- Rubin Data Products, including their production, scientific fidelity and persistence,

- Alert, Calibration and Data Release Production pipelines and the execution of payloads,

- Middleware,

- Qserv, the LSST parallel distributed database,

- Services provided by the Rubin Data Facility,

- Rubin facilities including the data archive, base, summit, and the communications between them to accept science and engineering data.

2.2   Features not to be tested

This document does not describe facilities for periodically generating or collecting key performance metrics (KPMs), except insofar as those KPMs are incidentally measured as part of executing the documented test cases.

2.3   Pass/fail criteria

The results of all tests will be assessed using the criteria described in LDM-503 §4.

Note that when executing pipelines, tasks, or individual algorithms, any unexplained or unexpected errors or warnings appearing in the associated log or on screen output must be described in the documentation for the system under test. Any warning or error for which this is not the case must be filed as a software problem report and filed with the DMCCB.

2.4   Suspension criteria and resumption requirements

Refer to individual test cases where applicable.

2.5   Naming convention

LVV : Is the label for the "LSST Verification and Validation" project in Jira.

LVV-XXX : Are Verification Elements, where XXX is the Verification Element identifier. Each Verification Element has at least one Test Case.

LVV-TYYY : Are Test Cases. Each Test Case is associated with a Verification Element, where YYY is the Test Case identifier.

The Verification Elements are drawn from LSE-61 requirements which have names of the form DMS-REQ-ZZZZ.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

6

Rubin Observatory

3 Test Cases Summary

Test Id	Test Name
LVV-T10	DRP-00-00: Installation of the Data Release Production v14.0 science payload
LVV-T11	DRP-00-05: Execution of the DRP Science Payload by the Batch Production Service
LVV-T12	DRP-00-10: Data Release Includes Required Data Products
LVV-T13	DRP-00-15: Scientific Verification of Source Catalog
LVV-T14	DRP-00-25: Scientific Verification of Object Catalog
LVV-T15	DRP-00-30: Scientific Verification of Processed Visit Images
LVV-T16	DRP-00-35: Scientific Verification of Coadd Images
LVV-T17	AG-00-00: Installation of the Alert Generation v16.0 science payload.
LVV-T18	AG-00-05: Alert Generation Produces Required Data Products
LVV-T19	AG-00-10: Scientific Verification of Processed Visit Images
LVV-T20	AG-00-15: Scientific Verification of Difference Images
LVV-T21	AG-00-20: Scientific Verification of DIASource Catalog
LVV-T22	AG-00-25: Scientific Verification of DIAObject Catalog
LVV-T23	Verify implementation of Storing Approximations of Per-pixel Metadata
LVV-T24	Verify implementation of Computing Derived Quantities
LVV-T25	Verify implementation of Denormalizing Database Tables
LVV-T26	Verify implementation of Maximum Likelihood Values and Covariances
LVV-T27	Verify implementation of Data Availability
LVV-T28	Verify implementation of measurements in catalogs from PVIs
LVV-T29	Verify implementation of Raw Science Image Data Acquisition
LVV-T30	Verify implementation of Wavefront Sensor Data Acquisition
LVV-T31	Verify implementation of Crosstalk Corrected Science Image Data Acquisition
LVV-T32	Verify implementation of Raw Image Assembly
LVV-T33	Verify implementation of Raw Science Image Metadata
LVV-T34	Verify implementation of Guider Calibration Data Acquisition
LVV-T35	Verify implementation of Nightly Data Accessible Within 24 hrs
LVV-T36	Verify implementation of Difference Exposures
LVV-T37	Verify implementation of Difference Exposure Attributes
LVV-T38	Verify implementation of Processed Visit Images
LVV-T39	Verify implementation of Generate Photometric Zeropoint for Visit Image

Rubin Observatory

Test Id	Test Name
LVV-T40	Verify implementation of Generate WCS for Visit Images
LVV-T41	Verify implementation of Generate PSF for Visit Images
LVV-T42	Verify implementation of Processed Visit Image Content
LVV-T43	Verify implementation of Background Model Calculation
LVV-T44	Verify implementation of Documenting Image Characterization
LVV-T45	Verify implementation of Prompt Processing Data Quality Report Definition
LVV-T46	Verify implementation of Prompt Processing Performance Report Definition
LVV-T47	Verify implementation of Prompt Processing Calibration Report Definition
LVV-T48	Verify implementation of Exposure Catalog
LVV-T49	Verify implementation of DIASource Catalog
LVV-T50	Verify implementation of Faint DIASource Measurements
LVV-T51	Verify implementation of DIAObject Catalog
LVV-T52	Verify implementation of DIAObject Attributes
LVV-T53	Verify implementation of SSObject Catalog
LVV-T54	Verify implementation of Alert Content
LVV-T55	Verify implementation of DIAForcedSource Catalog
LVV-T56	Verify implementation of Characterizing Variability
LVV-T57	Verify implementation of Calculating SSObject Parameters
LVV-T58	Verify implementation of Matching DIASources to Objects
LVV-T59	Verify implementation of Regenerating L1 Data Products During Data Release Processing
LVV-T60	Verify implementation of Publishing predicted visit schedule
LVV-T61	Verify implementation of Associate Sources to Objects
LVV-T62	Verify implementation of Provide PSF for Coadded Images
LVV-T63	Verify implementation of Produce Images for EPO
LVV-T64	Verify implementation of Coadded Image Provenance
LVV-T65	Verify implementation of Source Catalog
LVV-T66	Verify implementation of Forced-Source Catalog
LVV-T67	Verify implementation of Object Catalog
LVV-T68	Verify implementation of Provide Photometric Redshifts of Galaxies

Rubin Observatory

Test Id	Test Name
LVV-T69	Verify implementation of Object Characterization
LVV-T71	Verify implementation of Detecting extended low surface brightness objects
LVV-T72	Verify implementation of Coadd Image Method Constraints
LVV-T73	Verify implementation of Deep Detection Coadds
LVV-T74	Verify implementation of Template Coadds
LVV-T75	Verify implementation of Multi-band Coadds
LVV-T76	Verify implementation of All-Sky Visualization of Data Releases
LVV-T77	Verify implementation of Best Seeing Coadds
LVV-T78	Verify implementation of Persisting Data Products
LVV-T79	Verify implementation of PSF-Matched Coadds
LVV-T80	Verify implementation of Detecting faint variable objects
LVV-T81	Verify implementation of Targeted Coadds
LVV-T82	Verify implementation of Tracking Characterization Changes Between Data Releases
LVV-T83	Verify implementation of Bad Pixel Map
LVV-T84	Verify implementation of Bias Residual Image
LVV-T85	Verify implementation of Crosstalk Correction Matrix
LVV-T86	Verify implementation of Illumination Correction Frame
LVV-T87	Verify implementation of Monochromatic Flatfield Data Cube
LVV-T88	Verify implementation of Calibration Data Products
LVV-T89	Verify implementation of Calibration Image Provenance
LVV-T90	Verify implementation of Dark Current Correction Frame
LVV-T91	Verify implementation of Fringe Correction Frame
LVV-T92	Verify implementation of Processing of Data From Special Programs
LVV-T93	Verify implementation of Level 1 Processing of Special Programs Data
LVV-T94	Verify implementation of Special Programs Database
LVV-T95	Verify implementation of Constraints on Level 1 Special Program Products Generation
LVV-T96	Verify implementation of Query Repeatability
LVV-T97	Verify implementation of Uniqueness of IDs Across Data Releases
LVV-T98	Verify implementation of Selection of Datasets
LVV-T99	Verify implementation of Processing of Datasets
LVV-T100	Verify implementation of Transparent Data Access

Rubin Observatory

Test Id	Test Name
LVV-T101	Verify implementation of Transient Alert Distribution
LVV-T102	Verify implementation of Solar System Objects Available Within Specified Time
LVV-T103	Verify implementation of Generate Data Quality Report Within Specified Time
LVV-T104	Verify implementation of Generate DMS Performance Report Within Specified Time
LVV-T105	Verify implementation of Generate Calibration Report Within Specified Time
LVV-T106	Verify implementation of Calibration Images Available Within Specified Time
LVV-T107	Verify implementation of Level-1 Production Completeness
LVV-T108	Verify implementation of Level 1 Source Association
LVV-T109	Verify implementation of SSObject Precovery
LVV-T110	Verify implementation of DIASource Precovery
LVV-T111	Verify implementation of Use of External Orbit Catalogs
LVV-T112	Verify implementation of Alert Filtering Service
LVV-T113	Verify implementation of Performance Requirements for LSST Alert Filtering Service
LVV-T114	Verify implementation of Pre-defined alert filters
LVV-T115	Verify implementation of Calibration Production Processing
LVV-T116	Verify implementation of Associating Objects across data releases
LVV-T117	Verify implementation of DAC resource allocation for Level 3 processing
LVV-T118	Verify implementation of Level 3 Data Product Self Consistency
LVV-T119	Verify implementation of Provenance for Level 3 processing at DACs
LVV-T120	Verify implementation of Software framework for Level 3 catalog processing
LVV-T121	Verify implementation of Software framework for Level 3 image processing
LVV-T122	Verify implementation of Level 3 Data Import
LVV-T123	Verify implementation of Access Controls of Level 3 Data Products
LVV-T124	Verify implementation of Software Architecture to Enable Community Re-Use
LVV-T125	Verify implementation of Simulated Data

Test Id	Test Name
LVV-T126	Verify implementation of Image Differencing
LVV-T127	Verify implementation of Provide Source Detection Software
LVV-T128	Verify implementation Provide Astrometric Model
LVV-T129	Verify implementation of Provide Calibrated Photometry
LVV-T130	Verify implementation of Enable a Range of Shape Measurement Approaches
LVV-T131	Verify implementation of Provide User Interface Services
LVV-T132	Verify implementation of Pre-cursor and Real Data
LVV-T133	Verify implementation of Provide Beam Projector Coordinate Calculation Software
LVV-T134	Verify implementation of Provide Image Access Services
LVV-T136	Verify implementation of Data Product and Raw Data Access
LVV-T137	Verify implementation of Data Product Ingest
LVV-T138	Verify implementation of Bulk Download Service
LVV-T140	Verify implementation of Production Orchestration
LVV-T141	Verify implementation of Production Monitoring
LVV-T142	Verify implementation of Production Fault Tolerance
LVV-T144	Verify implementation of Task Specification
LVV-T145	Verify implementation of Task Configuration
LVV-T146	Verify implementation of DMS Initialization Component
LVV-T147	Verify implementation of Control of Level-1 Production
LVV-T148	Verify implementation of Unique Processing Coverage
LVV-T149	Verify implementation of Catalog Queries
LVV-T150	Verify implementation of Maintain Archive Publicly Accessible
LVV-T151	Verify Implementation of Catalog Export Formats From the Notebook Aspect
LVV-T152	Verify implementation of Keep Historical Alert Archive
LVV-T153	Verify implementation of Provide Engineering and Facility Database Archive
LVV-T154	Verify implementation of Raw Data Archiving Reliability
LVV-T155	Verify implementation of Un-Archived Data Product Cache
LVV-T156	Verify implementation of Regenerate Un-archived Data Products
LVV-T157	Verify implementation Level 1 Data Product Access
LVV-T158	Verify implementation Level 1 and 2 Catalog Access

Rubin Observatory

Test Id	Test Name
LVV-T159	Verify implementation of Regenerating Data Products from Previous Data Releases
LVV-T160	Verify implementation of Providing a Precovery Service
LVV-T161	Verify implementation of Logging of catalog queries
LVV-T162	Verify implementation of Access to Previous Data Releases
LVV-T163	Verify implementation of Data Access Services
LVV-T164	Verify implementation of Operations Subsets
LVV-T165	Verify implementation of Subsets Support
LVV-T166	Verify implementation of Access Services Performance
LVV-T167	Verify Capability to serve older Data Releases at Full Performance
LVV-T168	Verify design of Data Access Services allows Evolution of the LSST Data Model
LVV-T169	Verify implementation of Older Release Behavior
LVV-T170	Verify implementation of Query Availability
LVV-T171	Verify implementation of Pipeline Availability
LVV-T172	Verify implementation of Optimization of Cost, Reliability and Availability
LVV-T173	Verify implementation of Pipeline Throughput
LVV-T174	Verify implementation of Re-processing Capacity
LVV-T175	Verify implementation of Temporary Storage for Communications Links
LVV-T176	Verify implementation of Infrastructure Sizing for "catching up"
LVV-T177	Verify implementation of Incorporate Fault-Tolerance
LVV-T178	Verify implementation of Incorporate Autonomics
LVV-T179	Verify implementation of Compute Platform Heterogeneity
LVV-T180	Verify implementation of Data Management Unscheduled Downtime
LVV-T181	Verify Base Voice Over IP (VOIP)
LVV-T182	Verify implementation of Prefer Computing and Storage Down
LVV-T183	Verify implementation of DMS Communication with OCS
LVV-T185	Verify implementation of Summit to Base Network Availability
LVV-T186	Verify implementation of Summit to Base Network Reliability
LVV-T187	Verify implementation of Summit to Base Network Secondary Link
LVV-T188	Verify implementation of Summit to Base Network Ownership and Operation
LVV-T189	Verify implementation of Base Facility Infrastructure
LVV-T190	Verify implementation of Base Facility Co-Location with Existing Facility

Rubin Observatory

Test Id	Test Name
LVV-T191	Verify implementation of Commissioning Cluster
LVV-T192	Verify implementation of Base Wireless LAN (WiFi)
LVV-T193	Verify implementation of Base to Archive Network
LVV-T194	Verify implementation of Base to Archive Network Availability
LVV-T195	Verify implementation of Base to Archive Network Reliability
LVV-T196	Verify implementation of Base to Archive Network Secondary Link
LVV-T197	Verify implementation of Archive Center
LVV-T198	Verify implementation of Archive Center Disaster Recovery
LVV-T199	Verify implementation of Archive Center Co-Location with Existing Facility
LVV-T200	Verify implementation of Archive to Data Access Center Network
LVV-T201	Verify implementation of Archive to Data Access Center Network Availability
LVV-T202	Verify implementation of Archive to Data Access Center Network Reliability
LVV-T203	Verify implementation of Archive to Data Access Center Network Secondary Link
LVV-T204	Verify implementation of Access to catalogs for external Level 3 processing
LVV-T205	Verify implementation of Access to input catalogs for DAC-based Level 3 processing
LVV-T206	Verify implementation of Federation with external catalogs
LVV-T207	Verify implementation of Access to images for external Level 3 processing
LVV-T208	Verify implementation of Access to input images for DAC-based Level 3 processing
LVV-T209	Verify implementation of Data Access Centers
LVV-T210	Verify implementation of Data Access Center Simultaneous Connections
LVV-T211	Verify implementation of Data Access Center Geographical Distribution
LVV-T212	Verify implementation of No Limit on Data Access Centers
LVV-T216	Installation of the Alert Distribution payloads.
LVV-T217	Full Stream Alert Distribution
LVV-T218	Simple Filtering of the LSST Alert Stream
LVV-T283	RAS-00-00: Writing well-formed raw image
LVV-T284	RAS-00-05: (LDM-503-8b) Writing data from CCOB to the DBB for further data processing

Test Id	Test Name
LVV-T285	RAS-00-10: Raw images in Observatory Operations Data Service
LVV-T286	RAS-00-20: Raw image are part of the permanent record of survey via DBB
LVV-T287	RAS-00-30: Raw Image Archiving Availability, Throughput, Reliability, and Heterogeneity
LVV-T362	Installation of the LSST Science Pipelines Payloads
LVV-T363	Science Pipelines Release Documentation
LVV-T368	Loading and processing Camera test data
LVV-T374	Ingesting Camera test data
LVV-T376	Verify the Calculation of Ellipticity Residuals and Correlations
LVV-T377	Verify Calculation of Photometric Performance Metrics
LVV-T378	Verify Calculation of Astrometric Performance Metrics
LVV-T385	Verify implementation of minimum number of simultaneous retrievals of CCD-sized coadd cutouts
LVV-T454	LDM-503-8 Enable LSP viewing of spectrograph data.
LVV-T1085	Short Queries Functional Test
LVV-T1086	Full Table Scans Functional Test
LVV-T1087	Full Table Joins Functional Test
LVV-T1088	Concurrent Scans Scaling Test
LVV-T1089	Load Test
LVV-T1090	Heavy Load Test
LVV-T1097	Verify Summit Facility Network Implementation
LVV-T1168	Verify Summit - Base Network Integration
LVV-T1232	Verify Implementation of Catalog Export Formats From the Portal Aspect
LVV-T1240	Verify implementation of minimum astrometric standards per CCD
LVV-T1250	Verify implementation of minimum number of simultaneous DM EFD query users
LVV-T1251	Verify implementation of maximum time to retrieve DM EFD query results
LVV-T1252	Verify number of simultaneous alert filter users
LVV-T1264	Verify implementation of archiving camera test data
LVV-T1276	Verify implementation of latency of reporting optical transients
LVV-T1277	Verify processing of maximum number of calibration exposures
LVV-T1332	Verify implementation of maximum time for retrieval of CCD-sized coadd cutouts
LVV-T1524	Verify Implementation of Exporting MOCs as FITS

Rubin Observatory

Test Id	Test Name
LVV-T1525	Verify Implementation of Linkage Between HiPS Maps and Coadded Images
LVV-T1526	Verify Availability of Secure and Authenticated HiPS Service
LVV-T1527	Verify Support for HiPS Visualization
LVV-T1528	Verify Visualization of MOCs via Science Platform
LVV-T1529	Verify Production of All-Sky HiPS Map
LVV-T1530	Verify Production of Multi-Order Coverage Maps for Survey Data
LVV-T1549	LDM-503-6 Comcam verification readiness
LVV-T1550	LDM-503-10 DAQ Validation
LVV-T1556	LDM-503-10B Large Scale CCOB Data Access
LVV-T1560	Verify archiving of processing provenance
LVV-T1561	Verify provenance availability to science users
LVV-T1562	Verify availability of re-run tools
LVV-T1563	Verify re-run on different system produces the same results
LVV-T1564	Verify re-run on similar system produces the same results
LVV-T1612	Verify Summit - Base Network Integration (System Level)
LVV-T1745	Verify calculation of median relative astrometric measurement error on 20 arcminute scales
LVV-T1746	Verify calculation of fraction of relative astrometric measurement error on 5 arcminute scales exceeding outlier limit
LVV-T1747	Verify calculation of relative astrometric measurement error on 5 arcminute scales
LVV-T1748	Verify calculation of median error in absolute position for RA, Dec axes
LVV-T1749	Verify calculation of fraction of relative astrometric measurement error on 20 arcminute scales exceeding outlier limit
LVV-T1750	Verify calculation of separations relative to r-band exceeding color difference outlier limit
LVV-T1751	Verify calculation of median relative astrometric measurement error on 200 arcminute scales
LVV-T1752	Verify calculation of fraction of relative astrometric measurement error on 200 arcminute scales exceeding outlier limit
LVV-T1753	Verify calculation of RMS difference of separations relative to r-band
LVV-T1754	Verify calculation of residual PSF ellipticity correlations for separations less than 5 arcmin

Rubin Observatory

Test Id	Test Name
LVV-T1755	Verify calculation of residual PSF ellipticity correlations for separations less than 1 arcmin
LVV-T1756	Verify calculation of photometric repeatability in uzy filters
LVV-T1757	Verify calculation of photometric repeatability in gri filters
LVV-T1758	Verify calculation of photometric outliers in uzy bands
LVV-T1759	Verify calculation of photometric outliers in gri bands
LVV-T1830	Verify Implementation of Scientific Visualization of Camera Image Data
LVV-T1831	Verify Implementation of Data Management Nightly Reporting
LVV-T1836	Verify calculation of resolved-to-unresolved flux ratio errors
LVV-T1837	Verify calculation of band-to-band color zero-point accuracy
LVV-T1838	Verify calculation of image fraction affected by ghosts
LVV-T1839	Verify calculation of RMS width of photometric zeropoint
LVV-T1840	Verify calculation of sky brightness precision
LVV-T1841	Verify calculation of scientifically unusable pixel fraction
LVV-T1842	Verify calculation of zeropoint error fraction exceeding the outlier limit
LVV-T1843	Verify calculation of significance of imperfect crosstalk corrections
LVV-T1844	Verify calculation of u-band photometric zero-point RMS
LVV-T1845	Verify accuracy of photometric transformation to physical scale
LVV-T1846	Verify calculation of band-to-band color zero-point accuracy including u-band
LVV-T1847	Verify calculation of sensor fraction with unusable pixels
LVV-T1862	Verify determining effectiveness of dark current frame
LVV-T1863	Verify ability to process Special Programs data alongside normal processing
LVV-T1865	Verify implementation of time to L1 public release for Special Programs
LVV-T1866	Verify latency of reporting optical transients from Special Programs
LVV-T1867	Verify implementation of at least numStreams alert streams supported
LVV-T1868	Verify implementation of alert streams distributed within latency limit
LVV-T1946	Verify implementation of measurements in catalogs from coadds
LVV-T1947	Verify implementation of measurements in catalogs from difference images

Rubin Observatory

4   Active Test Cases

This section documents all active test cases that have a status in the Jira/ATM system of Draft, Defined or Approved.

4.1   LVV-T10 - DRP-00-00: Installation of the Data Release Production v14.0 science payload

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T10 in Jira

4.1.1   Verification Elements

- LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

4.1.2   Test Items

This test will check:

- That the Data Release Production science payload is available for distribution from documented channels;
- That the Data Release Production science payload can be installed on LSST Data Facility-managed systems.

4.1.3   Predecessors

4.1.4   Environment Needs

4.1.4.1   Software   All prerequisite packages listed at https://pipelines.lsst.io/install/ prereqs/-centos.html must be available on the test system and on the LSST-VC compute node.

Rubin Observatory

4.1.4.2   Hardware   This test case shall be executed on a developer system at the LSST Data Facility which serves as the "head node" or otherwise provides access to filesystems shared by the LSST Verification Cluster (LSST-VC). We assume that this system will be lsst-dev01.ncsa.illinois.edu and the filesystem will be a GPFS-based system mounted at /software. The test also requires access to one LSST-VC compute node.

4.1.5   Input Specification

No input data is required for this test case.

4.1.6   Output Specification

The Data Release Production science payload will be made available on a shared filesystem accessible from LSST-VC compute notes.

4.1.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Release 14.0 of the LSST Science Pipelines will be installed into the GPFS filesystem accessible at /software on lsst-dev01 following the instructions at https://pipelines.lsst. io/install/newinstall.html.
	Test Data	No data.
	Expected Result	
2	Description	The lsst_distrib top level package will be enabled: source /software/lsstsw/stack3/loadLSST.bash setup lsst_distrib
	Test Data	No data.
	Expected Result	
3	Description	The "LSST Stack Demo" package will be downloaded onto the test system from https://github.com/lsst/lsst_dm_stack_demo/releases/tag/14.0 and uncompressed.
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

18

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	The demo package will be executed by following the instructions in its "README" file. The string "Ok." should be returned.
	Test Data	No data.
	Expected Result	
5	Description	A shell on an LSST-VC compute node will now be obtained by executing: $ srun -l –pty bash
	Test Data	No data.
	Expected Result	
6	Description	The demo package will be executed on the compute node and the same result obtained.
	Test Data	No data.
	Expected Result	

4.2 LVV-T11 - DRP-00-05: Execution of the DRP Science Payload by the Batch Production Service

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T11 in Jira

4.2.1 Verification Elements

- LVV-46 - DMS-REQ-0106-V-01: Coadded Image Provenance

- LVV-124 - DMS-REQ-0293-V-01: Selection of Datasets

- LVV-134 - DMS-REQ-0303-V-01: Production Monitoring

- LVV-133 - DMS-REQ-0302-V-01: Production Orchestration

- LVV-136 - DMS-REQ-0305-V-01: Task Specification

- LVV-137 - DMS-REQ-0306-V-01: Task Configuration

Rubin Observatory

- LVV-62 - DMS-REQ-0158-V-01: Provide Pipeline Construction Services

4.2.2   Test Items

This test will check that the DRP Science Payload can be executed using a specific version of the Batch Production Service provided by the LSST Data Facility. Since the outputs are stored in the Data Backbone, it too is a component of this test.

4.2.3   Predecessors

LVV-T10 (DRP-00-00)

4.2.4   Environment Needs

4.2.4.1   Software   All the necessary software will be pre-installed. The software includes the science pipeline codes as well as the Data Management system codes (Batch Processing Service, Data Backbone).

For LDM-503-2, Python 2 versions of software will be used. The science pipeline codes will be provided via the LSST DM Software Stack, release 14.0. The Batch Processing Service and the Data Backbone are initial versions using the DESDM Framework packages. LSST-specific plugins as well as DRP pipeline integration codes are also pre-installed. All python DESDM Framework packages, plugins and integration codes exist in the lsst-dm github with tag 1.01. The DESDM prerequisites come from the official DESDM eups package firstcut Y4N+5. They are installed using DESDMâ€™s eups install process.

The ticket branch tickets/DM-12291 of the LSST Software Stack packages meas_base, pipe_tasks, and obs_subaru will be used to change the patch ID naming convention. This is due to issues of having commas in the filenames and data IDs, as discussed in RFC-361; the solution has been agreed in RFC-365 for future implementation in DM-11874, DM-11875, and DM-11876. For LDM-503-2, the software will be installed into the GPFS space at /project/production/ on LSST-VC. A single eups prototype package will be defined to encompass the above mentioned software.

4.2.4.2   Hardware   This test case shall be executed on a testbed at the LSST Data Facility. For LDM-503-2, this testbed includes:

Rubin Observatory

- LSST Verification Cluster (LSST-VC) with Slurm Job Scheduler
- Submit and compute nodes with read/write access to various GPFS shared filesystems:

    1. Filesystem containing the software stack
    2. Filesystem for the submit side temporary outputs
    3. Filesystem being used by the prototype DataBackbone.(This means that the framework can use a cp transfer protocol between the job and the Data Backbone and does not require additional transfer services to be running.)
    4. Filesystem for the individual job scratch directories.

- Single node Oracle database (version 12c)
- Submit node (lsst-dev01.ncsa.illinois.edu) running the HTCondor Central Manager (version 8.7.3).

4.2.5 Input Specification

A small number of selected tracts of the Hyper Suprime-Cam dataset will be used along with appropriate calibration datasets.
For LDM-503-2, the three tracts of the Hyper Suprime-Cam "RC1" dataset, as defined Appendix A.1.1, will be used. The calibration dataset will be the 20170105 version, defined as per DMTR-31. Raw files known to fail processCcd will be blacklisted.

4.2.6 Output Specification

The output data products will be available from the Data Backbone.
For LDM-503-2, the output data products will be available on the LSST-VC via a shared filesystem and advanced data discovery is done via SQL queries against the Oracle database.

4.2.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Setup. The LSST Science Pipelines and the DESDM Framework, plugins, and integration codes as described in Environment - Software paragraph have already been installed. The Operator merely sets up the expanded stack using eups.
	Test Data	No data.
	Expected Result	
2	Description	Input raw and calibration data must exist in the Data Backbone. If not, the data will be ingested into Data Backbone.
	Test Data	No data.
	Expected Result	
3	Description	The operator tags and blacklists input data as appropriate for test (see Input Specifications 4.2.5).
	Test Data	No data.
	Expected Result	
4	Description	Given the LSST Science Pipelines version, the operator will generate the full config files and schema files (Test Configuration 4.2.7), which are then ingested into the Data Backbone.
	Test Data	No data.
	Expected Result	
5	Description	Write a DRP pipeline workflow definition file from scratch or modify an existing file from github making its operations- and dataset-specific inputs match this test. • (a) For LDM-503-2, the pipeline workflow definition file is written in a workflow control language (wcl) format as used by the DESDM Framework.
	Test Data	No data.
	Expected Result	
6	Description	Make special hardware requests (e.g., disk or compute node reservations) if needed.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
7	Description	Execution starts. If HTCondor processes are not already running, start HTCondor processes on compute nodes. This step makes the compute nodes join the HTCondor Central Manager to cre- ate a working HTCondor Pool.
	Test Data	No data.
	Expected Result	
8	Description	The execution for each tract of the input data in the Input specification section (□□4.2.5) will be submitted to the hardware specified in "Environmental Needs - Hardware" section (□□4.2.4.1) using the configuration specified in "Test configuration" section (□□4.2.7).
	Test Data	No data.
	Expected Result	
9	Description	During execution, the operator will use software to demonstrate the ability to check the processing status. • (a) ForLDM-503-2,the available Batch Production Service monitoring software consists of two commands: one to summarize currently submitted processing, one to get more details of single submission.
	Test Data	No data.
	Expected Result	
10	Description	If the processing attempt completes, the attempt is marked as completed and tagged as potential for the next test steps. These campaign tags are used to make pre-release QA queries simpler.
	Test Data	No data.
	Expected Result	
11	Description	If the processing attempt fails, the attempt is marked as failed.
	Test Data	No data.
	Expected Result	
12	Description	If the processing attempt fails due to certain infrastructure configuration or transient instability (e.g., network blips), the processing of the tract can be tried again after the problem is resolved.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
13	Description	Checks. When the execution finishes, the success of the execution will be verified by checking the existence of the expected output data. • (a) For each of the expected data products types (listed in 4.3.2) and each of the expected units (visits, patches, etc), verify the data product is in the Data Backbone and has filesize greater than zero via DB queries. • (b) Verify the physical and location information in Data Backbone DB matches the Data Backbone filesystem and vice-versa.
	Test Data	No data.
	Expected Result	
14	Description	Check that for each data product type has appropriate metadata saved for each file as defined in "Test Configuration" section (4.2.7).
	Test Data	No data.
	Expected Result	
15	Description	Check provenance • (a) Verify that each file can be linked with the step and processing attempt that created it via the Data Backbone. • (b) Verify that the information linking input files to each step was saved to the Oracle database.
	Test Data	No data.
	Expected Result	
16	Description	Check runtime metrics, such as the number of executions of each code, wallclock per step, wallclock per tract, etc.
	Test Data	No data.
	Expected Result	

4.3   LVV-T12 - DRP-00-10: Data Release Includes Required Data Products

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T12 in Jira

4.3.1 Verification Elements

- LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

- LVV-98 - DMS-REQ-0267-V-01: Source Catalog

- LVV-99 - DMS-REQ-0268-V-01: Forced-Source Catalog

- LVV-106 - DMS-REQ-0275-V-01: Object Catalog

- LVV-110 - DMS-REQ-0279-V-01: Deep Detection Coadds

- LVV-125 - DMS-REQ-0294-V-01: Processing of Datasets

4.3.2 Test Items

This test will check that the basic data products which should be in an data release are generated by execution of the science payload.
These products will include:

- Source catalogs, derived from PVIs and coadded images (DMS-REQ-0267 & DMS-REQ-0277);
- Forced source catalogs (DMS-REQ-0268);
- Object catalogs (DMS-REQ-0275);
- Processed visit images (PVIs; DMS-REQ-0069);
- Coadded images (DMS-REQ-0279);

4.3.3 Predecessors

LVV-T10 (DRP-00-00)

4.3.4   Environment Needs

4.3.4.1   Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in DRP-00-00)

4.3.4.2   Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.3.5   Input Specification

A complete processing of the Hyper Suprime-Cam "RC1" dataset (Appendix A.1.1 through the DRP Science Payload.

This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.3.6   Output Specification

None.

4.3.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in DRP-00-00).
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	For each of the expected data products types (listed in Test Items section ⬜⬜4.3.2) and each of the expected units (PVIs, coadds, etc), the data product will be retrieved from the Butler and verified to be non-empty.
	Test Data	No data.
	Expected Result	

4.4   LVV-T13 - DRP-00-15: Scientific Verification of Source Catalog

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T13 in Jira

4.4.1   Verification Elements

- LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

- LVV-98 - DMS-REQ-0267-V-01: Source Catalog

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

- LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities

4.4.2   Test Items

This test will check that the source catalogs delivered by the DRP science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Measurements in the catalog are presented in flux units (DMS-REQ-0347);

Rubin Observatory

- Derived quantities are provided in pre-computed columns (DMS-REQ-0331);
- Aperture corrections for different photometry algorithms are consistent.
- Photometry measurements are consistent with reference catalog photometry (including sources not used in photometric calibration).
- Astrometry measurements are consistent with reference catalog positions (including sources not used in astrometric calibration).

This test does not include quantitative targets for the science quality criteria; we instead require for each test that we be able to quickly construct a plot in which such a target can be visualized.

4.4.3 Predecessors

lvv-t10 (DRP-00-00), lvv-t12 (DRP-00-10)

4.4.4 Environment Needs

4.4.4.1 Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in DRP-00-00).

4.4.4.2 Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.4.5 Input Specification

A complete processing of the Hyper Suprime-Cam "RC1" dataset (Appendix A.1.1 through the DRP Science Payload.

This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

Rubin Observatory

4.4.6 Output Specification

None.

4.4.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T10 - DRP-00-00).
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	Scripts from the pipe_analysis package will be run on every visit to check for the presence of data products and make plots.
	Test Data	No data.
	Expected Result	

4.5 LVV-T14 - DRP-00-25: Scientific Verification of Object Catalog

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T14 in Jira

4.5.1 Verification Elements

• LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

• LVV-106 - DMS-REQ-0275-V-01: Object Catalog

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

- LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities

4.5.2 Test Items

This test will check that the object catalogs delivered by the DRP science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Measurements in the catalog are presented in flux units (DMS-REQ-0347);
- Derived quantities are provided in pre-computed columns (DMS-REQ-0331);
- Aperture corrections for different photometry algorithms are consistent.
- PSF models correctly predict the ellipticities of stars over each tract.
- Photometry measurements are consistent with reference catalog photometry (including sources not used in photometric calibration).
- Astrometry measurements are consistent with reference catalog positions (including sources not used in astrometric calibration).
- Forced and unforced photometry measurements are consistent.
- The slope of the stellar locus in color-color space is not a function of position on the sky.

This test does not include quantitative targets for the science quality criteria; we instead require for each test that we be able to quickly construct a plot in which such a target can be visualized.
All science quality tests in this section shall distinguish between blended and isolated objects.

4.5.3 Predecessors

LVV-T10 (DRP-00-00)
LVV-T12 (DRP-00-10)

4.5.4 Environment Needs

4.5.4.1 Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in DRP-00-00).

Rubin Observatory

4.5.4.2   Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.5.5   Input Specification

A complete processing of the Hyper Suprime-Cam "RC1" dataset (Appendix A.1.1 through the DRP Science Payload.

This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.5.6   Output Specification

None.

4.5.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T10 - DRP-00-00).
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	Scripts from the pipe_analysis package will be run on every tract to check for the presence of data products and make plots
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.6   LVV-T15 - DRP-00-30: Scientific Verification of Processed Visit Images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T15 in Jira

4.6.1   Verification Elements

- LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

- LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images

- LVV-158 - DMS-REQ-0327-V-01: Background Model Calculation

- LVV-12 - DMS-REQ-0029-V-01: Generate Photometric Zeropoint for Visit Image

- LVV-30 - DMS-REQ-0070-V-01: Generate PSF for Visit Images

- LVV-13 - DMS-REQ-0030-V-01: Absolute accuracy of WCS

- LVV-31 - DMS-REQ-0072-V-01: Processed Visit Image Content

4.6.2   Test Items

This test will check that the Processed Visit Images (PVIs) delivered by the DRP science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Processed visit images have been generated and persisted during payload execution;
- Each PVI includes a background model (DMS-REQ-0327), photometric zero-point (DMS-REQ-0029), spatially-varying PSF (DMS-REQ-0070) and WCS (DMS-REQ-0030).
- Saturated pixels are correctly masked.
- Pixels affected by cosmic rays are correctly masked.
- The background is not oversubtracted around bright objects.

Rubin Observatory

This test does not include quantitative targets for the science quality criteria; we instead require for each test that we be able to quickly construct a plot or display summary images that allow such a target can be visualized.

4.6.3 Predecessors

LVV-T10
LVV-T12

4.6.4 Environment Needs

4.6.4.1 Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in DRP-00-00).

4.6.4.2 Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.6.5 Input Specification

A complete processing of the Hyper Suprime-Cam "RC1" dataset (Appendix A.1.1 through the DRP Science Payload.
This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".
It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.6.6 Output Specification

None.

Rubin Observatory

4.6.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T10 - DRP-00-00).
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	For each processed CCD, the PVI will be retrieved from the Butler, and the existence of all components described in section Test Items (⬜4.6.2) will be verified.
	Test Data	No data.
	Expected Result	
4	Description	Scripts from the pipe_analysis package will be run on every visit to check for the presence of data products and make plots
	Test Data	No data.
	Expected Result	
5	Description	Five sensors will be chosen at random from each of two visits and inspected by eye for unmasked artifacts.
	Test Data	No data.
	Expected Result	

4.7 LVV-T16 - DRP-00-35: Scientific Verification of Coadd Images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T16 in Jira

4.7.1 Verification Elements

- LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

- LVV-110 - DMS-REQ-0279-V-01: Deep Detection Coadds

- LVV-109 - DMS-REQ-0278-V-01: Coadd Image Method Constraints

- LVV-20 - DMS-REQ-0047-V-01: Provide PSF for Coadded Images

4.7.2 Test Items

This test will check that the coadded images delivered by the DRP science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Coadds have been generated and persisted during payload execution;
- Each coadd provides a spatially varying PSF model (DMS-REQ-0047).
- Saturated pixels are correctly masked.
- Pixels affected by satellite trails and ghosts are rejected from the coadd.
- The background is not oversubtracted around bright objects.

This test does not include quantitative targets for the science quality criteria; we instead require for each test that we be able to quickly construct a plot or display summary images that allow such a target can be visualized.

4.7.3 Predecessors

LVV-T10 (DRP-00-00)
LVV-T12 (DRP-00-10)

Rubin Observatory

4.7.4   Environment Needs

4.7.4.1   Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in DRP-00-00).

4.7.4.2   Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.7.5   Input Specification

A complete processing of the Hyper Suprime-Cam "RC1" dataset (Appendix A.1.1 through the DRP Science Payload.

This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.7.6   Output Specification

None.

4.7.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T10 - DRP-00-00)
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	For each combination of tract/patch/filter, the PVI will be retrieved from the Butler, and the existence of all components described in Test items section 4.6.2 will be verified.
	Test Data	No data.
	Expected Result	
4	Description	Scripts from the pipe_analysis package will be run on every visit to check for the presence of data products and make plots
	Test Data	No data.
	Expected Result	
5	Description	Ten patches will be chosen at random and inspected by eye for unmasked artifacts.
	Test Data	No data.
	Expected Result	

4.8 LVV-T17 - AG-00-00: Installation of the Alert Generation v16.0 science payload.

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T17 in Jira

4.8.1 Verification Elements

• LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

4.8.2 Test Items

This test will check:

Rubin Observatory

- That the Alert Generation science payload is available for distribution from documented channels;
- That the Alert Generation science payload can be installed on LSST Data Facility-managed systems.

4.8.3   Predecessors

None.

4.8.4   Environment Needs

4.8.4.1   Software   All prerequisite packages listed at https://pipelines.lsst.io/install/prereqs/centos.html must be available on the test system and on the LSST-VC compute node.

4.8.4.2   Hardware   This test case shall be executed on a developer system at NCSA which serves as the "head node" or otherwise provides access to filesystems shared by the LSST Verification Cluster (LSST-VC). We assume that this system will be lsst-dev01.ncsa.illinois.edu and the filesystem will be a GPFS-based system mounted at /software.
The test also requires access to one LSST-VC compute node.

4.8.5   Input Specification

No input data is required for this test case.

4.8.6   Output Specification

The Alert Generation science payload will be made available on a shared filesystem accessible from LSST-VC compute notes.

4.8.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Release 16.0 of the LSST Science Pipelines will be installed into the GPFS filesystem accessible at /software on lsst-dev01 following the instructions at `https://pipelines.lsst.io/install/newinstall.html` .
	Test Data	No data.
	Expected Result	
2	Description	The lsst_distrib top level package will be enabled: source /software/lsstsw/stack3/loadLSST.bash setup lsst_distrib
	Test Data	No data.
	Expected Result	
3	Description	The "LSST Stack Demo" package will be downloaded onto the test system from https://github.com/lsst/lsst_dm_stack_demo/releases/tag/16.0 and uncompressed.
	Test Data	No data.
	Expected Result	
4	Description	The demo package will be executed by following the instructions in its "README" file. The string "Ok." should be returned. Specifically, we execute: setup obs_sdss ./bin/demo.sh python bin/compare expected/Linux64/detected-sources.txt
	Test Data	No data.
	Expected Result	
5	Description	A shell on an LSST-VC compute node will now be obtained by executing: $ srun -I –pty bash
	Test Data	No data.
	Expected Result	
6	Description	The demo package will be executed on the compute node and the same result obtained.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
7	Description	The Alert Production datasets and packages are not yet part of lsst_distrib and so must be installed separately. They will be installed as follows on the GPFS filesystem:

```
setup git_lfs
git clone https://github.com/lsst/ap_verify_hits2015.git


                export      AP_VERIFY_HITS2015_DIR=$PWD/ap_verify_hits2015        cd
$AP_VERIFY_HITS2015_DIR
setup -r .
cd-

setup obs_decam
git clone https://github.com/lsst-dm/ap_association
cd ap_association
setup -k -r .
scons
cd-

git clone https://github.com/lsst-dm/ap_pipe
cd ap_pipe
setup -k -r .
scons
cd-

git clone https://github.com/lsst-dm/ap_verify
cd ap_verify
setup -k -r .
scons
cd-
```

	and any errors or failures reported.	
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

40

Rubin Observatory

4.9   LVV-T18 - AG-00-05: Alert Generation Produces Required Data Products

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T18 in Jira

4.9.1   Verification Elements

- LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images

- LVV-7 - DMS-REQ-0010-V-01: Difference Exposures

- LVV-100 - DMS-REQ-0269-V-01: DIASource Catalog

- LVV-102 - DMS-REQ-0271-V-01: Max nearby galaxies associated with DIASource

4.9.2   Test Items

This test will check that the basic data products produced by Alert Generation are generated by execution of the science payload.
These products will include:

- Processed visit images (PVIs; DMS-REQ-0069);
- Difference Exposures (DMS-REQ-0010);
- DIASource catalogs (DMS-REQ-0269);
- DIAObject catalogs (DMS-REQ-0271);

4.9.3   Predecessors

LVV-T17 (AG-00-00)

4.9.4   Environment Needs

4.9.4.1   Software   Release 16.0 of the DM Software Stack will be pre-installed (following the procedure described in AG-00-00).

4.9.4.2 Hardware The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.9.5 Input Specification

A complete processing of the DECam "HiTS" dataset, as defined at https://dmtn-039.lsst.io/ and https://github.com/lsst/ap_verify_hits2015, through the Alert Generation science payload. This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.9.6 Output Specification

None.

4.9.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack and Alert Processing packaged shall be initialized as described in LVT-T17 (AG-00-00).
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

42

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	The alert generation processing will be executed using the verification cluster:
		```bash python ap_verify/bin/prepare_demo_slurm_files.py # At present we must run a single ccd+visit to handle ingestion before # parallel processing can begin ./ap_verify/bin/exec_demo_run_1ccd.sh 410915 25 ln -s ap_verify/bin/demo_run.sl ln -s ap_verify/bin/demo_cmds.conf sbatch demo_run.sl ```
		and any errors or failures reported.
	Test Data	No data.
	Expected Result	
3	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
4	Description	For each of the expected data products types (listed in 4.2.2) and each of the expected units (PVIs, catalogs, etc.), the data product will be retrieved from the Butler and verified to be non-empty.
	Test Data	No data.
	Expected Result	
5	Description	DIAObjects are currently only stored in a database, without shims to the Butler, so the existence of the database table and its non-empty contents will be verified by directly accessing it using sqlite3 and executing appropriate SQL queries.
	Test Data	No data.
	Expected Result	

4.10   LVV-T19 - AG-00-10: Scientific Verification of Processed Visit Images

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T19 in Jira

4.10.1   Verification Elements

- LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images

- LVV-158 - DMS-REQ-0327-V-01: Background Model Calculation

- LVV-12 - DMS-REQ-0029-V-01: Generate Photometric Zeropoint for Visit Image

- LVV-30 - DMS-REQ-0070-V-01: Generate PSF for Visit Images

- LVV-13 - DMS-REQ-0030-V-01: Absolute accuracy of WCS

- LVV-31 - DMS-REQ-0072-V-01: Processed Visit Image Content

4.10.2   Test Items

This test will check that the Processed Visit Images (PVIs) delivered by the alert generation science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Processed visit images have been generated and persisted during payload execution;
- Each PVI includes a science pixel array, a mask array, and a variance array. (DMS-REQ-0072).
- Each PVI includes a background model (DMS-REQ-0327), photometric zero-point (DMS-REQ-0029), spatially-varying PSF (DMS-REQ-0070) and WCS (DMS-REQ-0030).
- Saturated pixels are correctly masked.
- Pixels affected by cosmic rays are correctly masked.
- The background is not oversubtracted around bright objects.

This test does not include quantitative targets for the science quality criteria.

Rubin Observatory

4.10.3 Predecessors

LVT-T17 (AG-00-00)
LVT-T18 (AG-00-05)

4.10.4 Environment Needs

4.10.4.1 Software Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in AG-00-00).

4.10.4.2 Hardware The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.10.5 Input Specification

A complete processing of the DECam "HiTS" dataset, as defined at https://dmtn-039.lsst.io/ and https://github.com/lsst/ap_verify_hits2015, through the Alert Generation science payload. This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".
It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.10.6 Output Specification

None.

4.10.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T17 - AG-00-00).
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	For each processed CCD, the PVI will be retrieved from the Butler, and the existence of all components described in ☐☐4.3.2 will be verified.
	Test Data	No data.
	Expected Result	
4	Description	Five sensors will be chosen at random from each of two visits and inspected by eye for unmasked artifacts.
	Test Data	No data.
	Expected Result	

4.11   LVV-T20 - AG-00-15: Scientific Verification of Difference Images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T20 in Jira

4.11.1   Verification Elements

- LVV-7 - DMS-REQ-0010-V-01: Difference Exposures

- LVV-32 - DMS-REQ-0074-V-01: Difference Exposure Attributes

Rubin Observatory

4.11.2   Test Items

This test will check that the difference images delivered by the Alert Generation science pay-
load meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- Difference images have been generated and persisted during payload execution;
- Each difference image includes information about the identity of the input exposures,
  and metadata such as a representation of the PSF matching kernel (DMS-REQ-0074);
- Masks are correctly propagated from the input images.

This test does not include quantitative targets for the science quality criteria.

4.11.3   Predecessors

LVV-T17 (AG-00-00)
LVV-T18 (AG-00-05)

4.11.4   Environment Needs

4.11.4.1   Software   Release 14.0 of the DM Software Stack will be pre-installed (following
the procedure described in AG-00-00).

4.11.4.2   Hardware   The test shall be carried out on a machine with at least 16 GB of RAM
and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST
Data Facility.

4.11.5   Input Specification

A complete processing of the DECam "HiTS" dataset, as defined at https://dmtn-039.lsst. io/
and https://github.com/lsst/ap_verify_hits2015, through the Alert Generation science payload.
This dataset shall be made available in a standard LSST data repository, accessible via the
"Data Butler".

Rubin Observatory

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.11.6 Output Specification

None.

4.11.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T-17 AG-00-00).
	Test Data	No data.
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	For each processed CCD, the difference image will be retrieved from the Butler, and the existence of all components described in 4.4.2 will be verified.
	Test Data	No data.
	Expected Result	
4	Description	Five sensors will be chosen at random from each of two visits and the masks of the input and difference images compared by eye.
	Test Data	No data.
	Expected Result	

4.12 LVV-T21 - AG-00-20: Scientific Verification of DIASource Catalog

Version	Status	Priority	Verification Type	Owner

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

48

Rubin Observatory

1	Approved	Normal	Test	Eric Bellm

Open LVV-T21 in Jira

4.12.1 Verification Elements

- LVV-100 - DMS-REQ-0269-V-01: DIASource Catalog

- LVV-101 - DMS-REQ-0270-V-01: Faint DIASource Measurements

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

- LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities

- LVV-18 - DMS-REQ-0043-V-01: Provide Calibrated Photometry

4.12.2 Test Items

This test will check that the difference image source catalogs delivered by the Alert Generation science payload meet the requirements laid down by LSE-61.

- Specifically, this will demonstrate that:
- Measurements in the catalog are presented in flux units (DMS-REQ-0347);
- Each DIASource record contains an appropriate subset of the attributes required by DMS-REQ-0269. In particular, the LDM-503-3-era pipeline is expected to provide DIASource positions (sky and focal plane), fluxes, and flags indicative of issues encountered during processing.
- Faint DIASources satisfying additional criteria are stored (DMS-REQ-0270).
- Derived quantities are provided in pre-computed columns (DMS-REQ-0331);

This test does not include quantitative targets for the science quality criteria.

4.12.3   Predecessors

LVT-T17 (AG-00-00)
LVT-T18 (AG-00-05)

4.12.4   Environment Needs

4.12.4.1   Software   Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in AG-00-00).

4.12.4.2   Hardware   The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

4.12.5   Input Specification

A complete processing of the DECam "HiTS" dataset, as defined at https://dmtn-039.lsst. io/ and https://github.com/lsst/ap_verify_hits2015, through the Alert Generation science payload. This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".
It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.12.6   Output Specification

None.

4.12.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T17 - AG-00-00).
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	A "Data Butler" will be initialized to access the repository.
	Test Data	No data.
	Expected Result	
3	Description	DIASource records will be accessed by querying the Butler, then examined interactively at a Python prompt.
	Test Data	No data.
	Expected Result	

4.13   LVV-T22 - AG-00-25: Scientific Verification of DIAObject Catalog

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T22 in Jira

4.13.1   Verification Elements

- LVV-116 - DMS-REQ-0285-V-01: Level 1 Source Association

- LVV-102 - DMS-REQ-0271-V-01: Max nearby galaxies associated with DIASource

- LVV-103 - DMS-REQ-0272-V-01: DIAObject Attributes

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

- LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities

- LVV-18 - DMS-REQ-0043-V-01: Provide Calibrated Photometry

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

51

Rubin Observatory

4.13.2 Test Items

This test will check that the DIAObject catalogs delivered by the Alert Generation science payload meet the requirements laid down by LSE-61.
Specifically, this will demonstrate that:

- DIAObjects are recorded with unique identifiers (DMS-REQ-0271);
- Measurements in the catalog are presented in flux units (DMS-REQ-0347);
- EachDIAObjectrecordcontainscontainsanappropriatesetofsummaryattributes(DMS-REQ-0271 and DMS-REQ-0272). Note:
  - This test is executed independently of the Data Release Production system. Hence, DIAObjects are not associated to Objects, and the association metadata specified by DMS-REQ-0271 is not expected to be available.
  - TheLDM-503-3erapipelineisnotexpectedtocalculateorpersistallattributesspec- ified by DMS-REQ-0272 requirement.
- Relevant derived quantities are provided in pre-computed columns (DMS-REQ-0331);

This test does not include quantitative targets for the science quality criteria.

4.13.3 Predecessors

LVT-T17 (AG-00-00)
LVT-T18 (AG-00-05)

4.13.4 Environment Needs

4.13.4.1 Software Release 14.0 of the DM Software Stack will be pre-installed (following the procedure described in AG-00-00).

4.13.4.2 Hardware The test shall be carried out on a machine with at least 16 GB of RAM and multiple CPU cores which has access to the /datasets shared (GPFS) filesystem at the LSST Data Facility.

Rubin Observatory

4.13.5   Input Specification

A complete processing of the DECam "HiTS" dataset, as defined at https://dmtn-039.lsst. io/ and https://github.com/lsst/ap_verify_hits2015, through the Alert Generation science payload. This dataset shall be made available in a standard LSST data repository, accessible via the "Data Butler".

It is not required that all combinations of visit and CCD have been processed successfully: a number of failures are expected. However, documentation to describe processing failures should be provided.

4.13.6   Output Specification

None.

4.13.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The DM Stack shall be initialized using the loadLSST script (as described in LVV-T17 - AG-00-00).
	Test Data	No data.
	Expected Result	
2	Description	sqlite3 or Python's sqlalchemy module will be used to access the Level 1 database.
	Test Data	No data.
	Expected Result	

4.14   LVV-T23 - Verify implementation of Storing Approximations of Per-pixel Metadata

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T23 in Jira

4.14.1 Verification Elements

- LVV-157 - DMS-REQ-0326-V-01: Storing Approximations of Per-pixel Metadata

4.14.2 Test Items

Test Items

Show that the compressed form depth and mask maps adequately represents the exact version of the same information.

4.14.3 Predecessors

4.14.4 Environment Needs

4.14.4.1 Software

4.14.4.2 Hardware

4.14.5 Input Specification

Test data: A data repository containing a full DRP data reduction of the HSC PDR dataset.

4.14.6 Output Specification

4.14.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options:
		• local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	For each of the expected data products types (listed in Test Items section 4.3.2) and each of the expected units (PVIs, coadds, etc), retrieve the data product from the Butler and verify that it is non-empty.
	Test Data	No data.
	Expected Result	
4	Description	Create the coadd pixel level depth map for the HSC PDR dataset.
	Test Data	No data.
	Expected Result	
5	Description	Generate compressed representation of the pixel level depth map.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
6	Description	Create the coadd pixel level mask map for the HSC PDR dataset.
	Test Data	No data.
	Expected Result	
7	Description	Generate compressed representation of the mask map.
	Test Data	No data.
	Expected Result	
8	Description	Sample randomly from both the pixel level and compressed depth maps. Compare the distribution of depths sampled from the pixel level depth map to that sampled from the compressed representation.
	Test Data	No data.
	Expected Result	
9	Description	Divide the mask planes into two groups: INFO and BAD. BAD flags are any that would cause a particular pixel to be excluded from processing: e.g. EDGE, SAT, BAD. Sample masks from both the pixel level mask map and the compressed mask map.

For each sample, compute sum(mask_pixel xor mask_compressed).   Produce the distribution of the number of bits that differ between the samples.

Repeat for both the INFO flags and the BAD flags. |
| | Test Data | No data. |
| | Expected Result | |

4.15 LVV-T24 - Verify implementation of Computing Derived Quantities

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Rubin Observatory

Open LVV-T24 in Jira

4.15.1 Verification Elements

- LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities

4.15.2 Test Items

To confirm that common derived quantities (apparent magnitude, FWHM in arcsec, ellipticity) are available to an end-user by, e.g., ensuring a color-color diagram is easy to construction, fitting functions to derived data, or generating other common scientific derivatives.

4.15.3 Predecessors

4.15.4 Environment Needs

4.15.4.1 Software

4.15.4.2 Hardware

4.15.5 Input Specification

Example data set (e.g., non-LSST or LSST commissioning) loaded into the Science Platform in a format consistent with the DPDD.

4.15.6 Output Specification

4.15.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	**Description**	The 'path' that you will use depends on where you are running the science pipelines. Options:
		• local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash
		From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary.
		To check versions in use, type: eups list -s
2-1 from LVV-T987	**Description**	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	**Description**	For each of the expected data product types (listed in Test Items section ☐☐4.3.2) and each of the expected units (PVIs, coadds, etc), retrieve the data product from the Butler and verify it to be non-empty.
	Test Data	No data.
	Expected Result	
4	**Description**	Load into DPDD+Science Platform
	Test Data	No data.
	Expected Result	
5	**Description**	Constructing color-color diagram and fitting stellar locus in Science Platform.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
6	Description	Invite three members of commissioning team to create color-color diagram from coadd catalogs based on merged coadd reference catalog.
	Test Data	No data.
	Expected Result	

4.16   LVV-T25 - Verify implementation of Denormalizing Database Tables

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T25 in Jira

4.16.1   Verification Elements

- LVV-163 - DMS-REQ-0332-V-01: Denormalizing Database Tables

4.16.2   Test Items

Verify that commonly useful views of data are easy to obtain through the Science Platform.

4.16.3   Predecessors

4.16.4   Environment Needs

4.16.4.1   Software

4.16.4.2   Hardware

4.16.5   Input Specification

4.16.6   Output Specification

4.16.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Connect to the Science Platform's portal query interface.
	Test Data	No data.
	Expected Result	
2	Description	List the available views in the database.
	Test Data	No data.
	Expected Result	
3	Description	Take 20 sampled queries and determine which are easily done on views and which require complicated joins. Discuss the complicated ones and determine if any could be simplified by adding additional views.
	Test Data	No data.
	Expected Result	

4.17   LVV-T26 - Verify implementation of Maximum Likelihood Values and Co-variances

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T26 in Jira

4.17.1   Verification Elements

- LVV-164 - DMS-REQ-0333-V-01: Maximum Likelihood Values and Covariances

Rubin Observatory

4.17.2   Test Items

- Check that all measurements in source and object schemas include columns containing uncertainties, including covariances between jointly-measured quantities.
- Check that all model-fit measurements in source and object schemas include columns that report goodness-of-fit.
- Check that most sources and objects with successful measurements report finite uncertainty values for those measurements.
- Check that most sources and objects with successful model-fit measurements report finite goodness-of-fit values.

4.17.3   Predecessors

4.17.4   Environment Needs

4.17.4.1   Software

4.17.4.2   Hardware

4.17.5   Input Specification

4.17.6   Output Specification

4.17.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	**Description**	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T987	**Description**	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	**Description**	For each of the expected data product types (listed in Test Items section ☐☐4.3.2) and each of the expected units (PVIs, coadds, etc), retrieve the data product from the Butler and verify it to be non-empty.
	Test Data	No data.
	Expected Result	
4	**Description**	Verify that maximum likelihood and covariant quantities are provided. Test and manually inspect that they are reasonable (finite, appropriately normed).
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

62

Rubin Observatory

4.18   LVV-T27 - Verify implementation of Data Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T27 in Jira

4.18.1   Verification Elements

- LVV-177 - DMS-REQ-0346-V-01: Data Availability

4.18.2   Test Items

Determine if all required categories of raw data (specifically enumerated: raw exposures, cal-
ibration frames, telemetry, configuration metadata) can be located through the Science Plat-
form and are available for download.   Verify through (1) administrative review; (2) checking
with precursor data; (3) checking on early data feeds from the Summit such as from AuxTel
and ComCam.

4.18.3   Predecessors

4.18.4   Environment Needs

4.18.4.1   Software

4.18.4.2   Hardware

4.18.5   Input Specification

4.18.6   Output Specification

4.18.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Invite two reviewers to review that plan that seems reasonable to expect the archiving and provision of raw data
	Test Data	No data.
	Expected Result	
2	Description	Pass a set of HSC data through (equal in size to the first public data release) the data backbone through ingest and provide interface
	Test Data	No data.
	Expected Result	
3	Description	Track the ingestion of AuxTel data during one month in 2018-2019 and verify delivery and test download.
	Test Data	No data.
	Expected Result	

4.19 LVV-T28 - Verify implementation of measurements in catalogs from PVIs

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Colin Slater

Open LVV-T28 in Jira

4.19.1 Verification Elements

• LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

4.19.2 Test Items

Verify that source measurements in catalogs containing measurements from processed visit images are in flux units.

4.19.3 Predecessors

Rubin Observatory

4.19.4   Environment Needs

4.19.4.1   Software

4.19.4.2   Hardware

4.19.5   Input Specification

4.19.6   Output Specification

4.19.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Identify and read an appropriate processed precursor dataset containing coadds with the Butler.
	Test Data	No data.
	Expected Result	
3	Description	Verify that the single-visit catalog provides measurements in flux units.
	Test Data	No data.
	Expected Result	Confirmation of measurements in catalogs encoded in flux units.

4.20   LVV-T29 - Verify implementation of Raw Science Image Data Acquisition

Version	Status	Priority	Verification Type	Owner

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

65

1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T29 in Jira

4.20.1 Verification Elements

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition

4.20.2 Test Items

Verify acquisition of raw data from L1 Test Stand DAQ while simulating all modes

4.20.3 Predecessors

4.20.4 Environment Needs

4.20.4.1 Software

4.20.4.2 Hardware

4.20.5 Input Specification

4.20.6 Output Specification

4.20.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest raw data from L1 Test Stand DAQ, simulating each observing mode
	Test Data	No data.
	Expected Result	
2	Description	Observe image and its metadata is present and queryable in the Data Backbone.

Step	Description, Input Data and Expected Result	
Test Data	No data.	
Expected Result	Well-formed image data with appropriate associated metadata.	

4.21 LVV-T30 - Verify implementation of Wavefront Sensor Data Acquisition

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T30 in Jira

4.21.1 Verification Elements

- LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition

4.21.2 Test Items

Verify successful ingestion of wavefront sensor data from L1 Test Stand DAQ while simulating all modes.

4.21.3 Predecessors

4.21.4 Environment Needs

4.21.4.1 Software

4.21.4.2 Hardware

4.21.5 Input Specification

4.21.6   Output Specification

4.21.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest wavefront sensor data from L1 Test Stand DAQ while simulating all modes
	Test Data	No data.
	Expected Result	
2	Description	Observe wavefront sensor data and metadata archived in the Data Backbone.
	Test Data	No data.
	Expected Result	Well-formed wavefront sensor image data with appropriate associated metadata.

4.22   LVV-T31 - Verify implementation of Crosstalk Corrected Science Image Data Acquisition

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T31 in Jira

4.22.1   Verification Elements

- LVV-10 - DMS-REQ-0022-V-01: Crosstalk Corrected Science Image Data Acquisition

4.22.2   Test Items

Verify successful ingestion of crosstalk corrected data from L1 Test Stand DAQ while simulating all modes.

4.22.3   Predecessors

Rubin Observatory

4.22.4   Environment Needs

4.22.4.1   Software

4.22.4.2   Hardware

4.22.5   Input Specification

4.22.6   Output Specification

4.22.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inject signals of different relative strength
	Test Data	No data.
	Expected Result	
2	Description	Apply Camera cross-talk correction
	Test Data	No data.
	Expected Result	
3	Description	Verify that DMS sytem can import the cross-talk corrected images
	Test Data	No data.
	Expected Result	
4	Description	Verify that images are corrected for crosstalk
	Test Data	No data.
	Expected Result	

4.23   LVV-T32 - Verify implementation of Raw Image Assembly

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T32 in Jira

4.23.1 Verification Elements

- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly

4.23.2 Test Items

Verify that the raw exposure data from all readout channels in a sensor can be assembled into a single image, and that all required/relevant metadata are associated with the image data.

4.23.3 Predecessors

4.23.4 Environment Needs

4.23.4.1 Software

4.23.4.2 Hardware

4.23.5 Input Specification

4.23.6 Output Specification

4.23.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest data from the L1 Camera Test Stand DAQ.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	Simulate all different modes of data gathering.
	Test Data	No data.
	Expected Result	
3	Description	Verify that a raw image is constructed in correct format.
	Test Data	No data.
	Expected Result	A single raw image combining data from all readout channels for a given sensor.
4	Description	Verify that a raw image is constructed with correct metadata.
	Test Data	No data.
	Expected Result	Image header or ancillary table contains the required metadata about the observing context in which data were gathered.

4.24 LVV-T33 - Verify implementation of Raw Science Image Metadata

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T33 in Jira

4.24.1 Verification Elements

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-1234 - OSS-REQ-0122-V-01: Provenance

4.24.2 Test Items

Verify successful ingestion of raw data from L1 Test Stand DAQ and that image metadata is present and queryable.

4.24.3   Predecessors

LVV-T29, LVV-T32

4.24.4   Environment Needs

4.24.4.1   Software

4.24.4.2   Hardware

4.24.5   Input Specification

4.24.6   Output Specification

4.24.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify (or gather) a dataset of raw science images.
	Test Data	No data.
	Expected Result	
2	Description	Verify that time of exposure start/end, site metadata, telescope metadata, and camera metadata are stored in DMS system.
	Test Data	No data.
	Expected Result	Raw image data contain the required metadata.

4.25   LVV-T34 - Verify implementation of Guider Calibration Data Acquisition

Version	Status	Priority	Verification Type	Owner

1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T34 in Jira

4.25.1 Verification Elements

- LVV-96 - DMS-REQ-0265-V-01: Guider Calibration Data Acquisition

4.25.2 Test Items

Verify successful
1. Ingestion of calibration frames from L1 Test Stand DAQ
2. Execution of CPP payloads
3. Availability of observed guider calibration products

4.25.3 Predecessors

4.25.4 Environment Needs

4.25.4.1 Software

4.25.4.2 Hardware

4.25.5 Input Specification

4.25.6 Output Specification

4.25.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest calibration frames for the guider sensors from L1 Test Stand DAQ
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Observe that guider calibration products have been produced.
	Test Data	No data.
	Expected Result	Well-formed calibration frames for the guider sensors.

4.26   LVV-T35 - Verify implementation of Nightly Data Accessible Within 24 hrs

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T35 in Jira

4.26.1   Verification Elements

- LVV-175 - DMS-REQ-0004-V-01: Time to L1 public release

4.26.2   Test Items

Test Items

Verify that

1. Alerts are available within OTT1

2. Level 1 Data Products are available within L1PublicT

3. Solar System Object orbits are available within L1PublicT of the updated calculations completion on the following night.

4.26.3 Predecessors

4.26.4 Environment Needs

4.26.4.1 Software

4.26.4.2 Hardware

4.26.5 Input Specification

4.26.6 Output Specification

4.26.7 Test Procedure

Step	Description, Input Data and Expected Result
1-1 from LVV-T860	**Description** The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code: **Test Data**

Rubin Observatory

Step		Description, Input Data and Expected Result
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary.
		To check versions in use, type: eups list -s
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	Time processing of data starting from (pre-ingested) raw files until an alert is available for distribution; verify that this time is less than OTT1.
	Test Data	No data.
	Expected Result	
4	Description	Time processing of data starting from (pre-ingested) raw files until the required data products are available in the Science Platform. Verify that this time is less than L1PublicT.
	Test Data	No data.
	Expected Result	
5	Description	Run MOPS on 1 night equivalent of LSST observing worth of precursor data and verify that Solar System Object orbits can be updated within 24 hours.
	Test Data	No data.
	Expected Result	
6	Description	Record time between completion of MOPS processing and availability of the updated SSObject catalogue through the Science Platform; verify this time is less than L1PublicT.

Rubin Observatory

Step	Description, Input Data and Expected Result
	Test Data No data.
	Expected Result

4.27   LVV-T36 - Verify implementation of Difference Exposures

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T36 in Jira

4.27.1   Verification Elements

- LVV-7 - DMS-REQ-0010-V-01: Difference Exposures

4.27.2   Test Items

Verify successful creation of a
1. PSF-matched template image for a given Processed Visit Image
2. Difference Exposure from each Processed Visit Image

4.27.3   Predecessors

4.27.4   Environment Needs

4.27.4.1   Software

4.27.4.2   Hardware

4.27.5   Input Specification

Rubin Observatory

4.27.6   Output Specification

4.27.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Demonstrate successful creation of a template image from HSC PDF and DECAM HiTS data. Demonstrate successful creation of a Difference Exposure for at least 10 other images from survey, ideally at a range of arimass. In particular, HiTS has 2013A u-band data. While the Blanco 4-m does have an ADC, there are still some chromatic effects and we should demonstrate that we can successfully produce Difference Exposures and templates for diferent airmass bins.
	Test Data	No data.
	Expected Result	

4.28   LVV-T37 - Verify implementation of Difference Exposure Attributes

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T37 in Jira

4.28.1   Verification Elements

- LVV-32 - DMS-REQ-0074-V-01: Difference Exposure Attributes

- LVV-1234 - OSS-REQ-0122-V-01: Provenance

4.28.2   Test Items

Verify that for each Difference Exposure the DMS stores
1. The identify of the input exposures and related provenance information
2. Metadata attributes of the subtraction, including the PSF-matching kernel used.

4.28.3   Predecessors

4.28.4   Environment Needs

4.28.4.1   Software

Rubin Observatory

4.28.4.2   Hardware

4.28.5   Input Specification

4.28.6   Output Specification

4.28.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

80

Step	Description, Input Data and Expected Result	
3	Description	For each of HSC PDR and DECAM HiTS data: set up three different templates and run subtractions on 10 different images from at least two different filters. Verify that we can recover the provenance information about which template was used for each subtraction, which input images were used for that template, and that we can successfull extract the PSF matching kernel.
	Test Data	No data.
	Expected Result	

4.29   LVV-T38 - Verify implementation of Processed Visit Images

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T38 in Jira

4.29.1   Verification Elements

- LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images

4.29.2   Test Items

Verify that the DMS

1. Successfully produces Processed Visit Images, where the instrument signature has been removed.

2. Successfully combines images obtained during a standard visit.

4.29.3   Predecessors

4.29.4   Environment Needs

4.29.4.1   Software

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

81

Rubin Observatory

4.29.4.2   Hardware

4.29.5   Input Specification

4.29.6   Output Specification

4.29.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify suitable precursor datasets containing unprocessed raw images.
	Test Data	No data.
	Expected Result	
2	Description	Run the Prompt Processing payload on these data. Verify that Processed Visit Images are generated at correct size and with significant instrumental artifacts removed.
	Test Data	No data.
	Expected Result	Raw precursor dataset images have been processed into Processed Visit Images, with instrumental artifacts corrected.
3	Description	Run camera test stand data through full acquisition+backbone+ISR.
	Test Data	No data.
	Expected Result	
4	Description	Run simulated LSST data with calibrations through prompt processing system and inspect Processed Visit images to verify that they have been cleaned of significant artifacts and are of the correct, shape, and described orientation.
	Test Data	No data.
	Expected Result	Raw images have been processed into Processed Visit Images, with instrumental artifacts corrected.

4.30   LVV-T39 - Verify implementation of Generate Photometric Zeropoint for Visit Image

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Approved	Normal	Test	Jim Bosch

Open LVV-T39 in Jira

4.30.1 Verification Elements

- LVV-12 - DMS-REQ-0029-V-01: Generate Photometric Zeropoint for Visit Image

4.30.2 Test Items

Verify that Processed Visit Image data products produced by the DRP and AP pipelines include the parameters of a model that relates the observed flux on the image to physical flux units.

4.30.3 Predecessors

4.30.4 Environment Needs

4.30.4.1 Software

4.30.4.2 Hardware

4.30.5 Input Specification

4.30.6 Output Specification

4.30.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset with processed visit images in multiple filters.
	Test Data	No data.
	Expected Result	

Step	Description, Input Data and Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Extract the photometric zeropoint from the source catalog associated with a visit image. Repeat this for all available filters, and confirm that the zeropoint has been set, and has a reasonable value.
	Test Data	No data.
	Expected Result	A zeropoint that enables one to convert the measured fluxes to magnitudes.
4	Description	Extract fluxes for some sources, and convert them to magnitudes. Confirm that the distribution spans a reasonable range.
	Test Data	No data.
	Expected Result	In most cases, well-measured magnitudes (i.e., for high S/N measurements) should be between 12 to 28 for all bands.

4.31   LVV-T40 - Verify implementation of Generate WCS for Visit Images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T40 in Jira

4.31.1   Verification Elements

- LVV-13 - DMS-REQ-0030-V-01: Absolute accuracy of WCS

4.31.2   Test Items

Verify that Processed Visit Images produced by the AP and DRP pipelines include FITS WCS accurate to specified **astrometricAccuracy** over the bounds of the image.

4.31.3 Predecessors

4.31.4 Environment Needs

4.31.4.1 Software

4.31.4.2 Hardware

4.31.5 Input Specification

4.31.6 Output Specification

4.31.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify an appropriate processed dataset for this test.
	Test Data	No data.
	Expected Result	A dataset with Processed Visit Images available.
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Select a single visit from the dataset, and extract its WCS object and the source list.
	Test Data	No data.
	Expected Result	A table containing detected sources, and a WCS object associated with that catalog.
4	Description	Confirm that each CCD within the visit image contains at least **astrometricMinStandards** astrometric standards that were used in deriving the astrometric solution.
	Test Data	No data.

Rubin Observatory

Step		Description, Input Data and Expected Result
	Expected Result	At least **astrometricMinStandards** from each CCD were used in determining the WCS solution.
5	Description	Starting from the XY pixel coordinates of the sources, apply the WCS to obtain RA, Dec coordinates.
	Test Data	No data.
	Expected Result	A list of RA, Dec coordinates for all sources in the catalog.
6	Description	We will assume that Gaia provides a source of "truth." Match the source list to Gaia DR2, and calculate the positional offset between the test data and the Gaia catalog.
	Test Data	No data.
	Expected Result	A matched catalog of sources in common between the test source list and Gaia DR2.
7	Description	Apply appropriate cuts to extract the optimal dataset for comparison, then calculate statistics (median, 1-sigma range, etc.; also plot a histogram) of the offsets in milliarcseconds. Confirm that the offset is less than **astrometricAccuracy**.
	Test Data	No data.
	Expected Result	Histogram and relevant statistics needed to confirm that the WCS transformation is accurate.
8	Description	Repeat Step 5, but for subregions of the image, to confirm that the accuracy criterion is met at all positions.
	Test Data	No data.
	Expected Result	**astrometricAccuracy** requirement is met over the entire image.

4.32 LVV-T41 - Verify implementation of Generate PSF for Visit Images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T41 in Jira

Rubin Observatory

4.32.1   Verification Elements

- LVV-30 - DMS-REQ-0070-V-01: Generate PSF for Visit Images

4.32.2   Test Items

Verify that Processed Visit Images produced by the DRP and AP pipelines are associated with a model from which one can obtain an image of the PSF given a point on the image.

4.32.3   Predecessors

4.32.4   Environment Needs

4.32.4.1   Software

4.32.4.2   Hardware

4.32.5   Input Specification

4.32.6   Output Specification

4.32.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset with processed visit images in multiple filters.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Select Objects classified as point sources on at least 10 different processed visit images (including all bands). Evaluate the PSF model at the positions of these Objects, and verify that subtracting a scaled version of the PSF model from the processed visit image yields residuals consistent with pure noise.
	Test Data	No data.
	Expected Result	Images with the PSF model subtracted, leaving only residuals that are consistent with being noise.

4.33   LVV-T42 - Verify implementation of Processed Visit Image Content

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Jim Bosch

Open LVV-T42 in Jira

4.33.1   Verification Elements

- LVV-31 - DMS-REQ-0072-V-01: Processed Visit Image Content

4.33.2   Test Items

Verify that Processed Visit Images produced by the DRP and AP pipelines include the observed data, a mask array, a variance array, a PSF model, and a WCS model.

4.33.3   Predecessors

4.33.4   Environment Needs

4.33.4.1   Software

Rubin Observatory

4.33.4.2   Hardware

4.33.5   Input Specification

4.33.6   Output Specification

4.33.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Ingest the data from an appropriate processed dataset.
	Test Data	No data.
	Expected Result	
3	Description	Select a single visit from the dataset, and extract its WCS object, calexp image, psf model, and source list.
	Test Data	No data.
	Expected Result	
4	Description	Inspect the calexp image to ensure that 1. A well-formed image is present, 2. The variance plane is present and well-behaved, 3. Mask planes are present and contain information about defects.
	Test Data	No data.
	Expected Result	An astronomical image with mask and variance planes. This can be readily visualized using Firefly, which displays mask planes by default.
5	Description	Plot images of the PSF model at various points, and verify that the PSF differs with position.
	Test Data	No data.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

89

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	A "star-like" image of the PSF evaluated at various positions. The PSF should vary slightly with position (this could be readily visualized by taking a difference of PSFs at two positions).
6	Description	Starting from the XY pixel coordinates of the sources, apply the WCS to obtain RA, Dec coordinates. Plot these positions and confirm that they match the expected values from the WCS object.
	Test Data	No data.
	Expected Result	RA, Dec coordinates that are returned should be near the central position of the visit coordinate as given in either the calexp metadata or the WCS.
7	Description	Repeat steps 2-6, but now with difference images created by the Alert Production pipeline (for example, in the 'ap_verify' test data processing).
	Test Data	No data.
	Expected Result	

4.34   LVV-T43 - Verify implementation of Background Model Calculation

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T43 in Jira

4.34.1   Verification Elements

- LVV-158 - DMS-REQ-0327-V-01: Background Model Calculation

4.34.2   Test Items

Verify that Processed Visit Images produced by the DRP and AP pipelines have had a model of the background subtracted, and that this model is persisted in a way that permits the background subtracted from any CCD to be retrieved along with the image for that CCD.

4.34.3   Predecessors

LVV-T15
LVV-T19

4.34.4   Environment Needs

4.34.4.1   Software

4.34.4.2   Hardware

4.34.5   Input Specification

4.34.6   Output Specification

4.34.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset with processed visit images in multiple filters.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Display an image of the background model for a full CCD. Repeat this for all available filters, and confirm that the background is smoothly varying and defined over the full CCD.
	Test Data	No data.
	Expected Result	Well-formed background covering the entire CCD for all CCDs in all filters.

Rubin Observatory

4.35   LVV-T44 - Verify implementation of Documenting Image Characterization

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T44 in Jira

4.35.1   Verification Elements

- LVV-159 - DMS-REQ-0328-V-01: Documenting Image Characterization

4.35.2   Test Items

Verify that the persisted format for Processed Visit Images and associated instrument-signature-removal data products is documented.

4.35.3   Predecessors

4.35.4   Environment Needs

4.35.4.1   Software

4.35.4.2   Hardware

4.35.5   Input Specification

4.35.6   Output Specification

4.35.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to Alert Production
	Test Data	No data.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

92

Rubin Observatory

Step	Description, Input Data and Expected Result
	Expected
	Result

4.36   LVV-T45 - Verify implementation of Prompt Processing Data Quality Report Definition

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T45 in Jira

4.36.1   Verification Elements

- LVV-39 - DMS-REQ-0097-V-01: Level 1 Data Quality Report Definition

4.36.2   Test Items

Verify that the DMS produces a Prompt Processing Data Quality Report.   Specifically check absolute value and temporal variation of

1. Photometric zeropoint
2. Sky brightness
3. Seeing
4. PSF
5. Detection efficiency

4.36.3   Predecessors

4.36.4   Environment Needs

4.36.4.1   Software

Rubin Observatory

4.36.4.2   Hardware

4.36.5   Input Specification

4.36.6   Output Specification

4.36.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest raw data from L1 Test Stand DAQ.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	Load the Prompt Processing QC reports, and observe that a dynamically updated Data Quality Report has become available at the relevant UI.
	Test Data	No data.
	Expected Result	A Prompt Processing QC report is available via a UI, and contains information about the photometric zeropoint, sky brightness, seeing, PSF, and detection efficiency, and possibly other relevant quantities.
4	Description	Check that a static report is created and archived in a readily-accessible location.
	Test Data	No data.
	Expected Result	Persistence of a static QC report in an accessible location, containing the same information as in the report from Step 3.

4.37 LVV-T46 - Verify implementation of Prompt Processing Performance Report Definition

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T46 in Jira

4.37.1 Verification Elements

- LVV-41 - DMS-REQ-0099-V-01: Level 1 Performance Report Definition

4.37.2 Test Items

Verify that the DMS produces a Prompt Processing Performance Report. Specifically check that the number of observations that describe each of the following:
1. Successfully processed, recoverable failures, unrecoverable failures.
2. Archived
3. Result in science.

This is testing more the processing rather than the observatory system.

4.37.3 Predecessors

4.37.4 Environment Needs

4.37.4.1 Software

4.37.4.2 Hardware

4.37.5 Input Specification

Rubin Observatory

4.37.6   Output Specification

4.37.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal, observe report
	Test Data	No data.
	Expected Result	

4.38   LVV-T47 - Verify implementation of Prompt Processing Calibration Report Definition

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T47 in Jira

4.38.1   Verification Elements

- LVV-43 - DMS-REQ-0101-V-01: Level 1 Calibration Report Definition

4.38.2   Test Items

Verify that the DMS produces a Prompt Processing Calibration Report. Specifically check that this report is capable of identifying when aspects of the telescope or camera are changing with time.

4.38.3   Predecessors

4.38.4   Environment Needs

4.38.4.1   Software

Rubin Observatory

4.38.4.2   Hardware

4.38.5   Input Specification

4.38.6   Output Specification

4.38.7   Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Identify precursor and simulated calibration datasets on which to run the L1 calibration pipeline.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1059	Description	Execute the Daily Calibration Products Update payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1059	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Check that a dynamic report is created that triggers alerts if calibrations go out of range.
	Test Data	No data.
	Expected Result	A dynamic report is available via UI to users, and if any out-of-spec changes have occurred, alerts have been issued.
4	Description	Check that a static report is created and archived in a readily-accessible location.
	Test Data	No data.
	Expected Result	An archived version of the calibration report is available and will be retained in a static file format.

Rubin Observatory

4.39   LVV-T48 - Verify implementation of Exposure Catalog

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Jim Bosch

Open LVV-T48 in Jira

4.39.1   Verification Elements

- LVV-97 - DMS-REQ-0266-V-01: Exposure Catalog

4.39.2   Test Items

Verify that the DMS creates an Exposure Catalog that includes
1. Observation datetime, exposure time
2. Filter
3. Dome, telescope orientation and status
4. Calibration status
5. Airmass and zenith
6. Environmental information
7. Per-sensor information

4.39.3   Predecessors

4.39.4   Environment Needs

4.39.4.1   Software

4.39.4.2   Hardware

4.39.5   Input Specification

4.39.6   Output Specification

Rubin Observatory

4.39.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Verify that Exposure Catalogs contain the required elements. At present, the form of the exposure catalog is not defined. This information can be found for a given Butler repo from the metadata, but will ultimately be aggregated into a database/table summarizing available exposures.
	Test Data	No data.
	Expected Result	A list of the required metadata for a set of exposures is returned and both human- and machine-readable.

4.40   LVV-T49 - Verify implementation of DIASource Catalog

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T49 in Jira

4.40.1 Verification Elements

• LVV-100 - DMS-REQ-0269-V-01: DIASource Catalog

4.40.2 Test Items

Verify that the DMS produces a Source catalog from Difference Exposures with the required attributes.

4.40.3 Predecessors

4.40.4 Environment Needs

4.40.4.1 Software

Rubin Observatory

4.40.4.2 Hardware

4.40.5 Input Specification

4.40.6 Output Specification

4.40.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	**Description**	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T866	**Description**	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	**Description**	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

100

Rubin Observatory

Step	Description, Input Data and Expected Result	

	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
3-1 from		
LVV-T987	Test Data	
	Expected Result	Butler repo available for reading.

	Description	Verify that products are produced for DIASource catalog
4	Test Data	No data.
	Expected Result	

4.41   LVV-T50 - Verify implementation of Faint DIASource Measurements

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T50 in Jira

4.41.1   Verification Elements

- LVV-101 - DMS-REQ-0270-V-01: Faint DIASource Measurements

4.41.2   Test Items

Verify that the DMS can produces DIASources measurements for sources below the nominal S/N cutoff that satisfy additional criteria.

4.41.3   Predecessors

Rubin Observatory

4.41.4   Environment Needs

4.41.4.1   Software

4.41.4.2   Hardware

4.41.5   Input Specification

Input Data
 DECam HiTS data.

4.41.6   Output Specification

4.41.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	As an example of selecting with constrains, Re-run source detection as an afterburner to select isolated sources (defined as more than 2 arcseconds away from any other objects in the single-image-depth catalog) that are fainter than the fiducial transSNR cut.
	Test Data	No data.
	Expected Result	

4.42   LVV-T51 - Verify implementation of DIAObject Catalog

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T51 in Jira

4.42.1   Verification Elements

- LVV-102 - DMS-REQ-0271-V-01: Max nearby galaxies associated with DIASource

4.42.2   Test Items

Verify that the DIAObject includes a unique ID, identifiers for nearest stars and nearest galaxies, and probability of matching to static Object.

Rubin Observatory

4.42.3   Predecessors

4.42.4   Environment Needs

4.42.4.1   Software

4.42.4.2   Hardware

4.42.5   Input Specification

4.42.6   Output Specification

4.42.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

Step	Description, Input Data and Expected Result	
3	Description	Verify that DIAObjects have diaNearbyObjMaxStar and diaNearbyObjMaxGalaxies that point to the Object catalog and are within dianNearbyObjRadius; the probability of association; and the required DIAObject properties.
	Test Data	No data.
	Expected Result	

4.43 LVV-T52 - Verify implementation of DIAObject Attributes

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T52 in Jira

4.43.1 Verification Elements

- LVV-103 - DMS-REQ-0272-V-01: DIAObject Attributes

4.43.2 Test Items

Verify that the DMS provides summary attributes for each DIAObject, including periodicity measures.

4.43.3 Predecessors

4.43.4 Environment Needs

4.43.4.1 Software

4.43.4.2 Hardware

Rubin Observatory

4.43.5 Input Specification

4.43.6 Output Specification

4.43.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Confirm that the DIAObjects include summary attributes as specified.
	Test Data	No data.
	Expected Result	

4.44 LVV-T53 - Verify implementation of SSObject Catalog

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Test	Eric Bellm

Open LVV-T53 in Jira

4.44.1 Verification Elements

- LVV-104 - DMS-REQ-0273-V-01: SSObject Catalog

4.44.2 Test Items

Verify that the DMS produces a catalog of Solar System Objects identify from Moving Object Processing.
Verify that the SSObject catalog includes orbital elements and additional related quanitites.

4.44.3 Predecessors

4.44.4 Environment Needs

4.44.4.1 Software

4.44.4.2 Hardware

4.44.5 Input Specification

4.44.6 Output Specification

4.44.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T901	Description	Perform the steps of Moving Object Pipeline (MOPS) processing on newly detected DIASources, and generate Solar System data products including Solar System objects with associated Keplerian orbits, errors, and detected DIASources. This includes running processes to link DIASource detections within a night (called tracklets), to link these tracklets across multiple nights (into tracks), to fit the tracks with an orbital model to identify those tracks that are consistent with an asteroid orbit, to match these new orbits with existing SSObjects, and to update the SSObject table.
	Test Data	
	Expected Result	An output dataset consisting of an updated SSObject database with SSObjects both added and pruned as the orbital fits have been refined, and an updated DIASource database with DIASources assigned and unassigned to SSObjects.
2-2 from LVV-T901	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
4	Description	Inspect SSObject catalog and verify the presence of the required elements (LVV-104).
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.45   LVV-T54 - Verify implementation of Alert Content

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T54 in Jira

4.45.1   Verification Elements

- LVV-105 - DMS-REQ-0274-V-01: Alert Content

4.45.2   Test Items

Verify that the DMS creates an Alert for each detected DIASource
Verify that this Alert is broadcasted using community protocols
Verify that the context of the Alert packet match requirements.

4.45.3   Predecessors

4.45.4   Environment Needs

4.45.4.1   Software

4.45.4.2   Hardware

4.45.5   Input Specification

4.45.6   Output Specification

4.45.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2	Description	Examine the serialized alert packets to confirm the presence of the required elements (LVV-105).
	Test Data	No data.
	Expected Result	

4.46   LVV-T55 - Verify implementation of DIAForcedSource Catalog

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T55 in Jira

4.46.1   Verification Elements

- LVV-148 - DMS-REQ-0317-V-01: DIAForcedSource Catalog

4.46.2   Test Items

Verify that the DMS produces a DIAForcedSource Catalog and that the catalog contains measured fluxes for DIAObjects.

Rubin Observatory

4.46.3   Predecessors

4.46.4   Environment Needs

4.46.4.1   Software

4.46.4.2   Hardware

4.46.5   Input Specification

4.46.6   Output Specification

4.46.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame process-ing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the fol-lowing:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Confirm that the DIAForcedSource catalog contains measurements for each source.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	

4.47   LVV-T56 - Verify implementation of Characterizing Variability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T56 in Jira

4.47.1   Verification Elements

- LVV-150 - DMS-REQ-0319-V-01: Characterizing Variability

4.47.2   Test Items

Verify that the variability characterization in the DIAObject catalog includes data collected within previous "diaCharacterizationCutoff" period of time.

4.47.3   Predecessors

4.47.4   Environment Needs

4.47.4.1   Software

4.47.4.2   Hardware

4.47.5   Input Specification

Rubin Observatory

4.47.6   Output Specification

4.47.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2	Description	Verify that the issued alerts contain measurements during the diaCharacterizationCutoff.
	Test Data	No data.
	Expected Result	

4.48   LVV-T57 - Verify implementation of Calculating SSObject Parameters

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T57 in Jira

4.48.1   Verification Elements

- LVV-154 - DMS-REQ-0323-V-01: Calculating SSObject Parameters

4.48.2   Test Items

Verify that the DMS database provides functions to compute phase angles and magnitudes in LSST bands for every SSObject.

4.48.3   Predecessors

4.48.4   Environment Needs

4.48.4.1   Software

4.48.4.2   Hardware

4.48.5   Input Specification

4.48.6   Output Specification

4.48.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2-1 from LVV-T901	Description	Perform the steps of Moving Object Pipeline (MOPS) processing on newly detected DIASources, and generate Solar System data products including Solar System objects with associated Keplerian orbits, errors, and detected DIASources. This includes running processes to link DIASource detections within a night (called tracklets), to link these tracklets across multiple nights (into tracks), to fit the tracks with an orbital model to identify those tracks that are consistent with an asteroid orbit, to match these new orbits with existing SSObjects, and to update the SSObject table.
	Test Data	
	Expected Result	An output dataset consisting of an updated SSObject database with SSObjects both added and pruned as the orbital fits have been refined, and an updated DIASource database with DIASources assigned and unassigned to SSObjects.
2-2 from LVV-T901	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	Computer the phase angle, reduced and absolute asteroid magnitudes for objects identified in SSObject Catalog
	Test Data	No data.
	Expected Result	

4.49   LVV-T58 - Verify implementation of Matching DIASources to Objects

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T58 in Jira

4.49.1   Verification Elements

• LVV-155 - DMS-REQ-0324-V-01: Matching DIASources to Objects

4.49.2   Test Items

Verify that a cross-match table is available between DIASources and Objects.

4.49.3   Predecessors

4.49.4   Environment Needs

4.49.4.1   Software

4.49.4.2   Hardware

4.49.5   Input Specification

4.49.6   Output Specification

4.49.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Butler repo available for reading.
3	Description	Verify that a cross-match table between the Prompt DIASources and DRP Objects is available.
	Test Data	No data.
	Expected Result	

4.50   LVV-T59 - Verify implementation of Regenerating L1 Data Products During Data Release Processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T59 in Jira

4.50.1   Verification Elements

- LVV-156 - DMS-REQ-0325-V-01: Regenerating L1 Data Products During Data Release Processing

4.50.2   Test Items

Verify that the Prompt Processing data products are regenerated during DRP.

4.50.3   Predecessors

4.50.4   Environment Needs

4.50.4.1   Software

Rubin Observatory

4.50.4.2   Hardware

4.50.5   Input Specification

4.50.6   Output Specification

4.50.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute DRP
	Test Data	No data.
	Expected Result	
2	Description	Observe production of difference image data products
	Test Data	No data.
	Expected Result	

4.51   LVV-T60 - Verify implementation of Publishing predicted visit schedule

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T60 in Jira

4.51.1   Verification Elements

• LVV-184 - DMS-REQ-0353-V-01: Publishing predicted visit schedule

4.51.2   Test Items

Verify that a predict-visit schedule can be published by the OCS.

Rubin Observatory

4.51.3   Predecessors

4.51.4   Environment Needs

4.51.4.1   Software

4.51.4.2   Hardware

4.51.5   Input Specification

4.51.6   Output Specification

4.51.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.52   LVV-T61 - Verify implementation of Associate Sources to Objects

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Jim Bosch

Open LVV-T61 in Jira

4.52.1   Verification Elements

- LVV-16 - DMS-REQ-0034-V-01: Associate Sources to Objects

4.52.2   Test Items

Verify that each Source record contains an ID that associates it with a best guess at the Object it corresponds to.

4.52.3   Predecessors

4.52.4   Environment Needs

4.52.4.1   Software

4.52.4.2   Hardware

4.52.5   Input Specification

4.52.6   Output Specification

4.52.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Read a dataset via the Butler and extract its source and object catalogs.
	Test Data	No data.
	Expected Result	
3	Description	Verify that sources have objects
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
4	Description	Verify that objects list sources that seem reasonably near them.
	Test Data	No data.
	Expected Result	

4.53 LVV-T62 - Verify implementation of Provide PSF for Coadded Images

Version	Status	Priority	Verification Type	Owner
2	Approved	Normal	Test	Jim Bosch

Open LVV-T62 in Jira

4.53.1 Verification Elements

- LVV-20 - DMS-REQ-0047-V-01: Provide PSF for Coadded Images

4.53.2 Test Items

Verify that all coadd images produced by the DRP pipelines include a model from which an image of the PSF at any point on the coadd can be obtained.

4.53.3 Predecessors

4.53.4 Environment Needs

4.53.4.1 Software

4.53.4.2 Hardware

Rubin Observatory

4.53.5 Input Specification

Fully covered by preconditions for LVV-T16.

4.53.6 Output Specification

4.53.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset with coadded images in multiple filters.
	Test Data	No data.
	Expected Result	Multi-band data that has been processed through the coaddition stage.
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Load the exposures, then select Objects classified as point sources on at least 10 different coadd images (including all bands). Evaluate the PSF model at the positions of these Objects, and verify that subtracting a scaled version of the PSF model from the processed visit image yields residuals consistent with pure noise.
	Test Data	No data.
	Expected Result	Images with the PSF model subtracted, leaving only residuals that are consistent with being noise.

4.54 LVV-T63 - Verify implementation of Produce Images for EPO

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T63 in Jira

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

122

Rubin Observatory

4.54.1   Verification Elements

- LVV-45 - DMS-REQ-0103-V-01: Produce Images for EPO

4.54.2   Test Items

This test will verify that the DRP pipelines produce the image data products called out in LSE-131. Currently this is limited to a color all-sky HiPS map. This will be verified (1) by inspection of pipeline configurations and (2) in operations rehearsals on precursor data. The production of a usable HiPS map will be verified by browsing it with community tools.

4.54.3   Predecessors

4.54.4   Environment Needs

4.54.4.1   Software

4.54.4.2   Hardware

4.54.5   Input Specification

In order for an operational test to be successful, as a precondition the inputs to that production must exist.   For the only currently mandated image data production in LSE-131, a color all-sky HiPS map down to 1 arcsecond resolution, the prerequisite inputs to that are the single-filter coadds in the bands required by the yet-to-be-specified color prescription.

4.54.6   Output Specification

4.54.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	For each of the expected data product types needed for creation of HiPS images, retrieve the data product from the Butler and verify it to be non-empty.
	Test Data	No data.
	Expected Result	
3	Description	Verify that a HiPS image map covering the LSST survey area, with a limiting depth yielding 1 arcsecond resolution, has been produced matching the color prescriptions provided by EPO (in updates to LSE-131 which are expected to be made "once ComCam data is available").
	Test Data	No data.
	Expected Result	
4	Description	Place the image map in a location accessible to a Firefly and an Aladin Lite client, ideally with the client running in the EPO data systems environment.
	Test Data	No data.
	Expected Result	
5	Description	Use Firefly to manually explore the image map at the largest scales to verify coverage of the entire sky. Sample in various locations to confirm the 1 arcsecond maximum depth. Confirm using Aladin Lite that the format of the image map is supported by this common community tool.
	Test Data	No data.
	Expected Result	
6	Description	Verify programmatically, perhaps both by sampling a variety of locations, and by counting the tiles created at the 1-arcsecond-resolution depth, that the map is complete and meets its specifications.
	Test Data	No data.
	Expected Result	
7	Description	Apply an IVOA-community HiPS service validation tool, if available, to the service location.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
8	Description	Verify that the HiPS map created is in a location accessible to the EPO data systems.
	Test Data	No data.
	Expected Result	

4.55 LVV-T64 - Verify implementation of Coadded Image Provenance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T64 in Jira

4.55.1 Verification Elements

- LVV-46 - DMS-REQ-0106-V-01: Coadded Image Provenance

- LVV-1234 - OSS-REQ-0122-V-01: Provenance

4.55.2 Test Items

Verify that all coadd data products produced by the DRP pipelines are associated with provenance information that includes the set of input epochs contributing to that coadd as well as any additional information needed to exactly produce that coadd.

4.55.3 Predecessors

4.55.4 Environment Needs

4.55.4.1 Software

Rubin Observatory

4.55.4.2   Hardware

4.55.5   Input Specification

4.55.6   Output Specification

4.55.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	For each of the expected data product types and each of the expected units (PVIs, coadds, etc), retrieve the data product from the Butler and verify it to be non-empty.
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

126

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Query and verify provenance of input images, and software versions that went into producing stack.
	Test Data	No data.
	Expected Result	
5	Description	Test re-generating 10 different coadds tract+patches based on the provenance image given
	Test Data	No data.
	Expected Result	

4.56   LVV-T65 - Verify implementation of Source Catalog

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Jim Bosch

Open LVV-T65 in Jira

4.56.1   Verification Elements

- LVV-98 - DMS-REQ-0267-V-01: Source Catalog

4.56.2   Test Items

Verify that all Sources produced by the DRP pipelines contain the entries listed in DMS-REQ-0267.

4.56.3   Predecessors

4.56.4   Environment Needs

4.56.4.1   Software

Rubin Observatory

4.56.4.2   Hardware

4.56.5   Input Specification

4.56.6   Output Specification

4.56.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a suitable small dataset to process through the DRP.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1064	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	
	Expected Result	
3	Description	Confirm that source catalogs have been produced for single visits and coadds, and that it contains the required measurements.
	Test Data	No data.
	Expected Result	A source catalog containing the measured attributes (and associated errors), including location on the focal plane; a static point-source model fit to world coordinates and flux; a centroid and adaptive moments; and surface brightnesses through elliptical multiple apertures that are concentric, PSF-homogenized, and logarithmically spaced in intensity.

4.57   LVV-T66 - Verify implementation of Forced-Source Catalog

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T66 in Jira

Rubin Observatory

4.57.1 Verification Elements

- LVV-99 - DMS-REQ-0268-V-01: Forced-Source Catalog

4.57.2 Test Items

Verify that all ForcedSources produced by the DRP pipelines contain fluxes measured on difference and direct single-epoch images, associated uncertainties, an Object ID, and a Visit ID.

4.57.3 Predecessors

4.57.4 Environment Needs

4.57.4.1 Software

4.57.4.2 Hardware

4.57.5 Input Specification

4.57.6 Output Specification

4.57.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Retrieve the forced-source catalog from the Butler and verify it to be non-empty.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	Verify that there exist entries in the forced-photometry table for all coadd objects for the PVIs on which the object should appear.
	Test Data	No data.
	Expected Result	
4	Description	Verify that there exist entries in a forced-photometry table for each image for all DIAObjects.
	Test Data	No data.
	Expected Result	

4.58   LVV-T67 - Verify implementation of Object Catalog

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T67 in Jira

4.58.1   Verification Elements

• LVV-106 - DMS-REQ-0275-V-01: Object Catalog

4.58.2   Test Items

Verify that the DRP pipelines produce an Object catalog derived from detections made on both coadded images and difference images and measurements performed on coadds and possibly overlapping single-epoch images.

Rubin Observatory

4.58.3   Predecessors

4.58.4   Environment Needs

4.58.4.1   Software

4.58.4.2   Hardware

4.58.5   Input Specification

Input Data

DECam HiTS data (raw science images and master calibrations)
HSC "RC2" data (raw science images and master calibrations)

4.58.6   Output Specification

4.58.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	load LSST DM Stack
	Test Data	No data.
	Expected Result	
2	Description	Run the single-frame processing and self-calibration steps of the DRP pipeline.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Insert simulated sources into all single-frame images, including:
		• static objects (e.g. galaxies), including some too faint to be detectable in single-epoch images;
		• objects with static positions that are sufficiently bright and variable that they should be detectable in single-epoch difference images;
		• transient objects that appear in only a few epochs;
		• stars with significant proper motions and parallaxes, some below the single-epoch detection limit
		• simulated solar system objects with orbits that can be constrained from just the epochs in the test dataset
	Test Data	No data.
	Expected Result	
4	Description	Run all remaining DRP pipeline steps.
	Test Data	No data.
	Expected Result	
5	Description	Load data into DRP database
	Test Data	No data.
	Expected Result	
6	Description	Verify that the injected simulated objects are recovered at a rate consistent with their S/N *when not blended with each other or real objects*, and that flags indicating how each Object was detected are consistent with their properties:
		• static objects should be detected in coadds only (not difference images)
		• static-position/variable-flux objects should be detected in coadds and possibly difference images
		• transient objects should be detected in difference images only
		• stars with significant proper motions may be detected in either coadds or difference images
		• solar system objects should be detected in difference images only.
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.59   LVV-T68 - Verify implementation of Provide Photometric Redshifts of Galaxies

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T68 in Jira

4.59.1   Verification Elements

- LVV-19 - DMS-REQ-0046-V-01: Provide Photometric Redshifts of Galaxies

4.59.2   Test Items

Verify that Object catalogs produced by the DRP Pipeline include photometric redshift information.

4.59.3   Predecessors

4.59.4   Environment Needs

4.59.4.1   Software

4.59.4.2   Hardware

4.59.5   Input Specification

Input Data
HSC Public Data Release (raw science images, master calibrations)
Assorted public spectroscopic catalogs and high-accuracy photometric redshift catalogs in the HSC PDR footprint.

4.59.6   Output Specification

4.59.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Run DRP processing steps through (at least) final galaxy photometry measurements.
	Test Data	No data.
	Expected Result	
2	Description	Train photometric redshift algorithm(s) on spectroscopic and high-accuracy photometric redshift catalogs.
	Test Data	No data.
	Expected Result	
3	Description	Estimate photometric redshifts for all Objects generated by DRP processing.
	Test Data	No data.
	Expected Result	
4	Description	Load into DRP Database
	Test Data	No data.
	Expected Result	
5	Description	Inspect database to verify that photometric redshifts are present for all objects
	Test Data	No data.
	Expected Result	

4.60   LVV-T69 - Verify implementation of Object Characterization

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T69 in Jira

Rubin Observatory

4.60.1   Verification Elements

• LVV-107 - DMS-REQ-0276-V-01: Object Characterization

4.60.2   Test Items

Verify that Object catalogs produced by the DRP pipeline include all measurements listed in DMS-REQ-0276: a point-source model fit, a bulge-disk model fit, standard colors, a centroid, adap- tive moments, Petrosian and Kron fluxes, surface brightness at multiple apertures, proper motion and parallax, and a variability characterization.

4.60.3   Predecessors

4.60.4   Environment Needs

4.60.4.1   Software

4.60.4.2   Hardware

4.60.5   Input Specification

4.60.6   Output Specification

4.60.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Precursor data, execute DRP, load results, observe catalog contents
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

135

Rubin Observatory

4.61 LVV-T71 - Verify implementation of Detecting extended low surface brightness objects

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T71 in Jira

4.61.1 Verification Elements

- LVV-180 - DMS-REQ-0349-V-01: Detecting extended low surface brightness objects

4.61.2 Test Items

Verify that low-surface brightness objects (including those whose PSF S/N is lower than the detection threshold) are detected in coadds.

4.61.3 Predecessors

4.61.4 Environment Needs

4.61.4.1 Software

4.61.4.2 Hardware

4.61.5 Input Specification

Input Data
HSC "RC2" data (raw science images and master calibrations)

4.61.6 Output Specification

4.61.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	load LSST DM Stack
	Test Data	No data.
	Expected Result	
2	Description	Run the single-frame processing and self-calibration steps of the DRP pipeline.
	Test Data	No data.
	Expected Result	
3	Description	Insert simulated low-surface-brightness galaxies (with exponential profiles) consistently into all calibrated single-epoch images.
	Test Data	No data.
	Expected Result	
4	Description	Run all remaining DRP pipeline steps.
	Test Data	No data.
	Expected Result	
5	Description	Load data into DRP database
	Test Data	No data.
	Expected Result	
6	Description	Verify that the injected simulated objects are recovered at a rate consistent with their S/N and true profile *when not blended with each other or real objects.*
	Test Data	No data.
	Expected Result	

4.62   LVV-T72 - Verify implementation of Coadd Image Method Constraints

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch
		Open LVV-T72 in Jira		

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

137

4.62.1 Verification Elements

- LVV-109 - DMS-REQ-0278-V-01: Coadd Image Method Constraints

4.62.2 Test Items

Verify the implementation of how Coadd images are created.

4.62.3 Predecessors

4.62.4 Environment Needs

4.62.4.1 Software

4.62.4.2 Hardware

4.62.5 Input Specification

4.62.6 Output Specification

4.62.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset that has been processed to create coadd images.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

Rubin Observatory

Step	Description, Input Data and Expected Result	

3	Description	Retrieve the coadds in the dataset and verify that they are non-empty.
	Test Data	No data.
	Expected Result	
4	Description	Verify that coadds were created following specification
	Test Data	No data.
	Expected Result	

4.63   LVV-T73 - Verify implementation of Deep Detection Coadds

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T73 in Jira

4.63.1   Verification Elements

- LVV-110 - DMS-REQ-0279-V-01: Deep Detection Coadds

4.63.2   Test Items

Verify that the DRP pipelines produce a suite of per-band coadded images that are optimized for depth.

4.63.3   Predecessors

4.63.4   Environment Needs

4.63.4.1   Software

Rubin Observatory

4.63.4.2   Hardware

4.63.5   Input Specification

4.63.6   Output Specification

4.63.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Verify through inspection that per-filter coadds exist for each tract+patch possible
	Test Data	No data.
	Expected Result	
3	Description	Verify through inspection that the images used to generate those coadds met specified conditions
	Test Data	No data.
	Expected Result	
4	Description	Visually inspect a subset of the coadds to verify that they visually appear reasonable and to be from good quality data.
	Test Data	No data.
	Expected Result	

4.64   LVV-T74 - Verify implementation of Template Coadds

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Test	Eric Bellm

Open LVV-T74 in Jira

4.64.1 Verification Elements

- LVV-111 - DMS-REQ-0280-V-01: Template Coadds

4.64.2 Test Items

Verify that the DMS can produce Template Coadds for DIA processing.

4.64.3 Predecessors

4.64.4 Environment Needs

4.64.4.1 Software

4.64.4.2 Hardware

4.64.5 Input Specification

4.64.6 Output Specification

4.64.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2	Description	Confirm that the template coadds have been created and are well-formed.
	Test Data	No data.
	Expected Result	

4.65   LVV-T75 - Verify implementation of Multi-band Coadds

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch
		Open LVV-T75 in Jira		

4.65.1   Verification Elements

- LVV-112 - DMS-REQ-0281-V-01: Multi-band Coadds

4.65.2   Test Items

Verify that the DRP pipelines produce multi-band coadds for detection purposes.

4.65.3   Predecessors

4.65.4   Environment Needs

4.65.4.1   Software

Rubin Observatory

4.65.4.2   Hardware

4.65.5   Input Specification

4.65.6   Output Specification

4.65.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Verify that deep detection coadds exist based on all filters.
	Test Data	No data.
	Expected Result	

4.66   LVV-T76 - Verify implementation of All-Sky Visualization of Data Releases

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T76 in Jira

4.66.1   Verification Elements

• LVV-160 - DMS-REQ-0329-V-01: All-Sky Visualization of Data Releases

4.66.2 Test Items

Show that it's possible to produce large area visualizations from Data Release data products.

4.66.3 Predecessors

4.66.4 Environment Needs

4.66.4.1 Software

4.66.4.2 Hardware

4.66.5 Input Specification

Input Data
Dataset of perhaps ~100 square degrees. The first HSC Public Data Release will be used for this test. Larger (in sky area) datasets should be identified for further testing.

4.66.6 Output Specification

4.66.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Run all sky tile generation task to produce the data products necessary for serving the all sky visualization.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Manually perform, and log (including timing where applicable), the following steps against that all sky visualization application. At all steps take special care to note any missing or un-rendered image tiles: 1. Navigate to the all sky viewer and log the URL, browser and version. 2. Zoom to native pixel display (1 image pixel per display pixel) 3. Zoom to fit the full PDR footprint 4. Zoom to 1/4x native resolution 5. Pan to eastern edge of the footprint. 6. Pan to western edge of the footprint. 7. Navigate to the middle of the footprint. 8. Zoom to max magnification
	Test Data	No data.
	Expected Result	

4.67   LVV-T77 - Verify implementation of Best Seeing Coadds

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T77 in Jira

4.67.1   Verification Elements

• LVV-161 - DMS-REQ-0330-V-01: Best Seeing Coadds

4.67.2   Test Items

Verify that the DRP pipelines produce a suite of per-band coadds with input images filtered to optimize the size of the effective PSF on the coadd.

4.67.3   Predecessors

4.67.4 Environment Needs

4.67.4.1 Software

4.67.4.2 Hardware

4.67.5 Input Specification

4.67.6 Output Specification

4.67.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

146

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Explicitly create a coadd for a specified seeing range in each filter.
	Test Data	No data.
	Expected Result	
4	Description	Verify that these coadds exist.
	Test Data	No data.
	Expected Result	

4.68   LVV-T78 - Verify implementation of Persisting Data Products

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T78 in Jira

4.68.1   Verification Elements

- LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products

4.68.2   Test Items

Verify that per-band deep coadds and best-seeing coadds are present, kept, and available.

4.68.3   Predecessors

4.68.4   Environment Needs

4.68.4.1   Software

Rubin Observatory

4.68.4.2 Hardware

4.68.5 Input Specification

Precursor data from HSC PDR.

4.68.6 Output Specification

4.68.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Produce some relevant coadds and store them in the Archive
	Test Data	No data.
	Expected Result	
2	Description	Examine the data retention policies for those products
	Test Data	No data.
	Expected Result	

4.69 LVV-T79 - Verify implementation of PSF-Matched Coadds

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T79 in Jira

4.69.1 Verification Elements

- LVV-166 - DMS-REQ-0335-V-01: PSF-Matched Coadds

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. **– DRAFT NOT YET APPROVED**

148

Rubin Observatory

4.69.2   Test Items

Verify that the DRP pipelines produce PSF matched coadds.

4.69.3   Predecessors

4.69.4   Environment Needs

4.69.4.1   Software

4.69.4.2   Hardware

4.69.5   Input Specification

4.69.6   Output Specification

4.69.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Verify that PSF-matched coadds were created.
	Test Data	No data.
	Expected Result	

4.70   LVV-T80 - Verify implementation of Detecting faint variable objects

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Open LVV-T80 in Jira

4.70.1 Verification Elements

- LVV-168 - DMS-REQ-0337-V-01: Detecting faint variable objects

4.70.2 Test Items

To verify that the Data Release Production pipeline will be able to detect faint sources with long-term variability (e.g., quasars, proper motion stars) via, e.g., shorter timescale coadds (month to a few months).

4.70.3 Predecessors

4.70.4 Environment Needs

4.70.4.1 Software

4.70.4.2 Hardware

4.70.5 Input Specification

Input Data such as:
DECam HiTS data.
Gaia catalog of faint moving objects.
Catalog of spectroscopically confirmed quasars.
(Alternative: input data injected with faint variable sources).

4.70.6 Output Specification

Rubin Observatory

4.70.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Identify 100 objects from Gaia with proper motions high enough to have detectably moved during HSC observations.
	Test Data	No data.
	Expected Result	
4	Description	Measure reported proper motion of these objects in DM Stack processing. Verify that it is consistent with Gaia objects.
	Test Data	No data.
	Expected Result	
5	Description	Identify 100 quasars from color-space or existing extragalactic spectroscopic catalog.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
6	Description	Measure lightcurves of these quasars. Determine if structure function is reasonable (may require at least a year to determine if the structure function of 100 quasars is "reasonable").
	Test Data	No data.
	Expected Result	
7	Description	(Alternative: if faint variable source can be injected into the input data, test to see if they are recovered).
	Test Data	No data.
	Expected Result	(This Alternative would enable us not only to tell if faint variable objects are detected, but exactly which kinds, how faint, and with what efficiency.)

4.71   LVV-T81 - Verify implementation of Targeted Coadds

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jim Bosch

Open LVV-T81 in Jira

4.71.1   Verification Elements

- LVV-169 - DMS-REQ-0338-V-01: Targeted Coadds

4.71.2   Test Items

Verify that small sections of any coadd produced by the DRP pipelines can be retained, even if the full coadd is not.

4.71.3   Predecessors

4.71.4   Environment Needs

4.71.4.1   Software

Rubin Observatory

4.71.4.2   Hardware

4.71.5   Input Specification

4.71.6   Output Specification

4.71.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Remove DR from disk
	Test Data	No data.
	Expected Result	
2	Description	Observe retention of designated coadd sections
	Test Data	No data.
	Expected Result	
3	Description	Observe accessibility of designated coadd sections via simulated DAC LSP instance
	Test Data	No data.
	Expected Result	

4.72   LVV-T82 - Verify implementation of Tracking Characterization Changes Between Data Releases

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Jim Bosch

Open LVV-T82 in Jira

Rubin Observatory

4.72.1 Verification Elements

- LVV-170 - DMS-REQ-0339-V-01: Tracking Characterization Changes Between Data Releases

4.72.2 Test Items

Verify that small-area subsets of a DR can be retained when most of that DR is retired, for comparison with future DRs.

4.72.3 Predecessors

4.72.4 Environment Needs

4.72.4.1 Software

4.72.4.2 Hardware

4.72.5 Input Specification

4.72.6 Output Specification

4.72.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Prepare a second DRP run -> DPDD with different configuration parameters for this second test Data Release.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1064	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	Stage subset of products from first test Data Release to separate storage.
	Test Data	No data.
	Expected Result	
4	Description	Scientifically compare the results of the subset of that region of sky to those in the second test Data Release comparing the results of the DRP Scientific Verification tests.
	Test Data	No data.
	Expected Result	Diagnostic plots quantifying the differences between scientific outputs between the first and second test datasets.

4.73 LVV-T83 - Verify implementation of Bad Pixel Map

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T83 in Jira

4.73.1 Verification Elements

- LVV-22 - DMS-REQ-0059-V-01: Bad Pixel Map

4.73.2 Test Items

Verify that the DMS can produce a map of detector pixels that suffer from pathologies, and that these pathologies are encoded in at least 32-bit values.

4.73.3 Predecessors

4.73.4   Environment Needs

4.73.4.1   Software

4.73.4.2   Hardware

4.73.5   Input Specification

4.73.6   Output Specification

4.73.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Interrogate the calibRegistry for the metadata associated with a bad pixel map, where the validity range contains the date of interest.
	Test Data	No data.
	Expected Result	A bad pixel map for the requested date has been returned.
2	Description	Check that the bad pixel pathologies are encoded as at least 32-bit values, and that the various pathologies are represented by different encoding.
	Test Data	No data.
	Expected Result	Bad pixel values can be decoded to determine their pathologies using their 32-bit values.

4.74   LVV-T84 - Verify implementation of Bias Residual Image

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T84 in Jira

Rubin Observatory

4.74.1   Verification Elements

- LVV-23 - DMS-REQ-0060-V-01: Bias Residual Image

4.74.2   Test Items

Verify that DMS can construct a bias residual image that corrects for temporally-stable bias structures.
Verify that DMS can do this on demand.

4.74.3   Predecessors

4.74.4   Environment Needs

4.74.4.1   Software

4.74.4.2   Hardware

4.74.5   Input Specification

4.74.6   Output Specification

4.74.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify the location of an appropriate precursor dataset.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Butler repo available for reading.

3	Description	Import the standard libraries required for the rest of this test:
	Test Data	No data.
	Example Code	import osimport lsst.afw.display as afwDisplay from lsst.daf.persistence import Butler from lsst.ip.isr import IsrTask from firefly_client import FireflyClient from IPython.display import IFrame
	Expected Result	

4	Description	Ingest the dataset from step 1 using the Butler (e.g., following example code below).
	Test Data	No data.
	Example Code	butler = Butler($REPOSITORY_PATH) raw = butler.get("raw", visit=$VISIT_ID, detector=2) bias = butler.get("bias", visit=$VISIT_ID, detector=2)
	Expected Result	

5	Description	Display the bias image and inspect that its pixels contain unique values.
	Test Data	No data.
	Expected Result	A relatively flat image showing the bias level with roughly Poisson noise.

6	Description	Configure and run an Instrument Signature Removal (ISR) task on the raw data. Most corrections are disabled for simplicity, but the bias frame is applied.
	Test Data	No data.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

158

Rubin Observatory

Step		Description, Input Data and Expected Result
	Example Code	isr_config = IsrTask.ConfigClass() isr_config.doDark=False isr_config.doFlat=False isr_config.doFringe=False isr_config.doDefect=False isr_config.doAddDistortionModel=False isr_config.doLinearize=False isr = IsrTask(config=isr_config) result = isr.run(raw, bias=bias)
	Expected Result	A trimmed, bias-corrected image in 'result'.
7	Description	Display the 'result' image and confirm that the bias correction has been performed.
	Test Data	No data.
	Expected Result	A displayed image with bias removed (i.e., typical background counts reduced relative to the raw frame).

4.75   LVV-T85 - Verify implementation of Crosstalk Correction Matrix

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T85 in Jira

4.75.1   Verification Elements

- LVV-24 - DMS-REQ-0061-V-01: Crosstalk Correction Matrix

4.75.2   Test Items

Verify that the DMS can generate a cross-talk correction matrix from appropriate calibration data.
Verify that the DMS can measure the effectiveness of the cross-talk correction matrix.

4.75.3   Predecessors

Rubin Observatory

4.75.4   Environment Needs

4.75.4.1   Software

4.75.4.2   Hardware

4.75.5   Input Specification

4.75.6   Output Specification

4.75.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify an appropriate calibration dataset that can be used to derive the crosstalk correction matrix.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Confirm that the crosstalk correction matrix is produced and persisted.
	Test Data	No data.
	Expected Result	A correction matrix quantifying what fraction of the signal detected in any given amplifier on each sensor in the focal plane appears in any other amplifier.

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Apply the crosstalk correction to simulated images, and confirm that the correction is performing as expected.
	Test Data	No data.
	Expected Result	A noticeable difference between images before and after applying the correction.

4.76   LVV-T86 - Verify implementation of Illumination Correction Frame

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Lupton

Open LVV-T86 in Jira

4.76.1   Verification Elements

• LVV-25 - DMS-REQ-0062-V-01: Illumination Correction Frame

4.76.2   Test Items

Verify that the DMS can produce an illumination correction frame calibration product.
Verify that the DMS can determine the effectiveness of an illumination correction and determine how often it should be updated.

4.76.3   Predecessors

4.76.4   Environment Needs

4.76.4.1   Software

4.76.4.2   Hardware

Rubin Observatory

4.76.5 Input Specification

4.76.6 Output Specification

4.76.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to CPP
	Test Data	No data.
	Expected Result	

4.77 LVV-T87 - Verify implementation of Monochromatic Flatfield Data Cube

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Lupton

Open LVV-T87 in Jira

4.77.1 Verification Elements

- LVV-26 - DMS-REQ-0063-V-01: Monochromatic Flatfield Data Cube

4.77.2 Test Items

Verify that the DMS can generate a calibration image/cube that corrects for pixel-to-pixel wavelength-dependent detector response.
Verify that the DMS can measure the effectiveness of this monochromatic flatfield data cube.

4.77.3 Predecessors

4.77.4   Environment Needs

4.77.4.1   Software

4.77.4.2   Hardware

4.77.5   Input Specification

4.77.6   Output Specification

4.77.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to CPP
	Test Data	No data.
	Expected Result	

4.78   LVV-T88 - Verify implementation of Calibration Data Products

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T88 in Jira

4.78.1   Verification Elements

- LVV-57 - DMS-REQ-0130-V-01: Calibration Data Products

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

163

4.78.2 Test Items

Verify that the DMS can produce and archive the required Calibration Data Products: cross talk correction, bias, dark, monochromatic dome flats, broad-band flats, fringe correction, and illumination corrections.

4.78.3 Predecessors

4.78.4 Environment Needs

4.78.4.1 Software

4.78.4.2 Hardware

4.78.5 Input Specification

4.78.6 Output Specification

4.78.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a suitable set of calibration frames, including biases, dark frames, and flat-field frames.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	

	Description	Confirm that the expected data products are created, and that they have the expected properties.
3	Test Data	No data.
	Expected Result	A full set of calibration data products has been created, and they are well-formed.
	Description	Test that the calibration products are archived, and can readily be applied to science data to produce the desired corrections.
4	Test Data	No data.
	Expected Result	Confirmation that application of the calibration products to processed data has the desired effects.

4.79   LVV-T89 - Verify implementation of Calibration Image Provenance

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T89 in Jira

4.79.1   Verification Elements

- LVV-59 - DMS-REQ-0132-V-01: Calibration Image Provenance

- LVV-1234 - OSS-REQ-0122-V-01: Provenance

4.79.2   Test Items

Verify that the DMS records the required provenance information for the Calibration Data Products.

4.79.3   Predecessors

Rubin Observatory

4.79.4   Environment Needs

4.79.4.1   Software

4.79.4.2   Hardware

4.79.5   Input Specification

4.79.6   Output Specification

4.79.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest an appropriate precursor calibration dataset into a Butler repo.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Load the relevant database/Butler data product, and observe that all provenance information has been retained.
	Test Data	No data.
	Expected Result	A dataset consisting of calibration images, with provenance information recorded and properly associated with the calibration images.

4.80   LVV-T90 - Verify implementation of Dark Current Correction Frame

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T90 in Jira

4.80.1   Verification Elements

- LVV-113 - DMS-REQ-0282-V-01: Dark Current Correction Frame Creation

4.80.2   Test Items

Verify that the DMS can produce a dark correction frame calibration product.

4.80.3   Predecessors

4.80.4   Environment Needs

4.80.4.1   Software

4.80.4.2   Hardware

4.80.5   Input Specification

4.80.6   Output Specification

4.80.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify the path to a dataset containing dark frames (i.e., exposures taken with the shutter closed).
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	Execute the relevant steps from 'cp_pipe' (the calibration pipeline) to produce dark correction frames.
	Test Data	No data.
	Expected Result	
3	Description	Inspect the resulting dark correction frame to confirm that it appears as expected.
	Test Data	No data.
	Expected Result	A well-formed dark correction frame is present and accessible via the Data Butler.

4.81   LVV-T91 - Verify implementation of Fringe Correction Frame

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Lupton

Open LVV-T91 in Jira

4.81.1   Verification Elements

• LVV-114 - DMS-REQ-0283-V-01: Fringe Correction Frame

4.81.2   Test Items

Verify that the DMS can produce an fringe-correction frame calibration product.
Verify that the DMS can determine the effectiveness of the fringe-correction frame and determine how often it should be updated.

4.81.3   Predecessors

Rubin Observatory

4.81.4 Environment Needs

4.81.4.1 Software

4.81.4.2 Hardware

4.81.5 Input Specification

4.81.6 Output Specification

4.81.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to CPP
	Test Data	No data.
	Expected Result	

4.82 LVV-T92 - Verify implementation of Processing of Data From Special Programs

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Open LVV-T92 in Jira

4.82.1 Verification Elements

- LVV-151 - DMS-REQ-0320-V-01: Processing of Data From Special Programs

4.82.2   Test Items

For a simulated night of observing that includes some special program observations, show that the SP observations are reduced using their designated reconfigured pipelines (i.e., that the image metadata is sufficient to trigger the processing and include all other relevant images in the processing).

4.82.3   Predecessors

4.82.4   Environment Needs

4.82.4.1   Software

4.82.4.2   Hardware

4.82.5   Input Specification

A variety of imaging data from Special Programs, including these scenarios:
(1) Special Programs data that can be processed by the Prompt pipeline (i.e., standard visits)
(2) Special Programs data that requires 'real-time' (~24) processing with a reconfigured pipeline (e.g., DDF imaging sequence)
(3) Special Programs data that can (should) be processed by the Data Release pipeline (e.g., North Ecliptic Spur standard visits)

4.82.6   Output Specification

4.82.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	(1) Special Programs data that can be processed by the Prompt pipeline (i.e., standard visits). Check that all images with the header keyword for SP were processed by the Prompt pipeline. Check that the Prompt pipeline's data products – DIASource, DIAObject catalogs and the Alerts – contain items flagged with their origin as that SP.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	(2) Special Programs data that requires 'real-time' (~24) processing with a reconfigured pipeline (e.g., DDF imaging sequence) Check that all images with the header keywords for a given SP were processed by their reconfigured pipeline. Check that the pipeline's data products have been updated, and passed their QA.
	Test Data	No data.
	Expected Result	
3	Description	(3) Special Programs data that can (should) be processed by the Data Release pipeline (e.g., North Ecliptic Spur standard visits). SP data would be added manually to the DRP processing. Check that the DRP's data products – Source, Object, CoAdds – contain items flagged as originating in that SP.
	Test Data	No data.
	Expected Result	

4.83 LVV-T93 - Verify implementation of Level 1 Processing of Special Programs Data

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Open LVV-T93 in Jira

4.83.1 Verification Elements

• LVV-152 - DMS-REQ-0321-V-01: Level 1 Processing of Special Programs Data

Rubin Observatory

4.83.2   Test Items

Execute multi-day operations rehearsal. Observe whether Prompt Processing data products generated in time and confirm whether processing has completed before the start of the next simulated night.

4.83.3   Predecessors

4.83.4   Environment Needs

4.83.4.1   Software

4.83.4.2   Hardware

4.83.5   Input Specification

Imaging data obtained under a Special Program: for example, a sequence of consecutive images of a deep drilling field.

4.83.6   Output Specification

4.83.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	If imaging data for a Special Program that requires processing with the Prompt pipeline was obtained the previous night, check that there exist DIASources/Objects/Alerts with flags that they originated from the Special Program.
	Test Data	No data.
	Expected Result	
2	Description	If imaging data for a Special Program that requires prompt processing with a reconfigured pipeline was obtained the previous night, check that the relevant data products have been updated.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
	Expected
	Result

4.84 LVV-T94 - Verify implementation of Special Programs Database

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Open LVV-T94 in Jira

4.84.1 Verification Elements

- LVV-153 - DMS-REQ-0322-V-01: Special Programs Database

4.84.2 Test Items

To confirm that data products from Special Programs are based solely on images obtained as part of SP via, e.g., metadata queries. To confirm that the SP data products can be joined to Prompt and DRP products by attempting to do so via, e.g., coordinate table joins, and attempting to e.g., find the faint counterparts in a Deep Drilling stack to variables with no Object detections in the DRP coadds.

4.84.3 Predecessors

4.84.4 Environment Needs

4.84.4.1 Software

4.84.4.2 Hardware

4.84.5   Input Specification

Databases created by reconfigured pipelines for processing Special Programs data (e.g., DIAObject/DIASource catalogs for a Deep Drilling Field).

4.84.6   Output Specification

4.84.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	SP data product: DDF DIAObjects catalog Non-SP data product: WFD DIAObjects catalog Test: join the two catalogs by coordinate (e.g., to get a longer time baseline for variable stars in the DDF)
	Test Data	No data.
	Expected Result	
2	Description	SP data product: DDF Objects catalog Non-SP data product: WFD DIAObjects catalog Test: join the two catalogs by coordinate to identify faint host galaxies of transients found in WFD
	Test Data	No data.
	Expected Result	

4.85   LVV-T95 - Verify implementation of Constraints on Level 1 Special Program Products Generation

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Melissa Graham

Open LVV-T95 in Jira

4.85.1   Verification Elements

- LVV-175 - DMS-REQ-0004-V-01: Time to L1 public release

- LVV-1276 - OSS-REQ-0127-V-01: Level 1 Data Product Availability

4.85.2   Test Items

Execute single-day operations rehearsal. Observe Prompt Processing data products generated in time. Confirm that data from Special Programs is processed with the same latency as required for main survey data: release of public data within L1publicT and Alerts within OTT1.

4.85.3   Predecessors

4.85.4   Environment Needs

4.85.4.1   Software

4.85.4.2   Hardware

4.85.5   Input Specification

Data from a Special Program that is appropriate for the Prompt pipeline (i.e., a Deep Drilling type series of standard visits from a non-crowded field).

4.85.6   Output Specification

4.85.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
2	Description	Confirm that Special Program prompt data products have been generated within 24 hours.
	Test Data	No data.
	Expected Result	

4.86   LVV-T96 - Verify implementation of Query Repeatability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T96 in Jira

4.86.1   Verification Elements

- LVV-122 - DMS-REQ-0291-V-01: Query Repeatability

4.86.2   Test Items

Verify that prior queries can be rerun with identical results, or with new additional data for live (Alert Production) databases.

4.86.3   Predecessors

Rubin Observatory

4.86.4   Environment Needs

4.86.4.1   Software

4.86.4.2   Hardware

4.86.5   Input Specification

4.86.6   Output Specification

4.86.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Select and download (deterministic) random subsample of records from Data Release Object and Source tables.
	Test Data	No data.
	Expected Result	
2	Description	Select and download random subsample of PPDB DIAObject and DIASource tables.
	Test Data	No data.
	Expected Result	
3	Description	As appropriate, wait for some amount of non-trivial database usage to occur, such as Prompt Processing ingestion or ingestion of other DRP database tables.
	Test Data	No data.
	Expected Result	
4	Description	Re-run the queries in steps 1 and 2 and verify that the resulting data are identical.
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.87 LVV-T97 - Verify implementation of Uniqueness of IDs Across Data Releases

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T97 in Jira

4.87.1 Verification Elements

- LVV-123 - DMS-REQ-0292-V-01: Uniqueness of IDs Across Data Releases

4.87.2 Test Items

Verify that the IDs of Objects, Sources, DIAObjects, and DIASources from different Data Releases are unique.

4.87.3 Predecessors

4.87.4 Environment Needs

4.87.4.1 Software

4.87.4.2 Hardware

4.87.5 Input Specification

4.87.6 Output Specification

4.87.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Identify an appropriate precursor dataset to be processed through Data Release Production.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1064	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	
	Expected Result	
3-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
4	Description	After running the DRP payload multiple times, load the resulting data products (both data release and prompt products) using the Butler.
	Test Data	No data.
	Expected Result	Multiple datasets resulting from processing of the same input data.
5	Description	Inspect the IDs in the multiple data products and confirm that all IDs are unique.
	Test Data	No data.
	Expected Result	No IDs are repeated between multiple processings of the identical input dataset.

4.88   LVV-T98 - Verify implementation of Selection of Datasets

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T98 in Jira

Rubin Observatory

4.88.1 Verification Elements

- LVV-124 - DMS-REQ-0293-V-01: Selection of Datasets

4.88.2 Test Items

Verify that the DMS can identify and retrieve datasets consisting of logical groupings of Exposures, metadata, provenance, etc., or other groupings that are processed or produced as a logical unit.

4.88.3 Predecessors

4.88.4 Environment Needs

4.88.4.1 Software

4.88.4.2 Hardware

4.88.5 Input Specification

4.88.6 Output Specification

4.88.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Ingest data from an appropriate processed dataset.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	Observe retrieval of single Processed Visit Image (PVI) with metadata.
	Test Data	No data.
	Expected Result	A PVI and its associated metadata.
4	Description	Observe retrieval of multiple PVIs with metadata.
	Test Data	No data.
	Expected Result	A set of PVIs and their associated metadata.
5	Description	Observe retrieval of coadd patch with metadata and provenance information.
	Test Data	No data.
	Expected Result	An image of coadded data in a patch, along with its metadata and information describing the provenance of the patch constituents.
6	Description	Observe retrieval of subset of rows in each of the above catalogs.
	Test Data	No data.
	Expected Result	

4.89   LVV-T99 - Verify implementation of Processing of Datasets

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T99 in Jira

4.89.1   Verification Elements

• LVV-125 - DMS-REQ-0294-V-01: Processing of Datasets

4.89.2 Test Items

Execute AP and DRP, simulate failures, observe correct processing

4.89.3 Predecessors

4.89.4 Environment Needs

4.89.4.1 Software

4.89.4.2 Hardware

4.89.5 Input Specification

4.89.6 Output Specification

4.89.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute AP and DRP
	Test Data	No data.
	Expected Result	
2	Description	Simulate failures
	Test Data	No data.
	Expected Result	
3	Description	Observe correct processing
	Test Data	No data.
	Expected Result	

4.90   LVV-T100 - Verify implementation of Transparent Data Access

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T100 in Jira

4.90.1   Verification Elements

- LVV-126 - DMS-REQ-0295-V-01: Transparent Data Access

4.90.2   Test Items

Test Items

Observe dataset retrieval from multiple LSP instances

4.90.3   Predecessors

4.90.4   Environment Needs

4.90.4.1   Software

4.90.4.2   Hardware

4.90.5   Input Specification

4.90.6   Output Specification

4.90.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Observe dataset retrieval from multiple LSP instances
	Test Data	No data.
	Expected Result	

4.91 LVV-T101 - Verify implementation of Transient Alert Distribution

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T101 in Jira

4.91.1 Verification Elements

• LVV-3 - DMS-REQ-0002-V-01: Transient Alert Distribution

4.91.2 Test Items

Precursor or simulated data, execute AP, observe distribution to simulated clients using standard protocols

4.91.3 Predecessors

4.91.4 Environment Needs

4.91.4.1 Software

4.91.4.2 Hardware

Rubin Observatory

4.91.5   Input Specification

Obtain precursor or simulated data; duplicated by LVV-T217 – delete?

4.91.6   Output Specification

4.91.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute AP
	Test Data	No data.
	Expected Result	
2	Description	Observe distribution to simulated clients using standard protocols
	Test Data	No data.
	Expected Result	

4.92   LVV-T102 - Verify implementation of Solar System Objects Available Within Specified Time

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T102 in Jira

4.92.1   Verification Elements

• LVV-36 - DMS-REQ-0089-V-01: Solar System Objects Available Within Specified Time

• LVV-1276 - OSS-REQ-0127-V-01: Level 1 Data Product Availability

• LVV-9803 - DMS-REQ-0004-V-03: Time to availability of Solar System Object orbits

Rubin Observatory

4.92.2 Test Items

Execute single-day operations rehearsal, observe data products generated in time

4.92.3 Predecessors

4.92.4 Environment Needs

4.92.4.1 Software

4.92.4.2 Hardware

4.92.5 Input Specification

4.92.6 Output Specification

4.92.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal
	Test Data	No data.
	Expected Result	
2	Description	Observe data products generated in time
	Test Data	No data.
	Expected Result	

4.93 LVV-T103 - Verify implementation of Generate Data Quality Report Within Specified Time

Version	Status	Priority	Verification Type	Owner

1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T103 in Jira

4.93.1 Verification Elements

- LVV-38 - DMS-REQ-0096-V-01: Generate Data Quality Report Within Specified Time

4.93.2 Test Items

Verify that the DMS can generate a nightly L1 Data Quality Report within **dqReportCom-plTime = 4[hour]**, in both human- and machine-readable formats.

4.93.3 Predecessors

4.93.4 Environment Needs

4.93.4.1 Software

4.93.4.2 Hardware

4.93.5 Input Specification

4.93.6 Output Specification

4.93.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	After **dqReportComplTime = 4[hour]** has passed, confirm (via timestamps) that the data quality report has been generated within **dqReportComplTime = 4[hour],** and that it contains the correct contents.
	Test Data	No data.
	Expected Result	Both human- and machine-readable versions of the L1 Data Quality Report are available with dqReportComplTime.

4.94   LVV-T104 - Verify implementation of Generate DMS Performance Report Within Specified Time

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T104 in Jira

4.94.1   Verification Elements

• LVV-40 - DMS-REQ-0098-V-01: Generate DMS Performance Report Within Specified Time

4.94.2   Test Items

Verify that the DMS can generate a nightly Perfomance Report within perfReportComplTime

4.94.3   Predecessors

4.94.4   Environment Needs

4.94.4.1   Software

4.94.4.2   Hardware

Rubin Observatory

4.94.5 Input Specification

4.94.6 Output Specification

4.94.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal
	Test Data	No data.
	Expected Result	
2	Description	Observe performance report is generated on time and with correct contents
	Test Data	No data.
	Expected Result	

4.95 LVV-T105 - Verify implementation of Generate Calibration Report Within Specified Time

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T105 in Jira

4.95.1 Verification Elements

- LVV-42 - DMS-REQ-0100-V-01: Generate Calibration Report Within Specified Time

4.95.2 Test Items

Verify that the DMS can generate a night Calibration Report in both human-readable and machine-parseable forms.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

189

Rubin Observatory

4.95.3   Predecessors

4.95.4   Environment Needs

4.95.4.1   Software

4.95.4.2   Hardware

4.95.5   Input Specification

4.95.6   Output Specification

4.95.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal
	Test Data	No data.
	Expected Result	
2	Description	Observe calibration report is generated on time and with correct contents
	Test Data	No data.
	Expected Result	

4.96   LVV-T106 - Verify implementation of Calibration Images Available Within Specified Time

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim
Open LVV-T106 in Jira				

Rubin Observatory

4.96.1 Verification Elements

- LVV-58 - DMS-REQ-0131-V-01: Time allowed to process calibs

4.96.2 Test Items

Execute single-day operations rehearsal, observe data products generated

4.96.3 Predecessors

4.96.4 Environment Needs

4.96.4.1 Software

4.96.4.2 Hardware

4.96.5 Input Specification

4.96.6 Output Specification

4.96.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset of raw calibration exposures containing at least **nCalExpProc = 25** exposures. (If it contains more than 25 exposures, use only 25 for the test.)
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1059	Description	Execute the Daily Calibration Products Update payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2-2 from LVV-T1059	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	

3	Description	Confirm that the processing completed successfully within **calProcTime = 1200 seconds.**
	Test Data	No data.
	Expected Result	Calibration products resulting from processed raw calibration exposures are present within calProcTime, and are well-formed images.

4.97   LVV-T107 - Verify implementation of Level-1 Production Completeness

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T107 in Jira

4.97.1   Verification Elements

- LVV-115 - DMS-REQ-0284-V-01: Level-1 Production Completeness

4.97.2   Test Items

Verify that the DMS successfully processes all images of sufficiently quality for processing are eventually processed even after connectivity failures.

4.97.3   Predecessors

LVV-T284

Rubin Observatory

4.97.4   Environment Needs

4.97.4.1   Software

4.97.4.2   Hardware

4.97.5   Input Specification

4.97.6   Output Specification

4.97.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Ingest raw data while simulating failures and outages, observe eventual recovery
	Test Data	No data.
	Expected Result	

4.98   LVV-T108 - Verify implementation of Level 1 Source Association

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T108 in Jira

4.98.1   Verification Elements

- LVV-116 - DMS-REQ-0285-V-01: Level 1 Source Association

4.98.2   Test Items

Verify that the DMS associates DIASources into a DIAObject or SSObject.

Rubin Observatory

4.98.3 Predecessors

4.98.4 Environment Needs

4.98.4.1 Software

4.98.4.2 Hardware

4.98.5 Input Specification

4.98.6 Output Specification

4.98.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to AP
	Test Data	No data.
	Expected Result	

4.99 LVV-T109 - Verify implementation of SSObject Precovery

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T109 in Jira

4.99.1 Verification Elements

• LVV-117 - DMS-REQ-0286-V-01: SSObject Precovery

4.99.2 Test Items

Verify that the DMS associates additional DIAObjects (both forward and back in time) with objects classified as SSObjects.

4.99.3 Predecessors

4.99.4 Environment Needs

4.99.4.1 Software

4.99.4.2 Hardware

4.99.5 Input Specification

4.99.6 Output Specification

4.99.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to AP
	Test Data	No data.
	Expected Result	

4.100 LVV-T110 - Verify implementation of DIASource Precovery

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T110 in Jira

Rubin Observatory

4.100.1   Verification Elements

- LVV-118 - DMS-REQ-0287-V-01: Max look-back time for precovery

4.100.2   Test Items

Verify that DMS performs forced photometry for new DIAObjects at all available images within the precoveryWindow.

4.100.3   Predecessors

4.100.4   Environment Needs

4.100.4.1   Software

4.100.4.2   Hardware

4.100.5   Input Specification

4.100.6   Output Specification

4.100.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal, observe data products generated in time
	Test Data	No data.
	Expected Result	

4.101   LVV-T111 - Verify implementation of Use of External Orbit Catalogs

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

| 1 | Draft | Normal | Test | Eric Bellm |

Open LVV-T111 in Jira

4.101.1 Verification Elements

- LVV-119 - DMS-REQ-0288-V-01: Use of External Orbit Catalogs

4.101.2 Test Items

Verify that the DMS can make use of external catalogs to improve identification of SSObjects.

4.101.3 Predecessors

4.101.4 Environment Needs

4.101.4.1 Software

4.101.4.2 Hardware

4.101.5 Input Specification

4.101.6 Output Specification

4.101.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to AP
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.102   LVV-T112 - Verify implementation of Alert Filtering Service

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T112 in Jira

4.102.1   Verification Elements

- LVV-173 - DMS-REQ-0342-V-01: Alert Filtering Service

4.102.2   Test Items

Verify that user-defined filters can be used to generate a basic alert filtering service.

4.102.3   Predecessors

4.102.4   Environment Needs

4.102.4.1   Software

4.102.4.2   Hardware

4.102.5   Input Specification

4.102.6   Output Specification

4.102.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a suitable precursor dataset for processing through the Alert Production pipeline.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame process-ing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	Confirm that alerts are generated, and that an Alert Distribution service is making them available via a stream.
	Test Data	No data.
	Expected Result	Via either a UI or API, confirmation that a stream of alerts are available.
4	Description	Confirm that a UI (or API) exists that allows users to define simple filters. Define a fil-ter, and observe both the full and the filtered alert streams to confirm that the filter has reduced the volume of alerts.
	Test Data	No data.
	Expected Result	The user-defined filter has reduced the number of alerts being received relative to the full stream.

4.103   LVV-T113 - Verify implementation of Performance Requirements for LSST Alert Filtering Service

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T113 in Jira

Rubin Observatory

4.103.1   Verification Elements

- LVV-174 - DMS-REQ-0343-V-01: Number of full-size alerts

4.103.2   Test Items

Verify that the DMS alert filter service provides sufficient bandwidth for **numBrokerUsers = 100** simultaneously-operating brokers to receive up to **numBrokerAlerts = 20** alerts per visit.

4.103.3   Predecessors

4.103.4   Environment Needs

4.103.4.1   Software

4.103.4.2   Hardware

4.103.5   Input Specification

4.103.6   Output Specification

4.103.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Create a simulated alert stream.
	Test Data	No data.
	Expected Result	
2	Description	Simultaneously execute user-defined alert filters for at least **numBrokerUsers = 100** users, and confirm that the system successfully filters the stream as requested. Confirm that the bandwidth requirement of **numBrokerAlerts = 20** per user was met.
	Test Data	No data.
	Expected Result	All of the (simulated) users successfully receive their requested filtered alerts, with **numBrokerAlerts = 20** per user.

Rubin Observatory

Step	Description, Input Data and Expected Result

4.104 LVV-T114 - Verify implementation of Pre-defined alert filters

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T114 in Jira

4.104.1 Verification Elements

- LVV-179 - DMS-REQ-0348-V-01: Pre-defined alert filters

4.104.2 Test Items

Verify that users of the Alert Filtering service can use a predefined set of filters.

4.104.3 Predecessors

4.104.4 Environment Needs

4.104.4.1 Software

4.104.4.2 Hardware

4.104.5 Input Specification

4.104.6 Output Specification

4.104.7 Test Procedure

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

201

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Create a simulated alert stream. Confirm that alerts are generated, and that an Alert Distribution service is making them available.
	Test Data	No data.
	Expected Result	A stream of alerts that is confirmed to be generated and distributed.
2	Description	Confirm that a UI (or API) exists that presents users some pre-defined filters.
	Test Data	No data.
	Expected Result	The UI (or API) for accessing alert streams has some pre-defined filters available for users.
3	Description	Select one of the pre-defined filters, and confirm that the results have been properly filtered.
	Test Data	No data.
	Expected Result	After applying the pre-defined filter, the number of alerts has decreased relative to the raw stream.

4.105 LVV-T115 - Verify implementation of Calibration Production Processing

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Kian-Tat Lim

Open LVV-T115 in Jira

4.105.1 Verification Elements

• LVV-120 - DMS-REQ-0289-V-01: Calibration Production Processing

4.105.2 Test Items

Execute CPP on a variety of representative cadences, and verify that the calibration pipeline correctly produces necessary calibration products.

4.105.3 Predecessors

Rubin Observatory

4.105.4   Environment Needs

4.105.4.1   Software

4.105.4.2   Hardware

4.105.5   Input Specification

4.105.6   Output Specification

4.105.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a suitable set of calibration frames, including biases, dark frames, and flat-field frames.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Confirm that the expected data products are created, and that they have the expected properties.
	Test Data	No data.
	Expected Result	Repos containing valid calibration products that are well-formed and ready to be applied to processed datasets.

4.106 LVV-T116 - Verify implementation of Associating Objects across data releases

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T116 in Jira

4.106.1 Verification Elements

- LVV-181 - DMS-REQ-0350-V-01: Associating Objects across data releases

4.106.2 Test Items

Load DR, observe queryable association

4.106.3 Predecessors

4.106.4 Environment Needs

4.106.4.1 Software

4.106.4.2 Hardware

4.106.5 Input Specification

4.106.6 Output Specification

4.106.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Load DR
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
2	Description	Observe queryable association
	Test Data	No data.
	Expected Result	

4.107   LVV-T117 - Verify implementation of DAC resource allocation for Level 3 processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T117 in Jira

4.107.1   Verification Elements

- LVV-47 - DMS-REQ-0119-V-01: DAC resource allocation for Level 3 processing

4.107.2   Test Items

Verify that compute time and storage space allocations can be granted to science users.

4.107.3   Predecessors

4.107.4   Environment Needs

4.107.4.1   Software

4.107.4.2   Hardware

Rubin Observatory

4.107.5   Input Specification

4.107.6   Output Specification

4.107.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Create a test user account for the Science Platform.
	Test Data	No data.
	Expected Result	
2	Description	Set the LSP resource allocations for the test user to very low values.
	Test Data	No data.
	Expected Result	
3	Description	Initiate example batch jobs and notebook sessions that will exceed the specified resource limits.
	Test Data	No data.
	Expected Result	Quota error.
4	Description	Transfer sufficient data volumes into the user workspace and MyDB tables that would exceed the resource quotas.
	Test Data	No data.
	Expected Result	Quota error.
5	Description	Reset the user resource quotas to normal values.
	Test Data	No data.
	Expected Result	
6	Description	Initiate the same example batch jobs and notebook sessions that previously caused an error.
	Test Data	No data.
	Expected Result	Successful notebook and batch job execution.
7	Description	Transfer the same data volumes into the user workspace and MyDB tables that previously caused an error.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	Successful data transfer.

4.108 LVV-T118 - Verify implementation of Level 3 Data Product Self Consistency

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T118 in Jira

4.108.1 Verification Elements

- LVV-48 - DMS-REQ-0120-V-01: Level 3 Data Product Self Consistency

4.108.2 Test Items

Verify that user-driven Level 3 processing is conducted on consistent sets of input data.

4.108.3 Predecessors

4.108.4 Environment Needs

4.108.4.1 Software

4.108.4.2 Hardware

4.108.5 Input Specification

Rubin Observatory

4.108.6   Output Specification

4.108.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute representative processing on DR in PDAC, observe consistency
	Test Data	No data.
	Expected Result	

4.109   LVV-T119 - Verify implementation of Provenance for Level 3 processing at DACs

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T119 in Jira

4.109.1   Verification Elements

- LVV-49 - DMS-REQ-0121-V-01: Provenance for Level 3 processing at DACs
- LVV-1234 - OSS-REQ-0122-V-01: Provenance

4.109.2   Test Items

Verify that provenance information is recorded and accessible for user-generated Level 3 products.

4.109.3   Predecessors

4.109.4   Environment Needs

4.109.4.1   Software

Rubin Observatory

4.109.4.2   Hardware

4.109.5   Input Specification

4.109.6   Output Specification

4.109.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute representative processing on DR in PDAC, observe provenance recording
	Test Data	No data.
	Expected Result	

4.110   LVV-T120 - Verify implementation of Software framework for Level 3 catalog processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T120 in Jira

4.110.1   Verification Elements

- LVV-53 - DMS-REQ-0125-V-01: Software framework for Level 3 catalog processing

4.110.2   Test Items

Verify that user-driven Level 3 processing can be consistently applied to all records in a catalog.

4.110.3   Predecessors

Rubin Observatory

4.110.4   Environment Needs

4.110.4.1   Software

4.110.4.2   Hardware

4.110.5   Input Specification

4.110.6   Output Specification

4.110.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute representative processing on DR in PDAC, observe recognition of and recovery from failures
	Test Data	No data.
	Expected Result	

4.111   LVV-T121 - Verify implementation of Software framework for Level 3 image processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T121 in Jira

4.111.1   Verification Elements

• LVV-56 - DMS-REQ-0128-V-01: Software framework for Level 3 image processing

Rubin Observatory

4.111.2   Test Items

Verify that user-specified Level 3 processing can be applied to the desired set of images.

4.111.3   Predecessors

4.111.4   Environment Needs

4.111.4.1   Software

4.111.4.2   Hardware

4.111.5   Input Specification

4.111.6   Output Specification

4.111.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute representative processing on DR in PDAC, observe recognition of and recovery from failures
	Test Data	No data.
	Expected Result	

4.112   LVV-T122 - Verify implementation of Level 3 Data Import

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T122 in Jira

Rubin Observatory

4.112.1 Verification Elements

- LVV-121 - DMS-REQ-0290-V-01: Level 3 Data Import

4.112.2 Test Items

Verify that the Science Platform can ingest data from community-standard file formats.

4.112.3 Predecessors

4.112.4 Environment Needs

4.112.4.1 Software

4.112.4.2 Hardware

4.112.5 Input Specification

4.112.6 Output Specification

4.112.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Use the Science Platform catalog upload tool to ingest a small example FITS table.
	Test Data	No data.
	Expected Result	
2	Description	Use the Science Platform catalog upload tool to ingest a small example CSV table.
	Test Data	No data.
	Expected Result	
3	Description	Use the Science Platform catalog upload tool to ingest a large FITS table that needs to be spatially-sharded in the database.

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
4	Description	Perform example queries on each of the three tables to verify that all data is present.
	Test Data	No data.
	Expected Result	Data returned in the queries is identical to the data uploaded.

4.113 LVV-T123 - Verify implementation of Access Controls of Level 3 Data Products

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T123 in Jira

4.113.1 Verification Elements

• LVV-171 - DMS-REQ-0340-V-01: Access Controls of Level 3 Data Products

4.113.2 Test Items

This test touches upon the interface between the following areas: IT Security, Identity Management, LSP Portal, and Parallel Distributed Database. The purpose is to show that access to user generated data products (previously Level 3) can have a variety of access restrictions varying from single-user, a list, a named group, or open access.

4.113.3 Predecessors

4.113.4 Environment Needs

4.113.4.1 Software

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. **– DRAFT NOT YET APPROVED**

213

Rubin Observatory

4.113.4.2　Hardware

4.113.5　Input Specification

4.113.6　Output Specification

4.113.7　Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Configure representative access controls in PDAC, observe proper restrictions
	Test Data	No data.
	Expected Result	

4.114　LVV-T124 - Verify implementation of Software Architecture to Enable Community Re-Use

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Simon Krughoff

Open LVV-T124 in Jira

4.114.1　Verification Elements

• LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

4.114.2　Test Items

Show that the LSST software is capable of being executed in multiple contexts: single user instance, batch processing, continuous integration.
Also show that the algorithms can be reconfigured and, if desired, completely replaced at run time.

Rubin Observatory

4.114.3   Predecessors

4.114.4   Environment Needs

4.114.4.1   Software

4.114.4.2   Hardware

4.114.5   Input Specification

4.114.6   Output Specification

4.114.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Using curated test datasets for multiple precursor instruments, verify and log that the prototype DRP pipelines execute successfully in three contexts: 1. The CI system 2. On a single user system: laptop, desktop, or notebook running in the Notebook aspect of the LSP. 3. Project workflow system.
	Test Data	No data.
	Expected Result	
3	Description	Using a template testing notebook in the Notebook aspect of the LSP, verify and log the following: 1. Individual pipeline steps (tasks) are importable and executable on their own. this is not comprehensive, but demonstrative. 2. Individual pipeline steps may be overridden by configuration. 3. Users can implement a custom pipeline step and insert i into the processing flow via configuration.
	Test Data	No data.
	Expected Result	
4-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
5	Description	Read the resulting dataset using the Bulter, and confirm that it produced the desired data products.
	Test Data	No data.
	Expected Result	
6	Description	Run subset of full DRP from previous step on an individual node. Was this organizationally easy? Did the performance scale appropriately?
	Test Data	No data.
	Expected Result	
7	Description	Re-run aperture correction on subset. Verify that same results as DRP run are achieved.

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
8	Description	Re-run photometric redshift estimation algorithm on subset coadd catalogs. Verify that same results are achieved as from full DRP.
	Test Data	No data.
	Expected Result	

4.115 LVV-T125 - Verify implementation of Simulated Data

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Robert Lupton

Open LVV-T125 in Jira

4.115.1 Verification Elements

- LVV-6 - DMS-REQ-0009-V-01: Simulated Data

4.115.2 Test Items

Verify that the DMS can inject simulated data into data products for testing.

4.115.3 Predecessors

4.115.4 Environment Needs

4.115.4.1 Software

4.115.4.2 Hardware

Rubin Observatory

4.115.5   Input Specification

4.115.6   Output Specification

4.115.7   Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Identify a dataset that has been (or can be readily) processed through single-frame processing and coaddition.
	Test Data	No data.
	Expected Result	The 'calexp' and 'deepCoadd_calexp' images and their associated source catalogs are created.
2	Description	Roughly determine the coordinates of a bounding box that is contained within the images that were processed.
	Test Data	No data.
	Expected Result	RA, Dec boundaries of a region in which to generate fake sources.
3	Description	Generate a catalog in the correct format for 'insertFakes' to accept. The catalog should specify positions and magnitudes of stars (and optionally, parameters specifying galaxy shape, if galaxies are also being inserted).
	Test Data	No data.
	Expected Result	An input catalog of fake source positions and magnitudes to be inserted into the images.
4	Description	Execute 'insertFakes.py' on the repository, specifying the input catalog from the previous step.
	Test Data	No data.
	Expected Result	A repository with images that have fake sources inserted.
5	Description	Run 'multiBandDriver.py' on the repository, specifying the fake-source repository as the input.
	Test Data	No data.
	Expected Result	'calexp' and coadd images containing the artificial sources and sources catalogs that contain their measurements along with the sources detected in the original run.
6	Description	Confirm that the injected sources appear in the images and the catalogs.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
Expected Result	Fake sources and their measured properties are recoverable.	

4.116 LVV-T126 - Verify implementation of Image Differencing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T126 in Jira

4.116.1 Verification Elements

- LVV-14 - DMS-REQ-0032-V-01: Image Differencing

4.116.2 Test Items

Verify that the DMS can performance image differencing from single exposures and coadds.

4.116.3 Predecessors

4.116.4 Environment Needs

4.116.4.1 Software

4.116.4.2 Hardware

4.116.5 Input Specification

4.116.6 Output Specification

4.116.7 Test Procedure

Rubin Observatory

Step		Description, Input Data and Expected Result
1	Description	Identify a repository containing data that have been processed through the difference imaging pipeline. (e.g., the HiTS 2015 data that are processed monthly for testing)
	Test Data	No data.
	Expected Result	A dataset containing calexps, difference images, and source catalogs (of diaSrcs).
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Extract a 'calexp', a 'deepDiff_differenceExp', and the 'deepDiff_diaSrc' catalog of measurements.
	Test Data	No data.
	Expected Result	Well-formed images and catalogs containing the calexp from the visit image and the difference image, and measurements of sources from the difference image.
4	Description	Confirm (by visual inspection) that the difference image is mostly blank sky (i.e., has had a template of the same field subtracted), and that the source catalog contains sources with photometric and astrometric measurements.
	Test Data	No data.
	Expected Result	A mostly blank image (with perhaps some artifacts due to imperfect subtraction) and a catalog of sources detected/measured from that image.

4.117   LVV-T127 - Verify implementation of Provide Source Detection Software

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T127 in Jira

4.117.1   Verification Elements

- LVV-15 - DMS-REQ-0033-V-01: Provide Source Detection Software

4.117.2 Test Items

Verify that the DMS provides source detection software that can be applied to calibrated images, including both difference images and coadds. This will be verified using simulated data, but could also be done by inserting artificial sources into existing datasets.

4.117.3 Predecessors

4.117.4 Environment Needs

4.117.4.1 Software

4.117.4.2 Hardware

4.117.5 Input Specification

4.117.6 Output Specification

4.117.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Run DRP and AP processing, including source detection and measurement algorithms, on a small portion of the data from a simulated dataset.
	Test Data	No data.
	Expected Result	Source catalogs containing measurements of all sources detected in the input images.
2	Description	Confirm that the output repos contain catalogs of source detections. Compare these output catalogs to the original simulated source catalogs, and confirm that a large fraction of the sources within a reasonable signal-to-noise range were recovered.
	Test Data	No data.
	Expected Result	Most sources above a reasonable S/N threshold were detected, and their measured fluxes are reasonably close to the simulated inputs.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

221

4.118   LVV-T128 - Verify implementation Provide Astrometric Model

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T128 in Jira

4.118.1   Verification Elements

- LVV-17 - DMS-REQ-0042-V-01: Provide Astrometric Model

4.118.2   Test Items

Verify that an astrometric model is available for Objects and DIAObjects.

4.118.3   Predecessors

4.118.4   Environment Needs

4.118.4.1   Software

4.118.4.2   Hardware

4.118.5   Input Specification

4.118.6   Output Specification

4.118.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to AP and DRP
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
	Expected
	Result

4.119   LVV-T129 - Verify implementation of Provide Calibrated Photometry

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T129 in Jira

4.119.1   Verification Elements

- LVV-18 - DMS-REQ-0043-V-01: Provide Calibrated Photometry

4.119.2   Test Items

Verify that the DMS provides photometry calibrated in AB mags and fluxes (in nJy) for all measured objects and sources. Must be tested for both DRP and AP products.

4.119.3   Predecessors

4.119.4   Environment Needs

4.119.4.1   Software

4.119.4.2   Hardware

4.119.5   Input Specification

4.119.6   Output Specification

Rubin Observatory

4.119.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Ingest the data products from an appropriate DRP-processed dataset.
	Test Data	No data.
	Expected Result	
3	Description	Confirm that AB-calibrated magnitudes and fluxes are available for all measured Sources and Objects. [An enhanced verification could include matching the sources to an external source catalog and comparing the magnitudes to show that they are well-calibrated.]
	Test Data	No data.
	Expected Result	Calibrated fluxes and magnitudes are available for all sources, as well as tools to convert measured fluxes to magnitudes (and vice-versa).
4	Description	Ingest the data products from an appropriate AP processing dataset.
	Test Data	No data.
	Expected Result	
5	Description	Confirm that AB-calibrated magnitudes and fluxes are available for all measured Sources, DIASources, and Objects. [An enhanced verification could include matching the sources to an external source catalog and comparing the magnitudes to show that they are well-calibrated.]
	Test Data	No data.
	Expected Result	Calibrated fluxes and magnitudes are available for all Sources, DIASources, and Objects, as well as tools to convert measured fluxes to magnitudes (and vice-versa).

4.120 LVV-T130 - Verify implementation of Enable a Range of Shape Measurement Approaches

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T130 in Jira

4.120.1 Verification Elements

- LVV-21 - DMS-REQ-0052-V-01: Enable a Range of Shape Measurement Approaches

4.120.2 Test Items

Verify that multiple shape measurement algorithms can be used.

4.120.3 Predecessors

4.120.4 Environment Needs

4.120.4.1 Software

4.120.4.2 Hardware

4.120.5 Input Specification

4.120.6 Output Specification

4.120.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to AP and DRP
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.121 LVV-T131 - Verify implementation of Provide User Interface Services

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T131 in Jira

4.121.1 Verification Elements

- LVV-63 - DMS-REQ-0160-V-01: Provide User Interface Services

4.121.2 Test Items

Verify the availability and functionality of the broad range of user interface services called for in the requirement, as applied to both Nightly and DRP data. This will primarily be done by verifications performed at the LSST Science Platform level, based on the requirements in LDM-554; however, a high-level set of tests corresponding to the DMS-REQ-0160 requirement are defined below.

4.121.3 Predecessors

4.121.4 Environment Needs

4.121.4.1 Software

4.121.4.2 Hardware   As noted in Verification Configuration, the systems required to carry out the tests include both an "inside" test execution platform - the ability to execute test notebooks within the Science Platform Notebook Aspect - and an "outside" test execution platform with connectivity to the Science Platform instance under test that is comparable to that available to offsite science users.

4.121.5   Input Specification

1. Testing this requirement relies on a set of data products meeting the data model implied by the DPDD existing in a deployment of the Science Platform and its underlying database and file services.

   (a) In particular, both image and catalog data products are required.
   (b) From the specific language of the underlying requirement, it appears clear that coadded data products are required, but in practice single-epoch data products should be included in the test as well.

2. Depending on when this requirement is tested, the tests may involve either or both of precursor data and LSST commissioning data. The use of the latter is ultimately essential to ensure that the tests are performed with as LSST-like a dataset as possible.

4.121.6   Output Specification

4.121.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	**Establishment of test coordinates:** Establish sky positions and surrounding regions (e.g., cones or polygons), field sizes, filter bands, and temporal epochs for the tests that are consistent with the known content of the test dataset, whether precursor or LSST commissioning data. Establishing sky positions should include pre-determining the corresponding LSST "tract and patch" identifiers. If the plan to not keep all calibrated single-epoch images on disk is still in place at the time of the test, identify for use in the test both images that are, and are not, on disk. Establish target image boundaries, projections, and pixel scales to be used for resampling tests. Ensure that at least some of these test conditions include coadded image boundaries that cross tract and patch boundaries, and single-epoch image boundaries that cross focal plane raft boundaries.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	**Butler image access:** From within the Notebook Aspect, verify that coadded images for the identified regions of sky and filter bands are accessible via the Butler. Verify that the same images are available whether obtained by direct reference to the previous established tract/patch identifiers or by the use of LSST stack code for retrieving images based on sky coordinates. From within the Notebook Aspect, verify that single-epoch raw images for the selected locations and times are available. Verify that calibrated images (PVIs) for the selected locations and times are available; depending on the details of the test dataset, verify that PVIs still on disk can be retrieved immediately. Verify that lists or tables of image metadata, not just individual images, can be retrieved. E.g., a list of all the single-epoch images covering a selected sky location.
	Test Data	No data.
	Expected Result	
3	Description	**Programmatic PVI re-creation:** From within the Notebook Aspect, verify that the recreation on demand of a PVI can be performed. Ideally, this should be done as follows: • Verify that recreation of a PVI that *is* still available works and that it reproduces the original PVI exactly (except for provenance metadata that must be different) or within the reasonable ability of processing systems to do so (e.g., taking into account that the original calibration and the recreation may have run on different CPU architectures). • The test conditions should ensure the verification that a recreation was actually performed, i.e., that the still-available PVI was not returned instead. • Note that it does not appear to be a requirement that *at Butler level* recreation on demand of PVIs is a completely transparent process. If this *is* decided to be a requirement, the test must also verify that it has been satisfied. If it is *not* a requirement, verify that adequate documentation on the PVI-recreation process (e.g., the SuperTasks and configuration to be used) is available.
	Test Data	No data.
	Expected Result	
4	Description	**Butler catalog access:** From within the Notebook Aspect, verify that all the catalog data products described in the DPDD can be retrieved for the coordinates selected above via the Butler. (This test should include access to SSObject data, but the details of how such a test would depend on the coordinate selections require additional thought.)
	Test Data	No data.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

228

Rubin **Observatory**

Step	Description, Input Data and Expected Result	
	Expected Result	
5	Description	**LSST-stack-based resampling/reprojection:** Verify the availability of software in the LSST stack, and associated documentation, that permits the resampling of LSST images to different pixel grids and projections. Exercise this capability for the test conditions selected in Step 1 above. Perform photometric and astrometric tests on the resulting resampled images to provide evidence that the transformations performed were correct to the accuracy supported by the data.
	Test Data	No data.
	Expected Result	
6	Description	**Comment:** The following API Aspect test steps should be carried out on the required "offsite-like" test platform, to ensure that their success does not reflect any privileged access given to processes inside the Data Access Center or other Science Platform instance. However, at least a small sampling of them should *also* be carried out *within* the Science Platform environment, i.e., in the Notebook Aspect, and the results compared.
	Test Data	No data.
	Expected Result	
7	Description	**API Aspect image access:** Using IVOA services such as the Registry and ObsTAP, from the "offsite-like" test platform, verify that the existence of the classes of image data products foreseen in the DPDD can be determined. Verify that ObsTAP and/or SIAv2 can be used to find the same images and lists of images for the established test coordinates that were retrieved via the Butler in Step 2 above. Verify that the selected images are retrievable from the Web services. Verify that the retrieved images are identical in their pixel content and metadata. The tests must include both coadded and single-epoch images.
	Test Data	No data.
	Expected Result	
8	Description	**API Aspect image transformations:** Verify that image cutouts and resamplings can be performed via the IVOA SODA service, and that the results are identical to those obtained for the same parameters from the LSST-stack-based tests in Step 5. (The requirements for supported reprojections, if any, in the SODA service have not been established at the time of writing.)

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
9	Description	**API Aspect catalog data access:** Verify that the IVOA Registry, RegTAP, TAP_SCHEMA, and other relevant mechanisms can be used to discover the existence of all the catalog data products foreseen in the DPDD. Using the IVOA TAP service, verify that all the catalog data products foreseen in the DPDD can be retrieved for the coordinates determined in Step 1. Verify that their scientific content is the same as when they are retrieved via the Butler.
	Test Data	No data.
	Expected Result	
10	Description	**Comment:** The Portal Aspect tests below should be carried out from a web browser on an "offsite-like" test platform, to ensure that no privileged access provided to intra-data-center clients is relied upon.
	Test Data	No data.
	Expected Result	
11	Description	**Portal Aspect data browsing:** Verify that the Portal Aspect can be used to discover the existence of all the data products foreseen in the DPDD. Verify that the UI permits locating the data for the coordinates selected in Step 1 by visual means, e.g., by zooming and panning in from an all-sky view. Verify that the UI permits locating the data by typing in coordinates as well.
	Test Data	No data.
	Expected Result	
12	Description	**Portal Aspect image access:** Verify that the Portal Aspect allows both the retrieval of "original" image data, i.e., in its native LSST pixel projection and with full metadata, as well as retrieval of on-demand UI cutouts of coadded image data for selected locations.
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

230

Rubin Observatory

Step	Description, Input Data and Expected Result	
13	Description	**Portal Aspect catalog query and visualization:** Verify that the Portal Aspect allows graphical querying of DPDD catalog data, both coadded and single-epoch, for selected regions of sky and/or with selected properties, and supports the visualization of the results (including histogramming, scatterplots, time series, table manipulations, and overplotting on image data). (Note that the Science Platform requirements, LDM-554, lay out a detailed set of requirements on the selection and visualization of catalog data.)
	Test Data	No data.
	Expected Result	
14	Description	**Portal Aspect data download:** Verify that data identified and/or visualized in the Portal Aspect can be downloaded to the remote system running the web browser in which the Portal is displayed, as well as to the User Workspace.
	Test Data	No data.
	Expected Result	

4.122   LVV-T132 - Verify implementation of Pre-cursor and Real Data

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Robert Gruendl

Open LVV-T132 in Jira

4.122.1   Verification Elements

• LVV-127 - DMS-REQ-0296-V-01: Pre-cursor, and Real Data

4.122.2   Test Items

Demonstrate that pixel-oriented data from astronomical imaging cameras (precursor or otherwise) can be processed using LSST Science Algorithms and organized for access through the Data Butler Access Client.

Rubin Observatory

4.122.3   Predecessors

4.122.4   Environment Needs

4.122.4.1   Software

4.122.4.2   Hardware

4.122.5   Input Specification

4.122.6   Output Specification

4.122.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Confirm that the CI jobs used to test DRP processing successfully run. These jobs use precursor datasets from cameras other than LSST.
	Test Data	No data.
	Expected Result	
2	Description	For the precursor dataset, instantiate the Butler, load the data products, and confirm that they exist as expected.
	Test Data	No data.
	Expected Result	Processed images, catalogs, calibration information, and other related data products are present and accessible via the Butler.

4.123   LVV-T133 - Verify implementation of Provide Beam Projector Coordinate Calculation Software

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Lupton

Open LVV-T133 in Jira

Rubin Observatory

4.123.1   Verification Elements

- LVV-182 - DMS-REQ-0351-V-01: Provide Beam Projector Coordinate Calculation Software

4.123.2   Test Items

Verify that the DMS provides software to calculate coordinates relating the collimated beam projector position and telescope pupil position to the illumination position on the telescope optical elements and focal plane.

4.123.3   Predecessors

4.123.4   Environment Needs

4.123.4.1   Software

4.123.4.2   Hardware

4.123.5   Input Specification

4.123.6   Output Specification

4.123.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	On the LSST development cluster or notebook aspect, git clone the repo containing the CBP package: `https://github.com/lsst/cbp`
	Test Data	No data.
	Expected Result	
2	Description	Follow the steps in the package README to install the package.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	
3	Description	Confirm that the package can be loaded in python, and that some of the tests in the 'tests/' folder will execute.
	Test Data	No data.
	Expected Result	Successful execution of test scripts, which demonstrate the calculation of beam projector coordinates.

4.124 LVV-T134 - Verify implementation of Provide Image Access Services

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Gregory Dubois-Felsmann

Open LVV-T134 in Jira

4.124.1 Verification Elements

- LVV-27 - DMS-REQ-0065-V-01: Provide Image Access Services

4.124.2 Test Items

Verify that images can be identified and that images and image cut-outs can be retrieved using the network interfaces - primarily IVOA standards-based - and Python APIs provided for image access by science users.

4.124.3 Predecessors

4.124.4 Environment Needs

4.124.4.1 Software

Rubin Observatory

4.124.4.2   Hardware

4.124.5   Input Specification

Testing requires the establishment of running services such as SIAv2 and SODA to which the tests can be applied.

4.124.6   Output Specification

4.124.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inspect that the following test cases have been executed and passed: LVV-T803, LVV-T810, LVV-T811, LVV-T812. The requirement is fully satisfied by lower-level LSP test cases.
	Test Data	No data.
	Expected Result	Test cases LVV-T803, LVV-T810, LVV-T811, LVV-T812 passed without blocking issues.

4.125   LVV-T136 - Verify implementation of Data Product and Raw Data Access

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Colin Slater

Open LVV-T136 in Jira

4.125.1   Verification Elements

- LVV-129 - DMS-REQ-0298-V-01: Data Product and Raw Data Access

Rubin Observatory

4.125.2 Test Items

Verify that available image, file, and catalog data products, and their metadata and prove-
nance information, can be listed and retrieved.

4.125.3 Predecessors

4.125.4 Environment Needs

4.125.4.1 Software

4.125.4.2 Hardware

4.125.5 Input Specification

4.125.6 Output Specification

4.125.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Details of the Gen3 Butler and ObsTAP tables are still being worked out. The general overview of this test will be to use some combination of the Gen3 Butler and TAP access to the ObsTAP tables to test that the required access is provided.
	Test Data	No data.
	Expected Result	Verification that the relevant data products and their related tables, metadata, and prove-nance information are available and readily accessible.

4.126 LVV-T137 - Verify implementation of Data Product Ingest

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Colin Slater

Open LVV-T137 in Jira

4.126.1 Verification Elements

- LVV-130 - DMS-REQ-0299-V-01: Data Product Ingest

4.126.2 Test Items

Verify that data products can be ingested.

4.126.3 Predecessors

4.126.4 Environment Needs

4.126.4.1 Software

4.126.4.2 Hardware

4.126.5 Input Specification

4.126.6 Output Specification

4.126.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a suitable set of raw data to be run through "mini-DRP" processing.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1064	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
4	Description	Confirm that the data products from the DRP processing have been ingested into the Data Backbone.
	Test Data	No data.
	Expected Result	Processed images, catalogs, calibration information, and other related data products are present and accessible via the Butler.

4.127   LVV-T138 - Verify implementation of Bulk Download Service

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T138 in Jira

4.127.1   Verification Elements

- LVV-131 - DMS-REQ-0300-V-01: Bulk Download Service

4.127.2   Test Items

Bulk Download

4.127.3   Predecessors

Rubin Observatory

4.127.4   Environment Needs

4.127.4.1   Software

4.127.4.2   Hardware

4.127.5   Input Specification

A large dataset (at least a few TB) must be available.

Requires identity management to confirm bulk download use.

While this can be tested and shown to work using LSST DAC, Chilean DAC, and IN2P3 end-points, this should also be tested to demonstrate expected throughput for outside users (e.g. FNAL, NERSC sites could be tested).

4.127.6   Output Specification

4.127.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Setup large transfer request and examine the data transfer rates achieved.
	Test Data	No data.
	Expected Result	
2	Description	Test should be repeated while observing in firehose mode (with LSSTCam) during science verification to ensure that bulk transfer does not compromise normal nightly operations.
	Test Data	No data.
	Expected Result	

4.128   LVV-T140 - Verify implementation of Production Orchestration

Version	Status	Priority	Verification Type	Owner

1	Defined	Normal	Test		Robert Gruendl

Open LVV-T140 in Jira

4.128.1 Verification Elements

- LVV-133 - DMS-REQ-0302-V-01: Production Orchestration

4.128.2 Test Items

Demonstrate use to orchestration software to perform real-time and batch production on LSST compute platform(s).

4.128.3 Predecessors

4.128.4 Environment Needs

4.128.4.1 Software

4.128.4.2 Hardware

4.128.5 Input Specification

4.128.6 Output Specification

4.128.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify an appropriate precursor dataset.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Execute a batch processing job using the orchestration system, and confirm (manually and/or via QA tools typically used for HSC reprocessing) that the pipeline executed and produced all expected products (or error logs in cases of failure).
	Test Data	No data.
	Expected Result	Calexp single-visit and coadd images, and associated catalogs, are present in a Butler repository. Logs of the processing are available to be inspected for identification of problems in the processing.

4.129   LVV-T141 - Verify implementation of Production Monitoring

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Gruendl

Open LVV-T141 in Jira

4.129.1   Verification Elements

- LVV-134 - DMS-REQ-0303-V-01: Production Monitoring

4.129.2   Test Items

Demonstrate monitoring capabilities that give real-time view of pipeline execution and production systems usage/load.

4.129.3   Predecessors

LVV-T140

4.129.4   Environment Needs

4.129.4.1   Software

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

241

Rubin Observatory

4.129.4.2   Hardware

4.129.5   Input Specification

Data set and mechanism for Production Orchestration as outlined in LVV-T140.

4.129.6   Output Specification

4.129.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T1064	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	
	Expected Result	
2	Description	While DRP processing is executing, monitor the progress and resource usage of processing.
	Test Data	No data.
	Expected Result	Ability to monitor in real-time the orchestrated production processing, including resource usage.

4.130   LVV-T142 - Verify implementation of Production Fault Tolerance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T142 in Jira

4.130.1   Verification Elements

• LVV-135 - DMS-REQ-0304-V-01: Production Fault Tolerance

Rubin Observatory

4.130.2   Test Items

Demonstrate production systems report faults in pipeline executions and that system is able to recover. Where recovery can mean the ability to provide production artifacts for examination, return production elements ready for subsequent use, and/or reset and repeat production attempts.

4.130.3   Predecessors

4.130.4   Environment Needs

4.130.4.1   Software

4.130.4.2   Hardware

4.130.5   Input Specification

4.130.6   Output Specification

4.130.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute AP and DRP, simulate failures, observe correct processing
	Test Data	No data.
	Expected Result	

4.131   LVV-T144 - Verify implementation of Task Specification

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Kian-Tat Lim

Open LVV-T144 in Jira

Rubin Observatory

4.131.1 Verification Elements

- LVV-136 - DMS-REQ-0305-V-01: Task Specification

4.131.2 Test Items

Verify that the DMS provides the ability to define a new or modified pipeline task without recompilation.

4.131.3 Predecessors

4.131.4 Environment Needs

4.131.4.1 Software

4.131.4.2 Hardware

4.131.5 Input Specification

4.131.6 Output Specification

4.131.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inspect software architecture. Verify that there exist Tasks that can be run and configured without re-compilation.
	Test Data	No data.
	Expected Result	Confirmation that the software architecture has allowed for reconfiguring and running Tasks without recompilation.
2	Description	Verify that an example science algorithm can be run through one of these Tasks. Three examples from different areas: source measurement, image subtraction, and photometric-redshift estimation.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Successful Task execution with different configurations, including confirmation that the outputs are different from tasks with altered configurations.

4.132   LVV-T145 - Verify implementation of Task Configuration

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Robert Lupton

Open LVV-T145 in Jira

4.132.1   Verification Elements

- LVV-137 - DMS-REQ-0306-V-01: Task Configuration

4.132.2   Test Items

Verify that the DMS software provides configuration control to define, override, and verify the configuration for a DMS Task.

4.132.3   Predecessors

4.132.4   Environment Needs

4.132.4.1   Software

4.132.4.2   Hardware

4.132.5   Input Specification

4.132.6   Output Specification

Rubin Observatory

4.132.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inspect software design to verify that one can define the configuration for a Task.
	Test Data	No data.
	Expected Result	
2	Description	Run a Task with a known invalid configuration. Verify that the error is caught before the science algorithm executes.
	Test Data	No data.
	Expected Result	
3	Description	Run a simple task with two different configurations that make a material difference for a Task. E.g., specify a different source detection threshold. Verify that the configuration is different between the two runs through difference in recorded provenance and in results.
	Test Data	No data.
	Expected Result	

4.133 LVV-T146 - Verify implementation of DMS Initialization Component

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Robert Gruendl

Open LVV-T146 in Jira

4.133.1 Verification Elements

• LVV-128 - DMS-REQ-0297-V-01: DMS Initialization Component

4.133.2 Test Items

Demonstrate that the DMS can be initialized in a safe state that will not allow data corruption/loss.

Rubin Observatory

4.133.3   Predecessors

4.133.4   Environment Needs

4.133.4.1   Software

4.133.4.2   Hardware

4.133.5   Input Specification

4.133.6   Output Specification

4.133.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Power-cycle all of the DM systems at each Facility.
	Test Data	No data.
	Expected Result	Restart of all DM systems.
2	Description	Observe each system and ensure that it has recovered in a properly initialized state.
	Test Data	No data.
	Expected Result	Systems are all active and initialized for their designated purpose.

4.134   LVV-T147 - Verify implementation of Control of Level-1 Production

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T147 in Jira

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

247

Rubin Observatory

4.134.1   Verification Elements

- LVV-132 - DMS-REQ-0301-V-01: Control of Level-1 Production

4.134.2   Test Items

Demonstrate that the DMS can control all Prompt Processing across DMS facilities.

4.134.3   Predecessors

4.134.4   Environment Needs

4.134.4.1   Software

4.134.4.2   Hardware

4.134.5   Input Specification

4.134.6   Output Specification

4.134.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Observe existence and capability of Prompt DMCS
	Test Data	No data.
	Expected Result	

4.135   LVV-T148 - Verify implementation of Unique Processing Coverage

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Test	Colin Slater

Open LVV-T148 in Jira

4.135.1 Verification Elements

- LVV-138 - DMS-REQ-0307-V-01: Unique Processing Coverage

4.135.2 Test Items

Verify that a user-specified criterion can be used to process each record in a table exactly once.

4.135.3 Predecessors

4.135.4 Environment Needs

4.135.4.1 Software

4.135.4.2 Hardware

4.135.5 Input Specification

4.135.6 Output Specification

4.135.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute representative processing, observe lack of duplicates or missing rows even in the presence of failures
	Test Data	No data.
	Expected Result	

4.136   LVV-T149 - Verify implementation of Catalog Queries

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Colin Slater

Open LVV-T149 in Jira

4.136.1   Verification Elements

- LVV-33 - DMS-REQ-0075-V-01: Catalog Queries

4.136.2   Test Items

Verify that SQL, or a similar structured language, can be used to query catalogs.

4.136.3   Predecessors

4.136.4   Environment Needs

4.136.4.1   Software

4.136.4.2   Hardware

4.136.5   Input Specification

An operational QSERV database that has been verified via LVV-T1085 and LVV-T1086 and LVV-T1087.

4.136.6   Output Specification

4.136.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute a simple query (for example, the one below) and confirm that it returns the expected result.
	Test Data	No data.
	Example Code	SELECT * FROM Object WHERE qserv_areaspec_box(316.582327, −6.839078, 316.653938, −6.781822)
	Expected Result	A catalog of objects satisfying the specified constraints.
2	Description	Repeat the query from all available access routes (e.g., an external VO client, internal DM tools on the development cluster, the Science Platform query tool, and from within the Notebook Aspect), confirming in each case that the results are as expected.
	Test Data	No data.
	Expected Result	

4.137 LVV-T150 - Verify implementation of Maintain Archive Publicly Accessible

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Colin Slater

Open LVV-T150 in Jira

4.137.1 Verification Elements

- LVV-34 - DMS-REQ-0077-V-01: Maintain Archive Publicly Accessible

4.137.2 Test Items

Verify that prior data releases remain accessible.

4.137.3 Predecessors

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

251

Rubin Observatory

4.137.4   Environment Needs

4.137.4.1   Software

4.137.4.2   Hardware

4.137.5   Input Specification

Availability of at least three (3) data releases, of which at least one of them must be archived outside the QSERV database. These can be precursor datasets, if needed.

4.137.6   Output Specification

4.137.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Confirm that at least two data releases (the most recent, and one previous) are accessible to users (and can be queried) from the standard channels.
	Test Data	No data.
	Expected Result	Simple queries return catalog data from the data releases that are available in QSERV.
2	Description	Confirm that previous data releases are accessible for bulk download (perhaps with significant latency) from tape or other bulk store, and that the downloaded tables contain the expected data products.
	Test Data	No data.
	Expected Result	A download of an entire previous data release from its bulk store.

4.138   LVV-T151 - Verify Implementation of Catalog Export Formats From the Notebook Aspect

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Colin Slater

Rubin Observatory

Open LVV-T151 in Jira

4.138.1   Verification Elements

- LVV-35 - DMS-REQ-0078-V-01: Catalog Export Formats

4.138.2   Test Items

Verify that catalog data is exportable from the notebook aspect in a variety of community-standard formats.

4.138.3   Predecessors

4.138.4   Environment Needs

4.138.4.1   Software

4.138.4.2   Hardware

4.138.5   Input Specification

4.138.6   Output Specification

4.138.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T837	Description	Authenticate to the notebook aspect of the LSST Science Platform (NB-LSP). This is currently at https://lsst-lsp-stable.ncsa.illinois.edu/nb.
	Test Data	
	Expected Result	Redirection to the spawner page of the NB-LSP allowing selection of the containerized stack version and machine flavor.

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-2 from LVV-T837	Description	Spawn a container by: 1) choosing an appropriate stack version: e.g. the latest weekly. 2) choosing an appropriate machine flavor: e.g. medium 3) click "Spawn"
	Test Data	
	Expected Result	Redirection to the JupyterLab environment served from the chosen container containing the correct stack version.
2-1 from LVV-T838	Description	Open a new launcher by navigating in the top menu bar "File" -> "New Launcher"
	Test Data	
	Expected Result	A launcher window with several sections, potentially with several kernel versions for each.
2-2 from LVV-T838	Description	Select the option under "Notebook" labeled "LSST" by clicking on the icon.
	Test Data	
	Expected Result	An empty notebook with a single empty cell. The kernel show up as "LSST" in the top right of the notebook.
3-1 from LVV-T1207	Description	Execute a query in a notebook to select a small number of stars. In the example code below, we query the WISE catalog, then extract the results to an Astropy table.
	Test Data	
	Expected Result	
4	Description	Using the example code below, save the files to your storage space on the LSP Notebook Aspect. Confirm that non-empty output files appear on disk.
	Test Data	No data.
	Example Code	tab.write('test.csv', format='ascii.csv') tab.write('test.vot', format='votable') tab.write('test.fits', format='fits')

Step	Description, Input Data and Expected Result	
	Expected Result	For the example given here, there should be the following files with the file size as listed: • test.csv 5.7M • test.vot 16M • test.fits 4.5M
5	Description	Check that these files contain the same number of rows:
	Test Data	No data.
	Example Code	from astropy.table import Table dat_csv = Table.read('test.csv', format='ascii.csv') dat_vot = Table.read('test.vot', format='votable') dat_fits = Table.read('test.fits', format='fits') import numpy as np print(np.size(dat_csv), np.size(dat_vot), np.size(dat_fits))
	Expected Result	Print statement produces output "97058 97058 97058".
6-1 from LVV-T1208	Description	Under the 'File' menu at the top of your Jupyter notebook session, select one of the following: • Save All, Exit, and Log Out • Exit and Log Out Without Saving
	Test Data	
	Expected Result	You will be returned to the LSP landing page: `https://lsst-lsp-stable.ncsa.illinois.edu/` It is now safe to close the browser window.

4.139   LVV-T152 - Verify implementation of Keep Historical Alert Archive

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T152 in Jira

Rubin Observatory

4.139.1   Verification Elements

- LVV-37 - DMS-REQ-0094-V-01: Keep Historical Alert Archive

4.139.2   Test Items

Verify that the DMS preserves and makes accessible an Alert Archive for reference and for false alert analyses

4.139.3   Predecessors

4.139.4   Environment Needs

4.139.4.1   Software

4.139.4.2   Hardware

4.139.5   Input Specification

4.139.6   Output Specification

4.139.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Simulated alert stream, load Alert DB, observe access to Alert DB
	Test Data	No data.
	Expected Result	

4.140   LVV-T153 - Verify implementation of Provide Engineering and Facility Database Archive

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Robert Gruendl

Open LVV-T153 in Jira

4.140.1   Verification Elements

- LVV-44 - DMS-REQ-0102-V-01: Provide Engineering & Facility Database Archive

4.140.2   Test Items

Demonstrate Engineering and Facilities Data (images, associated metadata, and observatory environment and control data) are archived and available for public access within **L1PublicT (24 hours)**.

4.140.3   Predecessors

4.140.4   Environment Needs

4.140.4.1   Software

4.140.4.2   Hardware

4.140.5   Input Specification

4.140.6   Output Specification

4.140.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute a single-day operations rehearsal, ingesting (simulated) OCS commands into the EFD.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

257

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
2	Description	Wait at least **L1PublicT=24** hours, then access the archived EFD. Confirm that the data products are present in the archived EFD after **L1PublicT=24** hours have elapsed.
	Test Data	No data.
	Expected Result	The EFD contains the simulated OCS commands, and they were ingested within **L1PublicT=24** hours of the operations rehearsal.
3	Description	From the public access portal to the EFD, execute a query and demonstrate that the data are publicly available.
	Test Data	No data.
	Expected Result	A query at the public interface to the EFD successfully executes and returns EFD data.

4.141 LVV-T154 - Verify implementation of Raw Data Archiving Reliability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T154 in Jira

4.141.1 Verification Elements

- LVV-140 - DMS-REQ-0309-V-01: Raw Data Archiving Reliability

4.141.2 Test Items

Verify that raw images are reliably archived.

4.141.3 Predecessors

4.141.4 Environment Needs

4.141.4.1 Software

4.141.4.2 Hardware

4.141.5 Input Specification

4.141.6 Output Specification

4.141.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze sources of loss or corruption after mitigation to compute estimated reliability
	Test Data	No data.
	Expected Result	

4.142 LVV-T155 - Verify implementation of Un-Archived Data Product Cache

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T155 in Jira

4.142.1 Verification Elements

- LVV-141 - DMS-REQ-0310-V-01: Un-Archived Data Product Cache

Rubin Observatory

4.142.2   Test Items

Demonstrate that the DMS provides low-latency storage for at least l1CacheLifetime (30 days) to keep prompt processing pre-covery images on hand.

4.142.3   Predecessors

4.142.4   Environment Needs

4.142.4.1   Software

4.142.4.2   Hardware

4.142.5   Input Specification

4.142.6   Output Specification

4.142.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to DBB
	Test Data	No data.
	Expected Result	

4.143   LVV-T156 - Verify implementation of Regenerate Un-archived Data Products

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T156 in Jira

Rubin Observatory

4.143.1   Verification Elements

- LVV-142 - DMS-REQ-0311-V-01: Regenerate Un-archived Data Products

4.143.2   Test Items

Not all of the ancillary data products produced by a data release will be archived permanently. These ancillary products have been promised as accessible to the community.   Show that these products can be produced from an archived data release after the fact.

4.143.3   Predecessors

4.143.4   Environment Needs

4.143.4.1   Software

4.143.4.2   Hardware

4.143.5   Input Specification

4.143.6   Output Specification

4.143.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Run a small DRP processing job and download unarchived data products.
	Test Data	No data.
	Expected Result	
2	Description	Wait for (or force) a processing stack change so that the subsequent re-processing will be forced to use an older software build.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Using provenance information from the products in Step 1, request a re-processing and compare results with previously unarchived products.
	Test Data	No data.
	Expected Result	

4.144 LVV-T157 - Verify implementation Level 1 Data Product Access

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T157 in Jira

4.144.1 Verification Elements

- LVV-143 - DMS-REQ-0312-V-01: Level 1 Data Product Access

4.144.2 Test Items

Verify that Level 1 Data Products are accessible by science users.

4.144.3 Predecessors

4.144.4 Environment Needs

4.144.4.1 Software

4.144.4.2 Hardware

4.144.5 Input Specification

Rubin Observatory

4.144.6   Output Specification

4.144.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.145   LVV-T158 - Verify implementation Level 1 and 2 Catalog Access

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T158 in Jira

4.145.1   Verification Elements

- LVV-144 - DMS-REQ-0313-V-01: Level 1 & 2 Catalog Access

4.145.2   Test Items

Verify that Data Release Products are accessible by science users.

4.145.3   Predecessors

4.145.4   Environment Needs

4.145.4.1   Software

4.145.4.2   Hardware

Rubin Observatory

4.145.5   Input Specification

4.145.6   Output Specification

4.145.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.146   LVV-T159 - Verify implementation of Regenerating Data Products from Previous Data Releases

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T159 in Jira

4.146.1   Verification Elements

- LVV-167 - DMS-REQ-0336-V-01: Regenerating Data Products from Previous Data Releases

4.146.2   Test Items

Show that un-archived data products from previous data releases can be generated using through the LSST Science Platform.

4.146.3   Predecessors

Rubin Observatory

4.146.4   Environment Needs

4.146.4.1   Software

4.146.4.2   Hardware

4.146.5   Input Specification

4.146.6   Output Specification

4.146.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.147   LVV-T160 - Verify implementation of Providing a Precovery Service

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T160 in Jira

4.147.1   Verification Elements

- LVV-172 - DMS-REQ-0341-V-01: Max elapsed time for precovery results

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

265

4.147.2   Test Items

Verify that a technical capability to perform user-directed precovery analyses on difference images exists and that it is exposed through the LSST Science Platform.   Verified by testing against precursor datasets.
(Involves: LSP Portal, MOPS and Forced Photometry)

4.147.3   Predecessors

4.147.4   Environment Needs

4.147.4.1   Software

4.147.4.2   Hardware

4.147.5   Input Specification

1. DECam HiTS data could be an appropriate set for this activity.
2. Precovery pipelines for follow-on to alert processing must exist and be made available as a containerized version within the Science Platform.
3. Determine limitations over which general precovery is supported. I would suggest that precovery services be limited to current (or last two) DRP campaigns with the possible addition of including non-DRP products to encompass observations over the preceding year (does this then require means to re-generate PVIs from Alert Production in addition to DRP?)
4. Could re-use elements of LVV-T80 where quasars are used to test faint object detection.

4.147.6   Output Specification

4.147.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Run Precovery within follow-on Alert Production (i.e. daily post-processing on 30 day store).
	Test Data	No data.
	Expected Result	
2	Description	Within Science Platform, initiate request to perform precovery for a list of sources over same period (and longer). Include among the sources for precovery quasars from LVV-T80.
	Test Data	No data.
	Expected Result	
3	Description	Examine the results. Compare the results for the period where there is overlap with precovery run... and quasar photometry with those from LVV-T80 to verify user service performs as production services.
	Test Data	No data.
	Expected Result	

4.148   LVV-T161 - Verify implementation of Logging of catalog queries

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T161 in Jira

4.148.1   Verification Elements

• LVV-176 - DMS-REQ-0345-V-01: Logging of catalog queries

4.148.2   Test Items

Demonstrate logging of queries of LSST databases. Logged queries are globally available to DB administrators but otherwise private excepting the user that made the query.

Rubin Observatory

4.148.3 Predecessors

4.148.4 Environment Needs

4.148.4.1 Software

4.148.4.2 Hardware

4.148.5 Input Specification

4.148.6 Output Specification

4.148.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.149 LVV-T162 - Verify implementation of Access to Previous Data Releases

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T162 in Jira

4.149.1 Verification Elements

- LVV-189 - DMS-REQ-0363-V-01: Access to Previous Data Releases

Rubin Observatory

4.149.2   Test Items

Verify this high-level requirement, which states that the other data access requirements, for images and catalogs, all must be satisfied for multiple data releases. Verified by inspection, i.e., by determining that the data access system components, from middleware through APIs to user interfaces, are designed to support data from multiple releases, as well as by direct testing using a synthetic test environment containing multiple releases.
(Involves: Data Backbone, Managed Database, LSP Portal, LSP JupyterLab, LSP Web APIs, Parallel Distributed Database)

4.149.3   Predecessors

4.149.4   Environment Needs

4.149.4.1   Software

4.149.4.2   Hardware

4.149.5   Input Specification

Requires two or more (fake) releases within DAC (or PDAC) with common area/observations (preferably with some differing results but could use metadata identifying provenance).

4.149.6   Output Specification

4.149.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	From Science Platform initiate request for image and catalog products from one of the two release sets.
	Test Data	No data.
	Expected Result	
2	Description	From Science Platform re-issue the same request but specifying the alternate/earlier release set.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
3	Description	Compare results and identify differences that are germaine to the relevant Data Release Sets are found.
	Test Data	No data.
	Expected Result	

4.150   LVV-T163 - Verify implementation of Data Access Services

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T163 in Jira

4.150.1   Verification Elements

• LVV-190 - DMS-REQ-0364-V-01: Total number of data releases

4.150.2   Test Items

Demonstrate that Data Access Services are capable of scaling to serve data from nDRTot (11) data releases over a surveyYears (10) year survey.

4.150.3   Predecessors

4.150.4   Environment Needs

4.150.4.1   Software

4.150.4.2 Hardware

4.150.5 Input Specification

4.150.6 Output Specification

4.150.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.151 LVV-T164 - Verify implementation of Operations Subsets

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T164 in Jira

4.151.1 Verification Elements

- LVV-191 - DMS-REQ-0365-V-01: Operations Subsets

4.151.2 Test Items

Demonstrate that Data Access Services are designed such that subsets of a Data Release may be retained and served (made available) after a Data Release has been superseded. (Data Backbone, Managed Database, LSP Portal, LSP JupyterLab, LSP Web APIs, Parallel Distributed Database)

4.151.3 Predecessors

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. **– DRAFT NOT YET APPROVED**

271

Rubin Observatory

4.151.4 Environment Needs

4.151.4.1 Software

4.151.4.2 Hardware

4.151.5 Input Specification

4.151.6 Output Specification

4.151.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.152 LVV-T165 - Verify implementation of Subsets Support

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Lupton

Open LVV-T165 in Jira

4.152.1 Verification Elements

- LVV-192 - DMS-REQ-0366-V-01: Subsets Support

4.152.2 Test Items

Verify that the DMS can provide designated subsets of previous Data Releases.

Rubin Observatory

4.152.3   Predecessors

4.152.4   Environment Needs

4.152.4.1   Software

4.152.4.2   Hardware

4.152.5   Input Specification

4.152.6   Output Specification

4.152.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.153   LVV-T166 - Verify implementation of Access Services Performance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T166 in Jira

4.153.1   Verification Elements

• LVV-193 - DMS-REQ-0367-V-01: Access Services Performance

Rubin Observatory

4.153.2 Test Items

Demonstrate monitoring of Data Access Services that give real and long-time views of system performance and usage.

4.153.3 Predecessors

4.153.4 Environment Needs

4.153.4.1   Software

4.153.4.2   Hardware

4.153.5 Input Specification

4.153.6 Output Specification

4.153.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.154 LVV-T167 - Verify Capability to serve older Data Releases at Full Performance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T167 in Jira

Rubin Observatory

4.154.1 Verification Elements

- LVV-194 - DMS-REQ-0368-V-01: Implementation Provisions

4.154.2 Test Items

Verify that implementation of the data access services do not preclude serving all older Data Releases with the same performance requirements as current Data Releases. Note that it is an operational consideration whether sufficient compute and storage resources would actually be provisioned to meet those requirements.

4.154.3 Predecessors

4.154.4 Environment Needs

4.154.4.1 Software

4.154.4.2 Hardware

4.154.5 Input Specification

4.154.6 Output Specification

4.154.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

275

4.155 LVV-T168 - Verify design of Data Access Services allows Evolution of the LSST Data Model

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T168 in Jira

4.155.1 Verification Elements

- LVV-195 - DMS-REQ-0369-V-01: Evolution

4.155.2 Test Items

Verify that the design of the Data Access Services are able to accommodate changes/evolution of the LSST data model from one release to another.

4.155.3 Predecessors

4.155.4 Environment Needs

4.155.4.1 Software

4.155.4.2 Hardware

4.155.5 Input Specification

4.155.6 Output Specification

4.155.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.156 LVV-T169 - Verify implementation of Older Release Behavior

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T169 in Jira

4.156.1 Verification Elements

- LVV-196 - DMS-REQ-0370-V-01: Older Release Behavior

4.156.2 Test Items

Verify that the components of the data access system are technically capable of handling data releases beyond the two for which full services are required.   DMS-REQ-0364 requires that up to 11 be supported. Verified by inspection, i.e., by determination that the system design and implementation contain the necessary features to support this number of releases, and by direct test in a synthetic test environment with multiple releases.
(Involves: Data Backbone, Managed Database, LSP Portal, LSP JupyterLab, LSP Web APIs, Parallel Distributed Database)

4.156.3 Predecessors

4.156.4 Environment Needs

4.156.4.1 Software

4.156.4.2   Hardware

4.156.5   Input Specification

4.156.6   Output Specification

4.156.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.157   LVV-T170 - Verify implementation of Query Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T170 in Jira

4.157.1   Verification Elements

• LVV-197 - DMS-REQ-0371-V-01: Query Availability

4.157.2   Test Items

Verify that queries continue to be successfully executable over time.

4.157.3   Predecessors

Rubin Observatory

4.157.4   Environment Needs

4.157.4.1   Software

4.157.4.2   Hardware

4.157.5   Input Specification

4.157.6   Output Specification

4.157.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Delegate to LSP
	Test Data	No data.
	Expected Result	

4.158   LVV-T171 - Verify implementation of Pipeline Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T171 in Jira

4.158.1   Verification Elements

- LVV-5 - DMS-REQ-0008-V-01: Pipeline Availability

4.158.2   Test Items

Demonstrate that Data Management System pipelines are available for use without disruptions of greater than productionMaxDowntime (24 hours). This requires a regimented change control process and testing infrastructure for all pipelines and their underlying software services, and regimented management and monitoring of compute and networking resources. The list of services covered by this test include: Image and EFD Archiving, Prompt Processing, OCS Driven Batch, Telemetry Gateway, Alert Distribution, Alert Filtering, Batch Production, Data Backbone, Compute/Storage/LAN, Inter-Site Networks, and Service Management and Monitoring.

4.158.3   Predecessors

4.158.4   Environment Needs

4.158.4.1   Software

4.158.4.2   Hardware

4.158.5   Input Specification

4.158.6   Output Specification

4.158.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze sources of downtime after mitigation to compute estimated reliability; observe unscheduled downtime of developer, integration, and pre-production systems
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.159 LVV-T172 - Verify implementation of Optimization of Cost, Reliability and Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T172 in Jira

4.159.1 Verification Elements

- LVV-64 - DMS-REQ-0161-V-01: Optimization of Cost, Reliability and Availability in Order

4.159.2 Test Items

In matters of cost, system reliability (functioning properly at a given time) has precedence over system availability (ability to use the system at a given time). The optimization may be outside the realm of direct testing as it is more of a system provisioning guideline but on its face it demands that the Data Management System include failure reporting, regimented change control, acceptance testing, maintenance and monitoring.

4.159.3 Predecessors

4.159.4 Environment Needs

4.159.4.1 Software

4.159.4.2 Hardware

4.159.5 Input Specification

4.159.6 Output Specification

4.159.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Analyze resource management policy
	Test Data	No data.
	Expected Result	

4.160   LVV-T173 - Verify implementation of Pipeline Throughput

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T173 in Jira

4.160.1   Verification Elements

- LVV-65 - DMS-REQ-0162-V-01: Pipeline Throughput

4.160.2   Test Items

Demonstrate that the Alert Production Pipeline is capable of processing nRawExpNightMax (2800) science exposures within a (24-nightDurationMax) 12 hour period and issue alerts in offline batch mode.

4.160.3   Predecessors

4.160.4   Environment Needs

4.160.4.1   Software

4.160.4.2   Hardware

4.160.5   Input Specification

Rubin Observatory

4.160.6   Output Specification

4.160.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal, observe data products generated in time
	Test Data	No data.
	Expected Result	

4.161   LVV-T174 - Verify implementation of Re-processing Capacity

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T174 in Jira

4.161.1   Verification Elements

• LVV-66 - DMS-REQ-0163-V-01: Re-processing Capacity

4.161.2   Test Items

Verify that the DMS has sufficient processing, storage, and network to reprocess all data within "drProcessingPeriod" (1 year) while maintaining full Prompt Processing capability.

4.161.3   Predecessors

4.161.4   Environment Needs

4.161.4.1   Software

Rubin Observatory

4.161.4.2   Hardware

4.161.5   Input Specification

4.161.6   Output Specification

4.161.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze sizing model; execute DRP, observe scaling
	Test Data	No data.
	Expected Result	

4.162   LVV-T175 - Verify implementation of Temporary Storage for Communications Links

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T175 in Jira

4.162.1   Verification Elements

- LVV-67 - DMS-REQ-0164-V-01: Temporary Storage for Communications Links

4.162.2   Test Items

Demonstrate that storage capacity is present and usable to prevent data loss if networking is interrupted between summit and base, base and archive, or archive and DAC. The requirement is to have storage necessary to hold tempStorageReIMTTR (200%) of the expected raw data that would arrive during the Mean Time to Repair (summToBaseNetMTTR = 24 hours, baseToArchNetMTTR = 48 hours, archToDacNetMTTR = 48 hours).   This scale is further set by nCalibExpDay + nRawExpNightMax = 450 + 2800 = 3250 exposures/day.

Rubin Observatory

4.162.3   Predecessors

4.162.4   Environment Needs

4.162.4.1   Software

4.162.4.2   Hardware

4.162.5   Input Specification

4.162.6   Output Specification

4.162.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze sizing model and network/storage design
	Test Data	No data.
	Expected Result	

4.163   LVV-T176 - Verify implementation of Infrastructure Sizing for "catching up"

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T176 in Jira

4.163.1   Verification Elements

- LVV-68 - DMS-REQ-0165-V-01: Infrastructure Sizing for "catching up"

- LVV-994 - OSS-REQ-0051-V-01: Summit-Base Connectivity Loss

Rubin Observatory

4.163.2   Test Items

Demonstrate Data Management System has sufficient excess capacity (compute infrastructure) to process one night's data (2800 exposures) within 24 hours while also maintaining nightly Alert Production (note this is very similar to LVV-T173).

4.163.3   Predecessors

4.163.4   Environment Needs

4.163.4.1   Software

4.163.4.2   Hardware

4.163.5   Input Specification

4.163.6   Output Specification

4.163.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute single-day operations rehearsal including catch-up after failure, observe data products generated in time
	Test Data	No data.
	Expected Result	

4.164   LVV-T177 - Verify implementation of Incorporate Fault-Tolerance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T177 in Jira

4.164.1   Verification Elements

- LVV-69 - DMS-REQ-0166-V-01: Incorporate Fault-Tolerance

4.164.2   Test Items

Demonstrate that Data Management Systems have features that prevent data loss. Includes: MD5SUM/checksum verification for data transfer; RAID to eliminate single-point disk failures; multi-site and tape for disaster recovery of raw data; multiple site (and tape?) for backup/re-covery of Data Release products; DB transaction logging and backup to maintain DB integrity. (Note: storage to prevent loss in case of networking failures is covered in LVV-T175).

4.164.3   Predecessors

4.164.4   Environment Needs

4.164.4.1   Software

4.164.4.2   Hardware

4.164.5   Input Specification

4.164.6   Output Specification

4.164.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design; execute single-day operations rehearsal including failures, observe recovery without loss of data
	Test Data	No data.
	Expected Result	

4.165 LVV-T178 - Verify implementation of Incorporate Autonomics

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T178 in Jira

4.165.1 Verification Elements

- LVV-70 - DMS-REQ-0167-V-01: Incorporate Autonomics

4.165.2 Test Items

Demonstrate that production systems monitor and report faults. Where possible fault mitigation can include re-start, re-submission, or return of partial products for triage.

4.165.3 Predecessors

4.165.4 Environment Needs

4.165.4.1 Software

4.165.4.2 Hardware

4.165.5 Input Specification

4.165.6 Output Specification

4.165.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design; execute single-day operations rehearsal including failures, observe automated recovery and continuation of processing

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

288

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	

4.166 LVV-T179 - Verify implementation of Compute Platform Heterogeneity

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T179 in Jira

4.166.1 Verification Elements

- LVV-145 - DMS-REQ-0314-V-01: Compute Platform Heterogeneity

4.166.2 Test Items

Demonstrate that production results are the same (within machine accuracy) when production occurs on different platforms (OS, kernel, hardware provisioning).

4.166.3 Predecessors

4.166.4 Environment Needs

4.166.4.1 Software

4.166.4.2 Hardware

4.166.5 Input Specification

Rubin Observatory

4.166.6   Output Specification

4.166.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Configure heterogeneous cluster, execute AP+DRP+LSP, observe correct functioning
	Test Data	No data.
	Expected Result	

4.167   LVV-T180 - Verify implementation of Data Management Unscheduled Down-time

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T180 in Jira

4.167.1   Verification Elements

- LVV-149 - DMS-REQ-0318-V-01: Data Management Unscheduled Downtime

4.167.2   Test Items

This applies only to downtime that would prevent the collection of survey data. Verification means that analysis has occurred to identify likely hardware failures that would prevent survey operations and that mitigations that minimize the downtime to less than DMDowntime (1 day/year) are in place. Known systems that fall in this category include: Image and EFD Archiving, Observatory Operations Data, Telemetry Gateway, Data Backbone, Managed Database, Inter-Site Networks, and Service Management and Monitoring.

4.167.3   Predecessors

Rubin Observatory

4.167.4 Environment Needs

4.167.4.1 Software

4.167.4.2 Hardware

4.167.5 Input Specification

4.167.6 Output Specification

4.167.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze likely hardware failures with mitigations to compute estimated unplanned down-time
	Test Data	No data.
	Expected Result	

4.168 LVV-T181 - Verify Base Voice Over IP (VOIP)

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T181 in Jira

4.168.1 Verification Elements

• LVV-18491 - DMS-REQ-0352-V-02: Base Voice Over IP (VOIP)

Rubin Observatory

4.168.2   Test Items

Verify as-built VOIP at the Base Facility is operational and performs as expected (i.e. sufficient number of extensions allocated properly, no frequent drop-outs, no frequent jaggies on video, etc.) on both voice calls and videoconferening.

4.168.3   Predecessors

PMCS DLP-465 Complete
PMCS IT-702 Complete

4.168.4   Environment Needs

4.168.4.1   Software   See pre-conditions.

4.168.4.2   Hardware   See pre-conditions.

4.168.5   Input Specification

1. Base VOIP is installed/configured and Test Personnel have phone sets. Base Videoconference system is installed/configured. Summit, Headquarters, and/or LDF Videoconference system is installed/configured.
2. As-built documentation for all of the above is available.

4.168.6   Output Specification

4.168.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Test voice calls over VOIP system from Base Facility to locations in Base and to other Rubin Observatory facilities.
	Test Data	No data.
	Expected Result	As-built VOIP at the Base Facility is operational and performs as expected (i.e. sufficient number of extensions allocated properly, no frequent drop-outs, etc.).

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Test video conferences over system from Base Facility to locations in Base and to other Rubin Observatory facilities.
	Test Data	No data.
	Expected Result	Verify (a) plannned and (b) as-built VOIP at the Base Facility is operational and performs as expected (i.e. no frequent drop-outs, no frequent audio glitches, no frequent jaggies on video, etc.).

4.169   LVV-T182 - Verify implementation of Prefer Computing and Storage Down

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T182 in Jira

4.169.1   Verification Elements

• LVV-72 - DMS-REQ-0170-V-01: Prefer Computing and Storage Down

4.169.2   Test Items

Only build compute or storage facilities at the summit that are justified by operational need or to prevent loss of data during networking downtimes.

4.169.3   Predecessors

4.169.4   Environment Needs

4.169.4.1   Software

4.169.4.2   Hardware

Rubin Observatory

4.169.5 Input Specification

4.169.6 Output Specification

4.169.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design
	Test Data	No data.
	Expected Result	

4.170 LVV-T183 - Verify implementation of DMS Communication with OCS

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Gregory Dubois-Felsmann

Open LVV-T183 in Jira

4.170.1 Verification Elements

- LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS

4.170.2 Test Items

Verify that the DMS at the Base Facility can receive commands from the OCS and send command responses, events, and telemetry back. Verified by Early Integration activities and during AuxTel commissioning.

4.170.3 Predecessors

Rubin Observatory

4.170.4   Environment Needs

4.170.4.1   Software

4.170.4.2   Hardware

4.170.5   Input Specification

4.170.6   Output Specification

4.170.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	From the Base Site, connect to the (simulated) OCS telemetry stream.
	Test Data	No data.
	Expected Result	
2	Description	Send a command to the OCS, and observe that the command has been executed.
	Test Data	No data.
	Expected Result	Confirmation that the OCS command successfully executed.
3	Description	Extract information from the telemetry being broadcast by the OCS, and ensure that these data are readable.
	Test Data	No data.
	Expected Result	A readable extract from the OCS telemetry stream.

4.171   LVV-T185 - Verify implementation of Summit to Base Network Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Jeff Kantor
		Open LVV-T185 in Jira		

Rubin Observatory

4.171.1 Verification Elements

- LVV-74 - DMS-REQ-0172-V-01: Summit to Base Network Availability

4.171.2 Test Items

Verify the availability of Summit to Base Network by demonstrating that the mean time between failures is less than summToBaseNetMTBF (90 days) over 1 year.

4.171.3 Predecessors

See pre-conditions.

4.171.4 Environment Needs

4.171.4.1 Software   See pre-conditions.

4.171.4.2 Hardware   See pre-conditions.

4.171.5 Input Specification

1. PMCS DMTC-7400-2400 Complete.
2. 6 months of historical availability data for this link is available.
3. perSonar installed in Summit and publishing statistics to MadDash.
4. As-built documentation for all of the above is available.

NOE: After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.171.6 Output Specification

Rubin Observatory

4.171.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Monitor summit to base networking for at least 1 week
	Test Data	LATISS, ComCAM, and/or Full Camera data.
	Expected Result	Summit - base network is operational for 1 week and monitoring data is collected.
2	Description	Extrapolate annual availability, compare with at least 6 months of historical data on the link.
	Test Data	Historical and current logs
	Expected Result	The mean time between failures (MTBF) is projected to be less than summTo-BaseNetMTBF (90 days) over 1 year.

4.172 LVV-T186 - Verify implementation of Summit to Base Network Reliability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeff Kantor

Open LVV-T186 in Jira

4.172.1 Verification Elements

- LVV-75 - DMS-REQ-0173-V-01: Summit to Base Network Reliability

4.172.2 Test Items

Verify the reliability of the summit to base network by demonstrating reconnection and recovery to transfer of data at or exceeding rates specified in LDM-142 following a cut in network connection, within MTTR specification. The network operator will provide MTTR data on links during commissioning and operations.

Rubin Observatory

4.172.3   Predecessors

See pre-conditions.

4.172.4   Environment Needs

4.172.4.1   Software   See pre-conditions.

4.172.4.2   Hardware   See pre-conditions.

4.172.5   Input Specification

1. PMCS DMTC-7400-2400 Complete
2. As-built documentation for Summit - Base Network is available.

NOTE: After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.172.6   Output Specification

4.172.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Disconnect fiber cable at an endpoint location on the base side of the Summit - Base fiber.
	Test Data	LATISS, ComCAM, or FullCam data
	Expected Result	Fiber is disconnected and the fault is detected by the network monitoring system.
2	Description	Measure the cable with the OTDR to locate the distance from the end point. Diagnose that it is a break.
	Test Data	NA
	Expected Result	OTDR shows the fiber is disconnected (break).

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Elapse time to simulate the following: • Go to the most inaccessible place which would mean carrying all the tools/splicer/-generator/tent equipment some metres. • Erect a tent to make the splice • Start the generator • Do a splice on some random piece of cable • At an end point measure the cable again to ensure it is break free. • Take down and reinstall an isolated pole (not in the actual fiber path) • Put the cable on the pole.
	Test Data	NA
	Expected Result	Wall clock advances by 24 hours.
4	Description	Clean fiber connections. Restore connection (e.g. reconnect cable). Cycle equipment as necessary to confirm fiber is connected.
	Test Data	NA
	Expected Result	Network recovers and resumes sending data.
5	Description	Measure with OTDR to ensure back to normal state.
	Test Data	NA
	Expected Result	OTDR indicates normal state.

4.173   LVV-T187 - Verify implementation of Summit to Base Network Secondary Link

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T187 in Jira

4.173.1   Verification Elements

• LVV-76 - DMS-REQ-0174-V-01: Summit to Base Network Secondary Link

Rubin Observatory

4.173.2   Test Items

Verify automated fail-over from primary to secondary equipment in Rubin Observatory DWDM on simulated failure of primary.   Verify bandwidth sufficiency on secondary.   Verify automated recovery to primary equipment on simulated restoration of primary.   Repeat for failure of Rubin Observatory fiber and fail-over to AURA fiber and DWDM. Demonstrate use of secondary in "catch-up" mode.

4.173.3   Predecessors

See pre-conditions.

4.173.4   Environment Needs

4.173.4.1   Software   See pre-conditions.

4.173.4.2   Hardware   See pre-conditions.

4.173.5   Input Specification

1. PMCS DMTC-7400-2400 complete.
2. As-built documentation for Summit - Base Network is available.

NOTE: After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.173.6   Output Specification

4.173.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between summit and base on primary equipment (LSST Summit - Base) over uninterrupted 1 day period.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Normal operations.
2	Description	Simulate equipment outage by disconnecting power card from primary DWDM equipment on base side of Summit - Base Fiber.
	Test Data	NA
	Expected Result	Network fails over to secondary equipment in <=60s.
3	Description	Transfer data between summit and base over secondary equipment uninterrupted 1 day period while monitoring network.
	Test Data	NA
	Expected Result	Verify that secondary equipment is capable of transferring 1 night of raw data (nCalibExpDay + nRawExpNightMax = 450 + 2800 = 3250 exposures) within summToBaseNet2TransMax (72 hours), i.e. at or exceeding rates specified in LDM-142.
4	Description	Restore primary equipment (i.e. reconnect power card to primary equipment.)
	Test Data	NA
	Expected Result	Network recovers to primary in <= 60s.
5	Description	Simulate fiber outage by disconnecting fiber from primary DWDM equipment on base side of Summit - Base Fiber.
	Test Data	NA
	Expected Result	Network fails over to AURA DWDM and fiber.
6	Description	Transfer data between summit and base over AURA fiber and equipment uninterrupted 1 day period while monitoring network.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Verify that AURA fiber and equipment is capable of transferring 1 night of raw data (nCalibExpDay + nRawExpNightMax = 450 + 2800 = 3250 exposures) within summToBaseNet2TransMax (72 hours), i.e. at or exceeding rates specified in LDM-142.
7	Description	Restore primary fiber (i.e. reconnect fiber to Rubin Observatory DWDM equipment.)
	Test Data	No data.
	Expected Result	Network recovers to Rubin Observatory fiber and DWDM.

Rubin Observatory

Step	Description, Input Data and Expected Result	
8	Description	Demonstrate use of secondary in "catch-up" mode.
	Test Data	DAQ data buffer full of images and associated meta-data
	Expected Result	Images from DAQ buffer and associated metadata are retrievable over secondary path while current observing data is being transferred over primary path.

4.174 LVV-T188 - Verify implementation of Summit to Base Network Ownership and Operation

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Jeff Kantor

Open LVV-T188 in Jira

4.174.1 Verification Elements

- LVV-77 - DMS-REQ-0175-V-01: Summit to Base Network Ownership and Operation

4.174.2 Test Items

Verify Summit to Base Network Ownership and Operation by LSST and/or the operations entity by inspection of construction and operations contracts and Indefeasible Rights.

4.174.3 Predecessors

PMCS DMTC-7400-2140, -2240, -2330 Complete

4.174.4 Environment Needs

4.174.4.1 Software   None

4.174.4.2 Hardware   None

4.174.5   Input Specification

1. As-built documentation for all of the above contracts and IRUs is available.

4.174.6   Output Specification

4.174.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Examine contracts with REUNA and telefonica for fiber ownership and maintenance terms.
	Test Data	No data.
	Expected Result	Rubin Observatory is owner of fibers on AURA property and Summit - Base DWDM and has 15-year IRU for use of fibers on all segments. REUNA is owner of LS - SCL DWDM on AURA property and in Santiago, and is operator on all fibers and DWDM. Telefonica is contracted to maintain fibers not on AURA property.

4.175   LVV-T189 - Verify implementation of Base Facility Infrastructure

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T189 in Jira

4.175.1   Verification Elements

• LVV-78 - DMS-REQ-0176-V-01: Base Facility Infrastructure

4.175.2   Test Items

Verify that the (a) planned infrastructure and (b) as-built infrastructure for the Base Facility satisfies the needs for data transfer and buffering, a copy of the Archive Facility, and support for Commissioning.

Rubin Observatory

4.175.3   Predecessors

4.175.4   Environment Needs

4.175.4.1   Software

4.175.4.2   Hardware

4.175.5   Input Specification

4.175.6   Output Specification

4.175.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design and sizing model
	Test Data	No data.
	Expected Result	

4.176   LVV-T190 - Verify implementation of Base Facility Co-Location with Existing Facility

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T190 in Jira

4.176.1   Verification Elements

- LVV-80 - DMS-REQ-0178-V-01: Base Facility Co-Location with Existing Facility

4.176.2   Test Items

Verify that the Base Facility is located at an existing known supported facility.

4.176.3   Predecessors

4.176.4   Environment Needs

4.176.4.1   Software

4.176.4.2   Hardware

4.176.5   Input Specification

4.176.6   Output Specification

4.176.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design
	Test Data	No data.
	Expected Result	

4.177   LVV-T191 - Verify implementation of Commissioning Cluster

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T191 in Jira

Rubin Observatory

4.177.1 Verification Elements

- LVV-147 - DMS-REQ-0316-V-01: Commissioning Cluster

4.177.2 Test Items

Verify that the Commissioning Cluster has sufficient Compute/Storage/LAN at the Base Facility to support Commissioning.

4.177.3 Predecessors

4.177.4 Environment Needs

4.177.4.1 Software

4.177.4.2 Hardware

4.177.5 Input Specification

4.177.6 Output Specification

4.177.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design and budget
	Test Data	No data.
	Expected Result	

4.178 LVV-T192 - Verify implementation of Base Wireless LAN (WiFi)

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Test	Jeff Kantor

Open LVV-T192 in Jira

4.178.1   Verification Elements

- LVV-183 - DMS-REQ-0352-V-01: Base Wireless LAN (WiFi)

4.178.2   Test Items

Verify as-built wireless network at the Base Facility supports minBaseWiFi bandwidth (1000 Mbs).

4.178.3   Predecessors

PMCS DLP-465 Complete.

4.178.4   Environment Needs

4.178.4.1   **Software**   See pre-conditions.

4.178.4.2   **Hardware**   Desktop with WiFi NIC, email reader, internet browser.

4.178.5   Input Specification

1. Base Wireless LAN is installed/configured and Test Personnel have accounts for email, internet access.
2. As-built documentation for all of the above is available.

4.178.6   Output Specification

4.178.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Test internet web browsing and file download, email at summit and base over wireless.
	Test Data	NA
	Expected Result	Verify as-built wireless network at the Base Facility supports minBaseWiFi bandwidth (1000 Mbs). Verify wireless signal strength meets or exceeds typical, and average and peak bandwidths meet or exceed minBaseWiFI bandwidth.

4.179   LVV-T193 - Verify implementation of Base to Archive Network

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T193 in Jira

4.179.1   Verification Elements

• LVV-81 - DMS-REQ-0180-V-01: Base to Archive Network

4.179.2   Test Items

Verify that the data acquired by a DAQ can be transferred within the required time, i.e. verify that link is capable of transferring image for prompt processing in oArchiveMaxTransferTime = 5[second], i.e. at or exceeding rates specified in LDM-142.

4.179.3   Predecessors

PMCS DM-Net-5 Complete

4.179.4   Environment Needs

4.179.4.1   Software   See pre-conditions.

Rubin Observatory

4.179.4.2 Hardware   See pre-conditions.

4.179.5 Input Specification

1. Archiver/Forwarders are configured at Base, connected to REUNA DWDM, loaded with simulated or pre-cursor data, running on end node computers that are the production hardware or equivalent to it.
2. Archiver/Forwarder receivers or other capability is on configured at LDF, connected to Base - Archive Network, running on end node computers that are the production hardware or equivalent to it.
3. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.179.6 Output Specification

4.179.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between base and archive while monitoring the network over uninterrupted 1 day period (with repeated transfers on normal observing cadence).
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Data transfers occur without significant delay or frequent latency spikes.
2	Description	Analyze the network logs and monitoring system to determine average and peak latency and packet loss statistics.
	Test Data	No data.
	Expected Result	Data can be transferred within the required time, i.e. verify that link is capable of transferring image for prompt processing in oArchiveMaxTransferTime = 5[second]. Verify transfer of data at or exceeding rates specified in LDM-142 at least 98% of the time.

Rubin Observatory

4.180 LVV-T194 - Verify implementation of Base to Archive Network Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T194 in Jira

4.180.1 Verification Elements

- LVV-82 - DMS-REQ-0181-V-01: Base to Archive Network Availability

4.180.2 Test Items

Verify the availability of the Base to Archive Network communications by demonstrating that it meets or exceeds a mean time between failures, measured over a 1-yr period of MTBF > baseToArchNetMTBF (180[day])

4.180.3 Predecessors

PMCS DMTC-7400-2130 Complete

4.180.4 Environment Needs

4.180.4.1 Software

4.180.4.2 Hardware

4.180.5 Input Specification

1. Archiver/Forwarders are configured at Base, connected to REUNA DWDM, loaded with simulated or pre-cursor data, running on end node computers that are the production hardware or equivalent to it.

Rubin Observatory

2. Archiver/Forwarder receivers or other capability is on configured at LDF, connected to Base - Archive Network, running on end node computers that are the production hardware or equivalent to it.
3. At least 6 months of historical monitoring data on this link is available.
4. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.180.6   Output Specification

4.180.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between base and archive over uninterrupted 1 week period.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Data is successfully transferred during the entire week.
2	Description	Analyze monitoring/performance data, compare to historical data, and extrapolate to a full year, average and peak throughput and latency.
	Test Data	NA
	Expected Result	Extrapolated network availability meets baseToArchNetMTBF = 180[day]. Note that this is for complete loss of transfer service (all paths), not a single path failure with successful fail-over.

4.181   LVV-T195 - Verify implementation of Base to Archive Network Reliability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T195 in Jira

Rubin Observatory

4.181.1   Verification Elements

- LVV-83 - DMS-REQ-0182-V-01: Base to Archive Network Reliability

4.181.2   Test Items

Verify Base to Archive Network Reliability by demonstrating that the network can recover from outages within baseToArchNetMTTR = 48[hour].

4.181.3   Predecessors

PMCS DM-NET-5 Complete

4.181.4   Environment Needs

4.181.4.1   Software   See pre-conditions.

4.181.4.2   Hardware   See pre-conditions.

4.181.5   Input Specification

1. Archiver/Forwarders are configured at Base, connected to REUNA DWDM, loaded with simulated or pre-cursor data, running on end node computers that are the production hardware or equivalent to it.
2. Archiver/Forwarder receivers or other capability is on configured at LDF, connected to Base - Archive Network, running on end node computers that are the production hardware or equivalent to it.
3. At least 6 months of monitoring data for this link is available.
4. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as

Rubin Observatory

"Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.181.6   Output Specification

4.181.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Disconnect primary fiber on base side of Base - Archive network.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Network fails over to secondary path.
2	Description	Simulate diagnosis and repair by elapsed time.
	Test Data	NA
	Expected Result	Wall clock advances by 48 hours. Data is successfully transferred over secondary path.
3	Description	Reconnect primary fiber on base side of Base - Archive network.
	Test Data	NA
	Expected Result	Network recovers to primary path.
4	Description	Analyze fail-over and recovery times. Compare to historical data and extrapolate to MTTR.
	Test Data	No data.
	Expected Result	Verify recovery can occur within baseToArchNetMTTR = 48[hour]. Demonstrate reconnection and recovery to transfer of data at or exceeding rates specified in LDM-142.

4.182   LVV-T196 - Verify implementation of Base to Archive Network Secondary Link

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T196 in Jira

4.182.1   Verification Elements

- LVV-84 - DMS-REQ-0183-V-01: Base to Archive Network Secondary Link

4.182.2   Test Items

Verify Base to Archive Network Secondary Link failover and capacity, and subsequent recovery primary. Demonstrate the use of the secondary path in "catch-up" mode.

4.182.3   Predecessors

PMCS DM-NET-5 Complete
PMCS DMTC-8000-0990 Complete
PMCS DMTC-8100-2130 Complete
PMCS DMTC-8100-2530 Complete
PMCS DMTC-8200-0600 Complete

4.182.4   Environment Needs

4.182.4.1   Software   See pre-conditions.

4.182.4.2   Hardware   See pre-conditions.

4.182.5   Input Specification

1. Archiver/Forwarders are configured at Base, connected to REUNA DWDM, loaded with simulated or pre-cursor data, running on end node computers that are the production

Rubin Observatory

hardware or equivalent to it.

2. Archiver/Forwarder receivers or other capability is on configured at LDF, connected to Base - Archive Network, running on end node computers that are the production hardware or equivalent to it.

3. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.182.6   Output Specification

4.182.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between base and archive on primary links over uninterrupted 1 day period.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Data is successfully transferred over primary link at or exceeding rates specified in LDM-142 throughout period.
2	Description	Simulate outage by disconnecting fiber on primary fiber on Base side of Base - Archive Network.
	Test Data	NA
	Expected Result	Network fails over to secondary links in <=60s
3	Description	Transfer data between base and archive over secondary equipment uninterrupted 1 day period.
	Test Data	LATISS, ComCAM, or FullCAM data.
	Expected Result	Data is successfully transferred over secondary link at or exceeding rates specified in LDM-142 throughout period.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

315

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Restore connection on primary link by reconnecting fiber.
	Test Data	NA
	Expected Result	Network recovers to primary.
5	Description	Demonstrate use of secondary in catch-up mode.
	Test Data	DAQ buffer full of images and associated metadata.
	Expected Result	Images from DAQ buffer and associated metadata are retrievable over secondary path while current observing data is being transferred over primary path.

4.183   LVV-T197 - Verify implementation of Archive Center

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T197 in Jira

4.183.1   Verification Elements

• LVV-85 - DMS-REQ-0185-V-01: Archive Center

4.183.2   Test Items

Verify that the Archive Center is sufficiently provisioned to support prompt processing, DRP, and data access needs.

4.183.3   Predecessors

Rubin Observatory

4.183.4   Environment Needs

4.183.4.1   Software

4.183.4.2   Hardware

4.183.5   Input Specification

4.183.6   Output Specification

4.183.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design and sizing model
	Test Data	No data.
	Expected Result	

4.184   LVV-T198 - Verify implementation of Archive Center Disaster Recovery

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T198 in Jira

4.184.1   Verification Elements

- LVV-86 - DMS-REQ-0186-V-01: Archive Center Disaster Recovery

4.184.2   Test Items

Verify disaster recovery plan for Archive Center.

Rubin Observatory

4.184.3   Predecessors

4.184.4   Environment Needs

4.184.4.1   Software

4.184.4.2   Hardware

4.184.5   Input Specification

4.184.6   Output Specification

4.184.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design; simulate storage failure, observe restore from disaster recovery
	Test Data	No data.
	Expected Result	

4.185   LVV-T199 - Verify implementation of Archive Center Co-Location with Existing Facility

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T199 in Jira

4.185.1   Verification Elements

- LVV-87 - DMS-REQ-0187-V-01: Archive Center Co-Location with Existing Facility

4.185.2 Test Items

Verify the Archive Center is located at an existing supported facility.

4.185.3 Predecessors

4.185.4 Environment Needs

4.185.4.1   Software

4.185.4.2   Hardware

4.185.5 Input Specification

4.185.6 Output Specification

4.185.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design
	Test Data	No data.
	Expected Result	

4.186   LVV-T200 - Verify implementation of Archive to Data Access Center Network

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T200 in Jira

4.186.1 Verification Elements

- LVV-88 - DMS-REQ-0188-V-01: Archive to Data Access Center Network

4.186.2 Test Items

Verify archiving of data to Data Access Center Network at or exceeding rates specified in LDM-142, i.e at archToDacBandwidth = 10000[megabit per second].

4.186.3 Predecessors

PMCS DMTC-8100-2550 Complete

4.186.4 Environment Needs

4.186.4.1 Software See pre-conditions.

4.186.4.2 Hardware See pre-conditions.

4.186.5 Input Specification

1. Data is staged in LDF and data transfer capabilities to US DAC and Chilean DAC are in place, running on end node computers that are the production hardware or equivalent to it.
2. At least 6 months of historical monitoring data is available on these network links.
3. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

Rubin Observatory

4.186.6   Output Specification

4.186.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data from Data Facility to US and Chilean DACs over an uninterrupted 1 week period.
	Test Data	Data Release
	Expected Result	Data transfers without significant failures or extended latency spikes
2	Description	Analyze network logs and compare with historical data on the links.
	Test Data	NA
	Expected Result	The networks can transfer data at archToDacBandwidth = 10000[megabit per second], i.e. at or exceeding rates specified in LDM-142.

4.187   LVV-T201 - Verify implementation of Archive to Data Access Center Network Availability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T201 in Jira

4.187.1   Verification Elements

- LVV-89 - DMS-REQ-0189-V-01: Archive to Data Access Center Network Availability

Rubin Observatory

4.187.2   Test Items

Verify availability of archiving to Data Access Center Network using test and historical data of or exceeding archToDacNetMTBF= 180[day].

4.187.3   Predecessors

PMCS DMTC-8100-2550 Complete

4.187.4   Environment Needs

4.187.4.1   Software   See pre-conditions.

4.187.4.2   Hardware   See pre-conditions.

4.187.5   Input Specification

1. Data is staged in LDF and data transfer capabilities to US DAC and Chilean DAC are in place, running on end node computers that are the production hardware or equivalent to it.
2. At least 6 months of historical monitoring data is available on these network links, running on end node computers that are the production hardware or equivalent to it.
3. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.187.6 Output Specification

4.187.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between archive and DACs over uninterrupted 1 week period.
	Test Data	Data Release or petabyte-scale test data set
	Expected Result	Data transfers without failures or extended latency spikes
2	Description	Analyze test data and compare to historical data. Extrapolate to 1 year testimate of MTBF.
	Test Data	NA
	Expected Result	Networks can meet archToDacNetMTBF = 180[day] at or exceeding rates specified in LDM-142.

4.188 LVV-T202 - Verify implementation of Archive to Data Access Center Network Reliability

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T202 in Jira

4.188.1 Verification Elements

• LVV-90 - DMS-REQ-0190-V-01: Archive to Data Access Center Network Reliability

4.188.2 Test Items

Verify the reliability of Archive to Data Access Center Network by demonstrating successful failover and capacity to the secondary part and subsequent recovery to primary within or exceeding chToDacNetMTTR = 48[hour].

Rubin Observatory

4.188.3   Predecessors

PMCS DMTC-8100-2550 Complete

4.188.4   Environment Needs

4.188.4.1   Software   See pre-conditions.

4.188.4.2   Hardware   See pre-conditions.

4.188.5   Input Specification

1. Data is staged in LDF and data transfer capabilities to US DAC and Chilean DAC are in place, running on end node computers that are the production hardware or equivalent to it.
2. As-built documentation for all of the above is available.
3. NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.188.6   Output Specification

4.188.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Simulate failure on primary paths by disconnecting fiber at an endpoint location in the archive on the Archive - DACs network.
	Test Data	NA
	Expected Result	Networks fail over to secondary paths.
2	Description	Monitor transfers on secondary paths for 1 day.

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	Transfers occur without extended failures or extended latency spikes. Data transfers on secondary at rates at or above those specified in LDM-142.
3	Description	Simulate repair and recovery period by leaving primary fiber disconnected for at least 1 day, then reconnecting primary fiber.
	Test Data	NA
	Expected Result	Wall clock advances by 1 day. Network recovers to primary path. Verify entire process meets chToDacNetMTTR = 48[hour].

4.189   LVV-T203 - Verify implementation of Archive to Data Access Center Network Secondary Link

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T203 in Jira

4.189.1   Verification Elements

- LVV-91 - DMS-REQ-0191-V-01: Archive to Data Access Center Network Secondary Link

4.189.2   Test Items

Verify the Archive to Data Access Center Network via Secondary Link by simulating a failure on the primary path and capacity on the secondary path.

4.189.3   Predecessors

PMCS DMTC-8100-2550 Complete

Rubin Observatory

4.189.4   Environment Needs

4.189.4.1   Software   See pre-conditions.

4.189.4.2   Hardware   See pre-conditions.

4.189.5   Input Specification

1. Data is staged in LDF and data transfer capabilities to US DAC and Chilean DAC are in place, running on end node computers that are the production hardware or equivalent to it.
2. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.189.6   Output Specification

4.189.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Transfer data between Archive and DACs on primary path over uninterrupted 1 week period.
	Test Data	Data Release or other petabyte-scale test data set.
	Expected Result	Data transfers without failures or extended latency spikes, at or exceeding rates specified in LDM-142 throughout fail-over period.
2	Description	Simulate outage on primary path by disconnecting fiber on primary on Archive side of Archive - DACs networks.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	NA
	Expected Result	Network fails over to secondary links in <= 60s.
3	Description	Transfer data between base and archive over secondary equipment uninterrupted 1 day period.
	Test Data	Data Release or other petabyte-scale test data set.
	Expected Result	Data transfers without failures or extended latency spikes, at or exceeding rates specified in LDM-142 throughout fail-over period.
4	Description	Restore connection on primary link (reconnect fiber).
	Test Data	NA
	Expected Result	Network recovers to primary in <= 60s.

4.190   LVV-T204 - Verify implementation of Access to catalogs for external Level 3 processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T204 in Jira

4.190.1   Verification Elements

• LVV-50 - DMS-REQ-0122-V-01: Access to catalogs for external Level 3 processing

4.190.2   Test Items

Verify that catalog export, and maintenance/validation tools for Level 3 products to outside of the Data Access Centers.

4.190.3   Predecessors

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

327

4.190.4 Environment Needs

4.190.4.1 Software

4.190.4.2 Hardware

4.190.5 Input Specification

4.190.6 Output Specification

4.190.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute bulk distribution of DRP catalogs
	Test Data	No data.
	Expected Result	
2	Description	Observe correct transfer and use of maintenance/validation tools
	Test Data	No data.
	Expected Result	

4.191 LVV-T205 - Verify implementation of Access to input catalogs for DAC-based Level 3 processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Robert Gruendl

Open LVV-T205 in Jira

Rubin Observatory

4.191.1   Verification Elements

- LVV-51 - DMS-REQ-0123-V-01: Access to input catalogs for DAC-based Level 3 processing

4.191.2   Test Items

Verify that data products are available at the Data Access Centers for use in Level 3 processing.

4.191.3   Predecessors

4.191.4   Environment Needs

4.191.4.1   Software

4.191.4.2   Hardware

4.191.5   Input Specification

4.191.6   Output Specification

4.191.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Load Prompt and DR catalogs into PDAC, observe access via LSP
	Test Data	No data.
	Expected Result	

4.192   LVV-T206 - Verify implementation of Federation with external catalogs

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Test	Colin Slater

Open LVV-T206 in Jira

4.192.1   Verification Elements

- LVV-52 - DMS-REQ-0124-V-01: Federation with external catalogs

4.192.2   Test Items

Verify that LSST-produced data can be combined with external datasets.

4.192.3   Predecessors

4.192.4   Environment Needs

4.192.4.1   Software

4.192.4.2   Hardware

4.192.5   Input Specification

4.192.6   Output Specification

4.192.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Load external catalog into PDAC (using VO if possible), observe federation with other catalogs via LSP
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.193   LVV-T207 - Verify implementation of Access to images for external Level 3 processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T207 in Jira

4.193.1   Verification Elements

- LVV-54 - DMS-REQ-0126-V-01: Access to images for external Level 3 processing

4.193.2   Test Items

Verify that bulk distribution of images, and accompanying maintenance/validation tools for Level 3 image products to outside of the Data Access Centers.

4.193.3   Predecessors

4.193.4   Environment Needs

4.193.4.1   Software

4.193.4.2   Hardware

4.193.5   Input Specification

4.193.6   Output Specification

4.193.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Execute bulk distribution of DRP images
	Test Data	No data.
	Expected Result	
2	Description	Observe correct transfer and use of maintenance/validation tools
	Test Data	No data.
	Expected Result	

4.194 LVV-T208 - Verify implementation of Access to input images for DAC-based Level 3 processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T208 in Jira

4.194.1 Verification Elements

- LVV-55 - DMS-REQ-0127-V-01: Access to input images for DAC-based Level 3 processing

4.194.2 Test Items

Verify that prompt processing and DRP products are available at the DACs for Level 3 processing at the DACs.

4.194.3 Predecessors

4.194.4 Environment Needs

4.194.4.1 Software

Rubin Observatory

4.194.4.2 Hardware

4.194.5 Input Specification

4.194.6 Output Specification

4.194.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Load Prompt and DR images into PDAC
	Test Data	No data.
	Expected Result	
2	Description	Observe access via LSP
	Test Data	No data.
	Expected Result	

4.195 LVV-T209 - Verify implementation of Data Access Centers

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Analysis	Kian-Tat Lim

Open LVV-T209 in Jira

4.195.1 Verification Elements

• LVV-92 - DMS-REQ-0193-V-01: Data Access Centers

4.195.2 Test Items

Verify that the Data Access Centers are provisioned with computing resources necessary to support end-user access to LSST Data Products.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

333

Rubin Observatory

4.195.3   Predecessors

4.195.4   Environment Needs

4.195.4.1   Software

4.195.4.2   Hardware

4.195.5   Input Specification

4.195.6   Output Specification

4.195.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design
	Test Data	No data.
	Expected Result	

4.196   LVV-T210 - Verify implementation of Data Access Center Simultaneous Connections

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T210 in Jira

4.196.1   Verification Elements

- LVV-93 - DMS-REQ-0194-V-01: Data Access Center Simultaneous Connections

4.196.2   Test Items

Verify that the each DAC can support at least dacMinConnections simultaneously

4.196.3   Predecessors

4.196.4   Environment Needs

4.196.4.1   Software

4.196.4.2   Hardware

4.196.5   Input Specification

4.196.6   Output Specification

4.196.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Simulate data access to PDAC
	Test Data	No data.
	Expected Result	
2	Description	Observe scaling
	Test Data	No data.
	Expected Result	

4.197   LVV-T211 - Verify implementation of Data Access Center Geographical Distribution

Version	Status	Priority	Verification Type	Owner

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. **– DRAFT NOT YET APPROVED**

335

Rubin Observatory

| 1 | Draft | Normal | Analysis | Kian-Tat Lim |

Open LVV-T211 in Jira

4.197.1   Verification Elements

- LVV-94 - DMS-REQ-0196-V-01: Data Access Center Geographical Distribution

4.197.2   Test Items

Verify that the DACs are geographically distributed to provide low-latency access to data-rights community.

4.197.3   Predecessors

4.197.4   Environment Needs

4.197.4.1   Software

4.197.4.2   Hardware

4.197.5   Input Specification

4.197.6   Output Specification

4.197.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design
	Test Data	No data.
	Expected Result	

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

336

Rubin Observatory

4.198   LVV-T212 - Verify implementation of No Limit on Data Access Centers

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Colin Slater

Open LVV-T212 in Jira

4.198.1   Verification Elements

- LVV-95 - DMS-REQ-0197-V-01: No Limit on Data Access Centers

4.198.2   Test Items

Verify that additional Data Access Centers can be set up.

4.198.3   Predecessors

4.198.4   Environment Needs

4.198.4.1   Software

4.198.4.2   Hardware

4.198.5   Input Specification

4.198.6   Output Specification

4.198.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Analyze design; instantiate and load simulated DAC, observe correct functioning
	Test Data	No data.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

337

Rubin Observatory

Step	Description, Input Data and Expected Result
	Expected
	Result

4.199   LVV-T216 - Installation of the Alert Distribution payloads.

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T216 in Jira

4.199.1   Verification Elements

- LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

4.199.2   Test Items

This test will check:

- That the Alert Distribution payloads are available from documented channels.
- That the Alert Distribution payloads can be installed on LSST Data Facility-managed systems.
- That the Alert Distribution payloads can be executed by LSST Data Facility-managed systems.

4.199.3   Predecessors

4.199.4   Environment Needs

4.199.4.1   Software

Rubin Observatory

4.199.4.2   Hardware   This test case shall be executed on the Kubernetes Commons at the LDF.

As discussed in https://dmtn-028.lsst.io/ and https://dmtn-081.lsst.io/, the test machine should have at least 16 cores, 64 GB of memory and access to at least 1.5 TB of shared storage.

4.199.5   Input Specification

4.199.6   Output Specification

4.199.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Download Kafka Docker image from https://github.com/lsst-dm/alert_stream.
	Test Data	No data.
	Expected Result	Runs without error
2	Description	Change to the alert_stream directory and build the docker image. `docker build -t "lsst-kub001:5000/alert_stream"`
	Test Data	No data.
	Expected Result	Runs without error
3	Description	Register it with Kubernetes `docker push lsst-kub001:5000/alert_stream`
	Test Data	No data.
	Expected Result	Runs without error

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	From the alert_stream/kubernetes directory, start Kafka and Zookeeper:

```
kubectl create -f zookeeper-service.yaml
kubectl create -f zookeeper-deployment.yaml
kubectl create -f kafka-deployment.yaml
kubectl create -f kafka-service.yaml
```

(use kubectl get pods/services between each command to check status; wait until each is "Running" before starting the next command)

	Test Data	No data.
	Expected Result	Runs without error

5	Description	Confirm Kafka and Zookeeper are listed when running

kubectl get pods

and

kubectl get services

	Test Data	No data.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

340

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Output should be similar to:

```
kubectl get pods
NAME                    READY   STATUS   RESTARTS  AGE
kafka-768ddf5564-xwgvh   1/1     Running  0        31s
zookeeper-f798cc548-mgkpn 1/1    Running  0        1m


kubectl get services
NAME      TYPE      CLUSTER-IP     EXTERNAL-IP  PORT(S)    AGE
kafka     ClusterIP  10.105.19.124  <none>       9092/TCP   6s
zookeeper  ClusterIP  10.97.110.124  <none>       32181/TCP  2m
```

4.200   LVV-T217 - Full Stream Alert Distribution

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T217 in Jira

4.200.1   Verification Elements

• LVV-3 - DMS-REQ-0002-V-01: Transient Alert Distribution

4.200.2   Test Items

This test will check that the full stream of LSST alerts can be distributed to end users.

Specifically, this will demonstrate that:

• Serialized alert packets can be loaded into the alert distribution system at LSST-relevant scales (10,000 alerts every 39 seconds);
• Alert packets can be retrieved from the queue system at LSST-relevant scales.

Rubin Observatory

4.200.3   Predecessors

LVV-T216

4.200.4   Environment Needs

4.200.4.1   Software   The Kafka cluster and Zookeeper shall be instantiated according to the procedure described in LVV-T216.

4.200.4.2   Hardware   This test case shall be executed on the Kubernetes Commons at the LDF.
As discussed in https://dmtn-028.lsst.io/ and https://dmtn-081.lsst.io/, the test machine should have at least 16 cores, 64 GB of memory and access to at least 1.5 TB of shared storage.

4.200.5   Input Specification

Input data: A sample of Avro-formatted alert packets.

4.200.6   Output Specification

Multiple Kafka consumers will run and write log files to disk.
The logs will include printing every *Nth* alert to to the log as well as a log summarizing the queue offset.

4.200.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

Step	Description, Input Data and Expected Result	
2	Description	Start a consumer that monitors the full stream and logs a deserialized version of every Nth packet: `kubectl create -f consumerall-deployment.yaml`
	Test Data	No data.
	Expected Result	Runs without error

3	Description	`Start a producer that reads alert packets from disk and loads them into the Kafka queue:`
		
		`kubectl create -f sender-deployment.yaml`

	Test Data	No data.
	Expected Result	Runs without error
4	Description	Determine the name of the alert sender pod with kubectl get pods Examine output log files. kubectl logs <pod name> Verify that alerts are being sent within 40 seconds by subtracting the timing measurements.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result

	Expected Result	Similar to

kubectl logs sender-7d6f98586f-nhwfj
visit: 1570.   time: 1530588618.0313473
visits finished: 1   time: 1530588653.5614944
visit: 1571.   time: 1530588657.0087624
visits finished: 2   time: 1530588692.506188
visit: 1572.   time: 1530588696.0051727
visits finished: 3   time: 1530588731.5900314

5	Description	Determine the name of the consumer pod with

kubectl get pods

Examine output log files.

kubectl logs <pod name>

The packet log should show deserialized alert packets with contents matching the input packets.

	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Similar to {'alertId': 12132024420, 'l1dbId': 71776805594116, 'diaSource': {'diaSourceId': 73499448928374785, 'ccdVisitId': 2020011570, 'diaObjectId': 71776805594116, 'ssObjectId': None, 'parentDiaSourceId': None, 'midPointTai': 59595.37041, 'filterName': 'y', 'ra': 172.24912810036074, 'decl': -80.64214929176521, 'ra_decl_Cov': {'raSigma': 0.0003428002819418907, 'declSigma': 0.00027273103478364646, 'ra_decl_Cov': 0.000628734880592674}, 'x': 2979.08837890625, 'y': 3843.328857421875, 'x_y_Cov': {'xSigma': 0.6135467886924744, 'ySigma': 0.77132648229599, 'x_y_Cov': 0.0007463791407644749}, 'apFlux': None, 'apFluxErr': None, 'snr': 0.36651650071144104, 'psFlux': 7.698232025177276e-07, 'psRa': None, 'psDecl': None, 'ps_Cov': None, 'psLnL': None, 'psChi2': None, 'psNdata': None, 'trailFlux': None, 'trailRa': etc.

4.201   LVV-T218 - Simple Filtering of the LSST Alert Stream

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T218 in Jira

4.201.1   Verification Elements

- LVV-173 - DMS-REQ-0342-V-01: Alert Filtering Service

- LVV-179 - DMS-REQ-0348-V-01: Pre-defined alert filters

- LVV-174 - DMS-REQ-0343-V-01: Number of full-size alerts

4.201.2   Test Items

This test will demonstrate the LSST Alert Filtering Service that returns a subset of alerts from the full stream identified by user-provided filters.

Specifically, this will demonstrate that:

Rubin Observatory

- The filtering service can retrieve alerts from the full alert stream and filter them according to their contents;
- The filtered subset can be delivered to science users.

4.201.3 Predecessors

LVV-T216
LVV-T217

4.201.4 Environment Needs

4.201.4.1 Software The Kafka cluster and Zookeeper shall be instantiated according to the procedure described in LVV-T216.

4.201.4.2 Hardware This test case shall be executed on the Kubernetes Commons at the LDF.
As discussed in https://dmtn-028.lsst.io/ and https://dmtn-081.lsst.io/, the test machine should have at least 16 cores, 64 GB of memory and access to at least 1.5 TB of shared storage.

4.201.5 Input Specification

Input data: A sample of Avro-formatted alert packets derived from LSST simulations corresponding to one night of simulated LSST observing.

4.201.6 Output Specification

4.201.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T216	Description	Download Kafka Docker image from https://github.com/lsst-dm/alert_stream.
	Test Data	
	Expected Result	Runs without error

Rubin Observatory

Step	Description, Input Data and Expected Result	
1-2 from LVV-T216	Description	Change to the alert_stream directory and build the docker image. `docker build –t "lsst-kub001:5000/alert_stream"`
	Test Data	
	Expected Result	Runs without error
1-3 from LVV-T216	Description	Register it with Kubernetes docker push lsst-kub001:5000/alert_stream
	Test Data	
	Expected Result	Runs without error

1-4 from LVV-T216	Description	From the alert_stream/kubernetes directory, start Kafka and Zookeeper:
		
		`kubectl create –f zookeeper-service.yaml`
		`kubectl create –f zookeeper-deployment.yaml`
		`kubectl create –f kafka-deployment.yaml`
		`kubectl create –f kafka-service.yaml`
		
		(use kubectl get pods/services between each command to check status; wait until each is "Running" before starting the next command)

	Test Data	
	Expected Result	Runs without error
1-5 from LVV-T216	Description	Confirm Kafka and Zookeeper are listed when running kubectl get pods and kubectl get services
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Output should be similar to:

```
kubectl get pods
NAME                    READY   STATUS   RESTARTS   AGE
kafka-768ddf5564-xwgvh    1/1     Running   0          31s
zookeeper-f798cc548-mgkpn  1/1     Running   0          1m


kubectl get services
NAME        TYPE      CLUSTER-IP      EXTERNAL-IP  PORT(S)     AGE
kafka     ClusterIP  10.105.19.124   <none>       9092/TCP    6s
zookeeper  ClusterIP  10.97.110.124  <none>       32181/TCP   2m
```

2	Description	Start 100 consumers that consume the filtered streams and logs a deserialized version of every Nth packet:

```
kubectl create -f consumer1-deployment.yaml
kubectl create -f consumer2-deployment.yaml
kubectl create -f consumer3-deployment.yaml
kubectl create -f consumer4-deployment.yaml
kubectl create -f consumer5-deployment.yaml
kubectl create -f consumer6-deployment.yaml
kubectl create -f consumer7-deployment.yaml
kubectl create -f consumer8-deployment.yaml
kubectl create -f consumer9-deployment.yaml
kubectl create -f consumer10-deployment.yaml
```

	Test Data	No data.
	Expected Result	Runs without error
3	Description	Start 5 filter groups:

```
kubectl create -f filterer1-deployment.yaml
kubectl create -f filterer2-deployment.yaml
kubectl create -f filterer3-deployment.yaml
kubectl create -f filterer4-deployment.yaml
kubectl create -f filterer5-deployment.yaml
```

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	Runs without error
4	Description	Start a producer that reads alert packets from disk and loads them into the Kafka queue:
		`kubectl create -f sender-deployment.yaml`
	Test Data	No data.
	Expected Result	Runs without error
5	Description	Determine the name of the alert sender pod with
		kubectl get pods
		Examine output log files.
		kubectl logs <pod name>
		Verify that alerts are being sent within 40 seconds by subtracting the timing measurements.
	Test Data	No data.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

349

Rubin Observatory

Step		Description, Input Data and Expected Result
	Expected Result	Similar to
		kubectl logs sender-7d6f98586f-nhwfj visit: 1570. time: 1530588618.0313473 visits finished: 1 time: 1530588653.5614944 visit: 1571. time: 1530588657.0087624 visits finished: 2 time: 1530588692.506188 visit: 1572. time: 1530588696.0051727 visits finished: 3 time: 1530588731.5900314
6	Description	Determine the name of the consumer pods with kubectl get pods Examine output log files. kubectl logs <pod name> The packet log should show deserialized alert packets with contents matching the input packets.
	Test Data	No data.
	Expected Result	Similar to
		{'alertId': 12132024420, 'l1dbId': 71776805594116, 'diaSource': {'diaSourceId': 73499448928374785, 'ccdVisitId': 2020011570, 'diaObjectId': 71776805594116, 'ssObjectId': None, 'parentDiaSourceId': None, 'midPointTai': 59595.37041, 'filterName': 'y', 'ra': 172.24912810036074, 'decl': -80.64214929176521, 'ra_decl_Cov': {'raSigma': 0.0003428002819418907, 'declSigma': 0.00027273103478364646, 'ra_decl_Cov': 0.000628734880592674}, 'x': 2979.08837890625, 'y': 3843.328857421875, 'x_y_Cov': {'xSigma': 0.6135467886924744, 'ySigma': 0.77132648229599, 'x_y_Cov': 0.0007463791407644749}, 'apFlux': None, 'apFluxErr': None, 'snr': 0.36651650071144104, 'psFlux': 7.698232025177276e-07, 'psRa': None, 'psDecl': None, 'ps_Cov': None, 'psLnL': None, 'psChi2': None, 'psNdata': None, 'trailFlux': None, 'trailRa': etc.

Rubin Observatory

4.202   LVV-T283 - RAS-00-00: Writing well-formed raw image

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Michelle Butler

Open LVV-T283 in Jira

4.202.1   Verification Elements

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition

- LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition

- LVV-96 - DMS-REQ-0265-V-01: Guider Calibration Data Acquisition

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly

- LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS

- LVV-115 - DMS-REQ-0284-V-01: Level-1 Production Completeness

4.202.2   Test Items

This test will check:

- The successful integration of the Pathfinder components with the DM Header Service and the Level 1 Archiver;
- That the raw images are well-formed and meet specifications in change-controlled documents LSE-61;

This Test Case shall be repeated for each of the different cameras (ATScam, LSSTCam) and sensors (Science, Wavefront, and Guider) combination.

Rubin Observatory

4.202.3   Predecessors

None.

4.202.4   Environment Needs

4.202.4.1   Software

- Level 1 software and services needed to create raw image
- LSST Monitoring Service and plugins specific to monitoring Level 1 Test Stand and services

4.202.4.2   Hardware

- Level 1 test stand
- Test machine for LSST Monitoring Service

4.202.5   Input Specification

None.

4.202.6   Output Specification

Raw image(s) that follow specifications defined in change-controlled document LSE-61.

4.202.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Configure system to pull appropriate data from the DAQ emulator
	Test Data	No data.
	Expected Result	A functional DAQ for images to be received from.

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Acquire raw data from DAQ readout and DMHS
	Test Data	No data.
	Expected Result	a raw image and a header from the DMHS
3	Description	Fetch data and reassemble correctly, regardless of CCD/Sensor manufacturer type (two different types will be used)
	Test Data	No data.
	Expected Result	Build the data into a fits file
4	Description	Check completeness and correctness of the raw images including format, metadata, and image data; • Check proper fetch and reassembly of image data from camera DAQ (correct format and data); • Check proper merge of header service data with image data; • Check correct insertion of exposure specific data needed in the data file that is not supplied by header service; • Check minimum required metadata (from requirements document LSE-61) exists in raw image header;
	Test Data	No data.
	Expected Result	a well formed FITS file with a proper header that has been verified to be correct.
5	Description	Check that the checksum of the file matches the previously calculated value that will be passed on to downstream services
	Test Data	No data.
	Expected Result	a MD5sum number generated from the step 4 file.
6	Description	Check confirmation that the data files arrive at their destination intact
	Test Data	No data.
	Expected Result	a transfer of the file to the correct location for further retrieval from other services.
7	Description	Check that LSST Monitoring Service showed the appropriate information successfully
	Test Data	No data.

Step	Description, Input Data and Expected Result
Expected Result	all systems remained green through out the test, and showed all systems up and available.

4.203 LVV-T284 - RAS-00-05: (LDM-503-8b) Writing data from CCOB to the DBB for further data processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Michelle Butler

Open LVV-T284 in Jira

4.203.1 Verification Elements

- LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition

- LVV-96 - DMS-REQ-0265-V-01: Guider Calibration Data Acquisition

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly

- LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS

- LVV-115 - DMS-REQ-0284-V-01: Level-1 Production Completeness

4.203.2 Test Items

This test will check:

- The successful integration of the DAQ archiver components with the CCOB
- That the file can then be ingested into the DBB and be retrieved for further analysis

4.203.3 Predecessors

None.

4.203.4 Environment Needs

4.203.4.1 Software

- CCOB device and the software to produce a file to be transferred and kept
- DBB software to produce a retrieval file for further processing

4.203.4.2 Hardware

- CCOB
- Test machine for LSST Monitoring Service
- consolidate DB
- DBB ingest file system
- DBB output file system
- data transfer protocol to move data from CCOB file systems to DBB ingest file system

4.203.5 Input Specification

None.

4.203.6 Output Specification

- CCOB (raw image) files that follow specifications;
- DBB files that follow specifications;
- CCOB device directs a human to where a file is wanted to be stored in the DBB;
- Transfer the file to the DBB ingest area;

4.203.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	CCOB device directs a human to where a raw file is wanted to be stored in the DBB
	Test Data	No data.
	Expected Result	A file with a unique file name is in a file system somewhere, and the data is then transferred to NCSA.
2	Description	Move the data from the transferred directory into the DBB foreign file ingest file system.
	Test Data	No data.
	Expected Result	A command is executed by a human with a file name and path to the file wanted to be stored in the DBB. The file is transferred to NCSA's DBB ingest area.
3	Description	Have data inspected by scientist for managing that all data was transferred.
	Test Data	No data.
	Expected Result	a specific Okay to move forward; or something is broke.
4	Description	The DBB is notified of a new file being in the ingest area, and the DBB ingest is run manually to ingest the CCOB file.
	Test Data	No data.
	Expected Result	The DBB puts the resulting file into the DBB file systems depending on what type of file it is. The DB is updated with metadata and providence of the file to be kept. The resulting file system is queryable by the LSP to find the CCOB raw image.
5	Description	The LSP can review and use the CCOB raw data file that was stored originally somewhere else such as slac
	Test Data	No data.
	Expected Result	LSP has the ability to find the file and view/use it.

4.204 LVV-T285 - RAS-00-10: Raw images in Observatory Operations Data Service

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Michelle Butler

Open LVV-T285 in Jira

Rubin Observatory

4.204.1   Verification Elements

None.

4.204.2   Test Items

This test will check:

- The handoff of a raw image from the Level 1 Archiver to the OODS cache manager is successful;
- A recently taken raw image is accessible to the Observatory Operations staff at the base and summit;

This Test Case shall be repeated for each of the different cameras (ATScam, LSSTCam) and sensors (Science, Wavefront, and Guider) combination.

4.204.3   Predecessors

LVV-T283

4.204.4   Environment Needs

4.204.4.1   Software   The following software must be installed:

- Level 1 Test Stand (include software from LVV-T283 - RAS-00-00)
- OODS cache manager
- LSST Monitoring Service and plugins specific to monitoring raw images and OODS
- LSST stack for checking raw images

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

357

Rubin Observatory

4.204.4.2   Hardware   To complete all tests in a manner which reflects the real system, the following hardware is needed. Note: If not testing inter-machine access, the hardware can be minimized to a single machine outside of the Level 1 Test Stand.

- Level1TestStand(include hardware from LVV-T283 - RAS-00-00)+read/write access to OODS cache disk
- Test Machine for OODS cache manager with read/write access to OODS cache disk
- Test machine for Observatory Operations staff at "base" that can access OODS cache disk
- Test machine for Observatory Operations staff at "summit" that can access OODS cache disk
- Test machine for LSST Monitoring Service

Size of cache disk is determined by number of files to be included in the test.

4.204.5   Input Specification

4.204.6   Output Specification

Raw image(s) that follow format defined in LSE-61;
Database (may be SQLite file) that enables the raw image(s) to be accessed via a "Data Butler".

4.204.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Initialize all services configuring the Level 1 Archiver Service so that the raw images are to be saved to the OODS
	Test Data	No data.
	Expected Result	all camera and services for images are running and reporting green through the monitoring programs for the services.
2	Description	Acquire a raw image
	Test Data	No data.

Rubin Observatory

Step		Description, Input Data and Expected Result
	Expected Result	Image present in the input folder.
3	Description	*The handoff of the raw image from the Level 1 Archiver Service to the test OODS automatically occurs*
	Test Data	No data.
	Expected Result	the raw image with a proper header is written to a file area managed by the OODS
4	Description	For each of the expected raw images, verify that the checksum matches the original Level 1 checksum
	Test Data	No data.
	Expected Result	checksum of the file is checked against the file for verification that the OODS has the correct file and it matches the original md5sum of the FITS file.
5	Description	Check that LSST Monitoring Service showed the appropriate information successfully
	Test Data	No data.
	Expected Result	Make sure all camera and OODS systems were available thorughout this test.

4.205 LVV-T286 - RAS-00-20: Raw image are part of the permanent record of survey via DBB

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Michelle Butler

Open LVV-T286 in Jira

4.205.1 Verification Elements

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-177 - DMS-REQ-0346-V-01: Data Availability

Rubin Observatory

• LVV-115 - DMS-REQ-0284-V-01: Level-1 Production Completeness

4.205.2   Test Items

This test will check:

• That the handoff of a raw image from the Level 1 Archiver Service to the DBB buffer manager is successful;
• That the raw image is ingested into the Data Backbone successfully;
• That the monitoring of the above items is successful;

This Test Case shall be repeated for each of the different cameras (ATScam, LSSTCam) and sensors (Science, Wavefront, and Guider) combination.

Note: For a complete check of the various aspects of what it means for a raw image to be in the Data Backbone, see the tests for the Data Backbone.

4.205.3   Predecessors

LVV-T283

4.205.4   Environment Needs

4.205.4.1   Software

• Level 1 Test Stand
• DBB buffer manager
• DBB raw image ingestion
• DBB database

Rubin Observatory

- LSST Monitoring Service and plugins specific to monitoring raw images, DBB buffer manager, and DBB

4.205.4.2   Hardware

- Level 1 Test Stand (include hardware from LVV-T-283 - RAS-00-00) + read/write access to DBB buffer disk;
- Test Machine for DBB buffer manager with read/write access to DBB buffer disk;
- Test machine for each DBB endpoint with read/write access to DBB disk;
- Test machine for LSST Monitoring Service

Size of buffer disk and DBB disk is determined by number of files to be included in the test.

Note: If not testing inter-machine operability, then the hardware can be minimized to a single machine outside of the Level 1 test stand.

4.205.5   Input Specification

None

4.205.6   Output Specification

- Raw image(s) are saved to storage and replicated to correct locations with checksums that match original Level 1 checksum;
- Database containing information of the following types: physical, location, science metadata, provenance as specified in LSE-61;
- Both image(s) and database entries replicated correctly;

4.205.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Initialize all services configuring the Level 1 Archiver Service so that the raw images are to be archived to the DBB
	Test Data	No data.
	Expected Result	all services for the camera images and the DBB services are all running and ready for data.
2	Description	Acquire a raw image (see LVV-T283 - RAS-00-00)
	Test Data	No data.
	Expected Result	have a raw Fits file with proper header.
3	Description	After the automatic handoff of the raw image between the Level 1 Archiver Service and the DBB buffer manager, the raw image will automatically be ingested into the Data Backbone
	Test Data	No data.
	Expected Result	the DBB file systems will have the file, and metadata and providence will be recorded in the consolidated DB. The file will also be replicated to mulitple locations for DR.
4	Description	Check that the raw image is accessible at each DBB endpoint and matches original Level 1 checksum
	Test Data	No data.
	Expected Result	data resides at NCSA DBB end point, and Chile end point and match with the same checksum.
5	Description	Check that LSST Monitoring Service showed the appropriate information successfully
	Test Data	No data.
	Expected Result	all related systems remained up during this test.
6	Description	More complete tests of the DBB can be done by running the DBB service tests on the raw image(s). These would check correctness and completeness of the data stored in the database as well as checking that the file has been replicated to all required places
	Test Data	No data.
	Expected Result	These would be more tests of when things go wrong to make sure that the DBB is able to continue to work, and not be in the way of taking images from the camera

Rubin Observatory

4.206   LVV-T287 - RAS-00-30: Raw Image Archiving Availability, Throughput, Reliability, and Heterogeneity

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Michelle Butler

Open LVV-T287 in Jira

4.206.1   Verification Elements

- LVV-5 - DMS-REQ-0008-V-01: Pipeline Availability

- LVV-65 - DMS-REQ-0162-V-01: Pipeline Throughput

- LVV-68 - DMS-REQ-0165-V-01: Infrastructure Sizing for "catching up"

- LVV-70 - DMS-REQ-0167-V-01: Incorporate Autonomics

- LVV-145 - DMS-REQ-0314-V-01: Compute Platform Heterogeneity

- LVV-149 - DMS-REQ-0318-V-01: Data Management Unscheduled Downtime

- LVV-140 - DMS-REQ-0309-V-01: Raw Data Archiving Reliability

4.206.2   Test Items

This test will check:

- Raw Image Archiving meets availability requirements;
- Raw Image Archiving meets throughput requirements;
- Raw Image Archiving meets reliability requirements;
- Raw Image Archiving meets heterogeneity requirements;

This test case need to be completed when more information is available.

4.206.3 Predecessors

4.206.4 Environment Needs

4.206.4.1 Software

4.206.4.2 Hardware

4.206.5 Input Specification

4.206.6 Output Specification

4.206.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	these will be filled out as the service becomes more known as to what the availablility, throughput, reliability and heterogeneity are.
	Test Data	No data.
	Expected Result	The archive system will stay up through thick and thin and perform like it's suppose to.

4.207 LVV-T362 - Installation of the LSST Science Pipelines Payloads

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	John Swinbank

Open LVV-T362 in Jira

Rubin Observatory

4.207.1   Verification Elements

- LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images

- LVV-98 - DMS-REQ-0267-V-01: Source Catalog

- LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

- LVV-127 - DMS-REQ-0296-V-01: Pre-cursor, and Real Data

- LVV-15 - DMS-REQ-0033-V-01: Provide Source Detection Software

4.207.2   Test Items

This test will check that:

- The Alert Production Pipeline payload is available for installation from documented channels;
- The Data Release Production Pipeline payload is available for installation from documented channels;
- The Calibration Products Production Pipeline payload is available for installation from documented channels;
- These payloads can be installed on systems at the LSST Data Facility following available documentation;
- The installed pipeline payloads are capable of successfully executing basic integration tests.

Note that this test assumes a 2018-era packaging of the Science Pipelines software, in which all the above payloads are represented by a single "meta-package", lsst_distrib.

4.207.3   Predecessors

4.207.4   Environment Needs

4.207.4.1   Software   Science Pipelines prerequisite software, as documented at https://pipelines.lsst.io/, must be installed on the target system.

Rubin Observatory

4.207.4.2   Hardware   This test requires a workstation or equivalent system running an operating system supported by the LSST Science Pipelines.

4.207.5   Input Specification

4.207.6   Output Specification

4.207.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	The LSST Science Pipelines, described by the lsst_distrib meta-package, should be installed following the documentation available at https://pipelines.lsst.io/. The suggested Conda environment will be used to ensure that a supported execution environment is available.
	Test Data	No data.
	Expected Result	Detailed output will depend on the installation method chosen, but will confirm the successful installation of the Science Pipelines.
2	Description	The lsst_distrib top-level metapackage will be enabled. Assuming that the software has been installed at ${LSST_DIR}: source ${LSST_DIR}/loadLSST.bash setup lsst_distrib
	Test Data	No data.
	Expected Result	Nothing is printed. The command eups list -s lsst_distrib may be used to confirm that the correct version of the codebase has been installed.
3	Description	The "LSST Stack Demo" package will be downloaded onto the test system from https://github.com/lsst/lsst_dm_stack_demo/releases. The version corresponding to to the version of the Science Pipelines under test should be chosen.
	Test Data	No data.
	Expected Result	Depends on the tool selected by the user for downloading.
4	Description	The stack demo package is uncompressed into a directory ${DEMO_DIR}.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Depends on options given to the tar command. Should confirm the availability of the stack demo source.
5	Description	The demo package will be executed by following the instructions in its README file.
	Test Data	No data.
	Expected Result	Successful execution will result in the string "Ok" being returned.

4.208   LVV-T363 - Science Pipelines Release Documentation

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Inspection	John Swinbank

Open LVV-T363 in Jira

4.208.1   Verification Elements

- LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use

- LVV-3402 - DMS-REQ-0360-V-01: Median astrometric error on 20 arcmin scales

4.208.2   Test Items

This test will check:

- That a particular Science Pipelines release is adequately described by documentation at the https://pipelines.lsst.io/ site;
- That the Science Pipelines release is accompanied by a characterization report which describes its scientific performance.

4.208.3   Predecessors

Rubin Observatory

4.208.4 Environment Needs

4.208.4.1 Software   A web browser.

4.208.4.2 Hardware   A device with internet access.

4.208.5 Input Specification

4.208.6 Output Specification

4.208.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Load the Science Pipelines website at https://pipelines.lsst.io/.
	Test Data	No data.
	Expected Result	The website is displayed.
2	Description	Identify documentation for the release under test. This should be clearly labelled on the documentation site.
		If the latest release is being tested, the default page loaded when visiting https://pipelines.lsst.io/ should be the documentation required.
		If this test is for another release, the site should present clear instructions for changing the edition (or version) of the documentation being examined, and documentation for the release under test should be available.
	Test Data	No data.
	Expected Result	The documentation for the release under test is displayed.
3	Description	Inspect the documentation to ensure that it refers to the release under test, and that it provides:

- Release notes, describing changes in this release relative to the previous;
- Installation instructions, together with a list of supported platforms and prerequisites;
- Getting started information.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

368

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	The user is satisfied that the required information is available.
4	Description	Locate the Characterization Metric Report corresponding to this release. It should be linked from the main release documentation.
	Test Data	No data.
	Expected Result	The user is satisfied that the report is available.
5	Description	Verify that the characterization metric report describes the scientific performance of the release in terms of a selection of performance metrics drawn from high-level requirements documentation (the Science Requirements Document, LPM-17; the LSST System Requirements, LSE-29; and/or the Observatory System Specifications, LSE-30).
	Test Data	No data.
	Expected Result	Metric values describing the performance of the release, for example as computed by validate_drp, are described in the report.

4.209   LVV-T368 - Loading and processing Camera test data

Version	Status	Priority	Verification Type	Owner
2	Approved	Normal	Test	John Swinbank

Open LVV-T368 in Jira

4.209.1   Verification Elements

• LVV-129 - DMS-REQ-0298-V-01: Data Product and Raw Data Access

• LVV-63 - DMS-REQ-0160-V-01: Provide User Interface Services

• LVV-23 - DMS-REQ-0060-V-01: Bias Residual Image

4.209.2   Test Items

This test will check:

Rubin Observatory

- That Camera test data is available for processing in the LSST Data Facility, and accessible through the LSST Science Platform;
- That the Data Management I/O abstraction (the "Data Butler") can load that data into the Science Platform environment;
- That Data Management algorithmic "tasks" can be executed to process that data;
- That results can be displayed in the Firefly display tool.

4.209.3   Predecessors

Executing LVV-T374 will satisfy the preconditions for this test, assuming that $REPOSITORY_PATH is set equal to the output location used in LVV-T374.

4.209.4   Environment Needs

4.209.4.1   Software   The LSST Science Pipelines version w_2018_45 must be available within the Notebook Aspect of the LSST Science Platform.

4.209.4.2   Hardware   This test assumes the availability of the Notebook and Portal aspects of the LSST Science Platform, deployed at https://lsst-lspdev.ncsa.illinois.edu.

4.209.5   Input Specification

Appropriate data — to include a "raw" and a "bias" exposure — from the Camera test systems must be available in a Butler data repository on a filesystem accessible to the Notebook Aspect of the Science Platform.

For the purposes of the following discussion, we assume that:

- Visit 258334666 from RTM (Raft Tower Module) 007 will be used;

Rubin Observatory

- The data is available in a repository at /project/bootcamp/repo_RTM-007/ on the Data Facility GPFS filesystem

In the test script, we refer to "258334666" as "$VISIT_ID" and "/project/bootcamp/repo_RTM-007/" as "$REPOSITORY_PATH"; other data may be substituted as appropriate.

4.209.6   Output Specification

4.209.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Connect to the Notebook Aspect of the Science Platform following the instructions at https://nb.lsst.io/. Log in, and "spawn" a new machine with image "Weekly 2018_45" and size "small".
	Test Data	No data.
	Expected Result	The JupyterLab environment appears.
2	Description	Create a terminal session. Use it to set up the LSST tools, then download and build version 5c12b06e6 of obs_lsst:

```
$ source /opt/lsst/software/stack/loadLSST.bash
$ setup lsst_distrib
$ git clone https://github.com/lsst/obs_lsst.git
$ cd obs_lsst
$ git checkout 5c12b06e6
$ setup -k -r .
$ scons
```

Arrange for obs_lsst to automatically be added to the environment when starting a new notebook:

```
$ echo "setup -j -r ~/obs_lsst" >> ~/notebooks/.user_setups
```

Exit the terminal.

Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	No errors are seen during execution of the provided commands.
3	Description	Create a new "LSST" notebook.
		Import the standard libraries required for the rest of this test:

		`import os`
		`import lsst.afw.display as afwDisplay`
		`from lsst.daf.persistence import Butler`
		`from lsst.ip.isr import IsrTask`
		`from firefly_client import FireflyClient`
		`from IPython.display import IFrame`

		and execute the cell.
	Test Data	No data.
	Expected Result	Nothing is printed.
4	Description	Create a Data Butler client, and use it to retrieve the data which will be used for this test.

		`butler = Butler($REPOSITORY_PATH)`
		`raw = butler.get("raw", visit=$VISIT_ID, detector=2)`
		`bias = butler.get("bias", visit=$VISIT_ID, detector=2)`

	Test Data	No data.
	Expected Result	Nothing is printed.

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board.** – **DRAFT NOT YET APPROVED**

372

Rubin Observatory

Step	Description, Input Data and Expected Result	
5	Description	Initialize the Firefly display system: my_channel = '{}_test_channel'.format(os.environ['USER']) server = 'https://lsst-lspdev.ncsa.illinois.edu' ff='{}/firefly/slate.html?__wsch={}'.format(server, my_channel) IFrame(ff,800,600) afwDisplay.setDefaultBackend('firefly') afw_display = afwDisplay.getDisplay(frame=1, name=my_channel) Click on the link provided after executing the above.
	Test Data	No data.
	Expected Result	A Firefly window is shown.
6	Description	Display the raw image data in the Firefly window: afw_display.mtv(raw)
	Test Data	No data.
	Expected Result	Raw image data is displayed.
7	Description	Configure and run an Instrument Signature Removal (ISR) task on the raw data. Most corrections are disabled for simplicity. but the bias frame is applied.

```
isr_config = IsrTask.ConfigClass()
isr_config.doDark=False
isr_config.doFlat=False
isr_config.doFringe=False
isr_config.doDefect=False
isr_config.doAddDistortionModel=False
isr_config.doLinearize=False
isr = IsrTask(config=isr_config)
result = isr.run(raw, bias=bias)
```

	Test Data	No data.

Step	Description, Input Data and Expected Result	
	Expected Result	Nothing is printed.
8	Description	Display the corrected image data in the Firefly window:
		afw_display.mtv(result.exposure)
	Test Data	No data.
	Expected Result	Processed (trimmed, bias-subtracted) image data is displayed.

4.210 LVV-T374 - Ingesting Camera test data

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	John Swinbank

Open LVV-T374 in Jira

4.210.1 Verification Elements

- LVV-130 - DMS-REQ-0299-V-01: Data Product Ingest
- LVV-129 - DMS-REQ-0298-V-01: Data Product and Raw Data Access

4.210.2 Test Items

This test will check:

- That raw Camera test data is available on a filesystem in the LSST Data Facility;
- That raw Camera test data can be ingested and made available through the Data Management I/O abstraction (the "Data Butler").

4.210.3 Predecessors

Rubin Observatory

4.210.4   Environment Needs

4.210.4.1   Software   The LSST Science Pipelines version w_2018_45 must be available within the Notebook Aspect of the LSST Science Platform.

4.210.4.2   Hardware   This test assumes the availability of the Notebook aspect of the LSST Science Platform, deployed at https://lsst-lspdev.ncsa.illinois.edu.

4.210.5   Input Specification

Appropriate raw data from Camera test systems must be available on a filesystem within the LSST Data Facility. This test data is assumed to include visit 258334666 (hereafter referred to as $VISIT_ID) from RTM (Raft Tower Module) 007 for the purposes of this test, but other, equivalent, may be substituted.

At time of writing, suitable data may be found on the GPFS filesystem at /project/bootcamp/data/LCA-11021_RTM-007/7086/fe55_raft_acq/v0/44981. In future, as data transport procedures to the Data Facility become more streamlined and formalised, this data may be moved elsewhere or made available through some other system. Throughout the test script, we use the string "$IN-PUT_DATA_DIR" as an alias for "/project/bootcamp/data/LCA-11021_RTM-007/7086/fe55_raft_acq/v0/44981" or wherever this data has been moved to.

4.210.6   Output Specification

4.210.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Connect to the Notebook Aspect of the Science Platform following the instructions at https://nb.lsst.io/. Log in, and "spawn" a new machine with image "Weekly 2018_45" and size "large".
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	The JupyterLab environment appears.
2	Description	Create a terminal session. Use it to set up the LSST tools, then download and build version 5c12b06e6 of obs_lsst:

```
$ source /opt/lsst/software/stack/loadLSST.bash
$ setup lsst_distrib
$ git clone https://github.com/lsst/obs_lsst.git
$ cd obs_lsst
$ git checkout 5c12b06e6
$ setup -k -r .
$ scons
```

	Test Data	No data.
	Expected Result	No errors are seen during execution of the provided commands.
3	Description	Ingest RTM-007 test data by executing the following commands:

```
OUTPUT_REPO_DIR=$OUTPUT_DATA_DIR
INPUT_DATA_DIR=$INPUT_DATA_DIR
mkdir -p $OUTPUT_REPO_DIR
echo "lsst.obs.lsst.ts8.Ts8Mapper" > $OUTPUT_REPO_DIR/_mapper
ingestImages.py $OUTPUT_REPO_DIR $INPUT_DATA_DIR/*/*.fits
 constructBias.py $OUTPUT_REPO_DIR –rerun calibs –id imageType=BIAS –batch-type
smp –cores 4
          ingestCalibs.py    $OUTPUT_REPO_DIR    –calibType    bias    $OUT-
PUT_REPO_DIR/rerun/calibs/bias/*/*.fits    –validity    9999    –output    $OUT-
PUT_REPO_DIR/CALIB –mode=link
```

Where:

$OUTPUT_DATA_DIR is some location on shared storage to which the user has write permission;
$INPUT_DATA_DIR is defined in the test case description.

	Test Data	No data.
	Expected Result	Many status messages are logged to screen, and the command exits with status 0.

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Demonstrate that raw and bias data for visit $VISIT_ID have been made available in the repository. Load a Python interpreter (run "python") and execute the following: from lsst.daf.persistence import Butler visit_id = $VISIT_ID b = Butler($OUTPUT_DATA_DIR) b.get("raw", visit=visit_id, detector=2) b.get("bias", visit=visit_id, detector=2)
	Test Data	No data.
	Expected Result	Each call to b.get() returns an instance of an ExposureF object. Warnings about lack of dark-time or WCS information may be ignored.

4.211 LVV-T376 - Verify the Calculation of Ellipticity Residuals and Correlations

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Leanne Guy

Open LVV-T376 in Jira

4.211.1 Verification Elements

- LVV-3404 - DMS-REQ-0362-V-01: Median residual PSF ellipticity correlations on 5 arcmin scales

- LVV-9780 - DMS-REQ-0362-V-02: Max fraction of excess ellipticity residuals on 1 and 5 arcmin scales

4.211.2 Test Items

Verify that the DMS includes software to enable the calculation of the ellipticity residuals and correlation metrics defined in the OSS.

4.211.3 Predecessors

4.211.4 Environment Needs

4.211.4.1 Software

4.211.4.2 Hardware

4.211.5 Input Specification

4.211.6 Output Specification

4.211.7 Test Procedure

Step		Description, Input Data and Expected Result
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Point the butler to an appropriate (precursor or simulated) dataset containing data in all filters, that is sufficient for the purposes of measuring astrometric performance metrics.
	Test Data	No data.
	Expected Result	
3	Description	Execute the LSST Stack package 'validate_drp' (or an alternate package that is relevant) on this dataset to perform the measurements of the metrics.
	Test Data	No data.
	Expected Result	Measurements of validation metrics and the presence of QA plots resulting from the validation pipeline.
4	Description	Compare measured ellipticity correlations to known (for simulated data) or measured (if using precursor data) values from input (precursor or simulated) data, and confirm that the output values for all of the ellipticity performance metrics are as expected.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Measured ellipticity metrics that are within reasonable values given the (known) input dataset.

4.212   LVV-T377 - Verify Calculation of Photometric Performance Metrics

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Leanne Guy

Open LVV-T377 in Jira

4.212.1   Verification Elements

- LVV-9751 - DMS-REQ-0359-V-02: Max fraction of sensors with excess unusable pixels

- LVV-9757 - DMS-REQ-0359-V-08: Max cross-talk imperfections

- LVV-9755 - DMS-REQ-0359-V-06: Accuracy of photometric transformation

- LVV-9756 - DMS-REQ-0359-V-07: RMS width of zero point in u-band

- LVV-9753 - DMS-REQ-0359-V-04: Accuracy of zero point for colors with u-band

- LVV-9762 - DMS-REQ-0359-V-13: Max sky brightness error

- LVV-9760 - DMS-REQ-0359-V-11: Fraction of zero point outliers

- LVV-9761 - DMS-REQ-0359-V-12: Max fraction of unusable pixels per sensor

- LVV-9764 - DMS-REQ-0359-V-15: Percentage of image area with ghosts

- LVV-9766 - DMS-REQ-0359-V-17: Max RMS of resolved/unresolved flux ratio

- LVV-9763 - DMS-REQ-0359-V-14: RMS width of zero point in all bands except u

- LVV-9765 - DMS-REQ-0359-V-16: Accuracy of zero point for colors without u-band

Rubin Observatory

4.212.2   Test Items

Verify that the DMS system provides software to calculate photometric performance metrics, and that the algorithms are properly calculating the desired quantities. Note that because the DMS requirement is that the software shall be provided (and not on the actual measured values of the metrics), we verify all of the requirements via a single test case.

4.212.3   Predecessors

4.212.4   Environment Needs

4.212.4.1   Software

4.212.4.2   Hardware

4.212.5   Input Specification

4.212.6   Output Specification

4.212.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Point the butler to a simulated dataset containing data in all filters, that is sufficient for the purposes of measuring photometric performance metrics.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Execute the LSST Stack package 'validate_drp' (or an alternate package that is relevant) on this dataset to perform the measurements of the metrics.
	Test Data	No data.
	Expected Result	Measurements of validation metrics and the presence of QA plots resulting from the validation pipeline.
4	Description	Compare measured photometry to known values from input simulated data, and confirm that the output values for all of the photometric performance metrics are as expected.
	Test Data	No data.
	Expected Result	Measured astrometry metrics that are within reasonable values given the (known) input dataset.

4.213   LVV-T378 - Verify Calculation of Astrometric Performance Metrics

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Leanne Guy

Open LVV-T378 in Jira

4.213.1   Verification Elements

- LVV-9778 - DMS-REQ-0360-V-12: RMS difference between r-band and other filter separation

- LVV-9777 - DMS-REQ-0360-V-11: Max fraction of r-band color difference outliers

- LVV-9779 - DMS-REQ-0360-V-13: Max fraction exceeding limit on 200 arcmin scales

- LVV-9773 - DMS-REQ-0360-V-07: Outlier limit on 5 arcmin scales

- LVV-9770 - DMS-REQ-0360-V-05: Outlier limit on 20 arcmin scales

- LVV-9775 - DMS-REQ-0360-V-09: Outlier limit on 200 arcmin scales

- LVV-9769 - DMS-REQ-0360-V-04: Median absolute error in RA, Dec

- LVV-9774 - DMS-REQ-0360-V-08: Median astrometric error on 200 arcmin scales

Rubin Observatory

- LVV-9768 - DMS-REQ-0360-V-03: Median astrometric error on 5 arcmin scales

- LVV-9771 - DMS-REQ-0360-V-06: Color difference outlier limit relative to r-band

- LVV-9776 - DMS-REQ-0360-V-10: Max fraction exceeding limit on 20 arcmin scales

- LVV-9767 - DMS-REQ-0360-V-02: Max fraction exceeding limit on 5 arcmin scales

4.213.2   Test Items

Verify that the DMS system provides software to calculate astrometric performance metrics, and that the algorithms are properly calculating the desired quantities. Note that because the DMS requirement is that the software shall be provided (and not on the actual measured values of the metrics), we verify all of the requirements via a single test case.

4.213.3   Predecessors

4.213.4   Environment Needs

4.213.4.1   Software

4.213.4.2   Hardware

4.213.5   Input Specification

4.213.6   Output Specification

4.213.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

Rubin Observatory

Step		Description, Input Data and Expected Result
2	Description	Point the butler to an appropriate (precursor or simulated) dataset containing data in all filters, that is sufficient for the purposes of measuring astrometric performance metrics.
	Test Data	No data.
	Expected Result	
3	Description	Execute the LSST Stack package 'validate_drp' (or an alternate package that is relevant) on this dataset to perform the measurements of the metrics.
	Test Data	No data.
	Expected Result	Measurements of validation metrics and the presence of QA plots resulting from the validation pipeline.
4	Description	Compare measured astrometry to known (for simulated data) or measured (if using precursor data) values from input (precursor or simulated) data, and confirm that the output values for all of the astrometric performance metrics are as expected.
	Test Data	No data.
	Expected Result	Measured astrometry metrics that are within reasonable values given the (known) input dataset.

4.214 LVV-T385 - Verify implementation of minimum number of simultaneous retrievals of CCD-sized coadd cutouts

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Leanne Guy

Open LVV-T385 in Jira

4.214.1 Verification Elements

- LVV-3394 - DMS-REQ-0377-V-01: Min number of simultaneous single-CCD coadd cutout image users

4.214.2 Test Items

Verify that at least **ccdRetrievalUsers = 20** users can simultaneously retrieve a single CCD-sized coadd cutout using the IVOA SODA protocol.

4.214.3 Predecessors

4.214.4 Environment Needs

4.214.4.1 Software

4.214.4.2 Hardware

4.214.5 Input Specification

4.214.6 Output Specification

4.214.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Confirm that CCD-sized cutouts from coadds, also containing mask and variance planes, are available on the SODA server. If none are available, copy an image (or some images) to the server.
	Test Data	No data.
	Expected Result	At least one CCD-sized coadd cutout is available, and is a well-formed image.
2	Description	Simulate SODA queries by at least **ccdRetrievalUsers = 20** users at the same time.
	Test Data	No data.
	Expected Result	
3	Description	Confirm that all simulated users retrieved the desired image(s), and that the returned images are well-formed, with (at least) image, mask, and variance planes.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	All of the simulated **ccdRetrievalUsers = 20** users retrieved images within the specified time (see related Verification Element and Test Case).

4.215   LVV-T454 - LDM-503-8 Enable LSP viewing of spectrograph data.

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Michelle Gower

Open LVV-T454 in Jira

4.215.1   Verification Elements

- LVV-140 - DMS-REQ-0309-V-01: Raw Data Archiving Reliability

4.215.2   Test Items

- Acquire spectrograph image data, transfer that data to NCSA, ingest data into a Butler (G2 or G3 when available), and enable viewing of data on LSP.

4.215.3   Predecessors

LDM-503-4b

4.215.4   Environment Needs

4.215.4.1   Software

4.215.4.2   Hardware   ATS storage server system housed with spectrograph.   Receiver system at NCSA for data.

Rubin Observatory

4.215.5   Input Specification

Data must be well formed on Spectrograph data archiving system (ATS). Well-formed means "good image" and correct headers. (LSE-400)

4.215.6   Output Specification

4.215.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Have data on the ATS archiver system from the spectrograph.
	Test Data	No data.
	Expected Result	Well formed files on the ATS system that need to be transferred to NCSA for further analysis
2	Description	A first few iterations is the human runs script to transfer data to NCSA through secure pipeline. after the process is unchanging/solid, a cronjob starts up data "sync" process.
	Test Data	No data.
	Expected Result	Data is transferred to NCSA, and is located in NCSA file systems.
3	Description	All files transferred have a ButlerG2 (or G3 when ready) ingest process.
	Test Data	No data.
	Expected Result	files now can be accessed by Butler access methods
4	Description	LSP processes can now view spectrograph generate files
	Test Data	No data.
	Expected Result	LSP jupyter notebooks can view spectrograph files.

4.216   LVV-T1085 - Short Queries Functional Test

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1085 in Jira

4.216.1 Verification Elements

- LVV-33 - DMS-REQ-0075-V-01: Catalog Queries

- LVV-9787 - DMS-REQ-0356-V-04: Max time to retrieve low-volume query results

4.216.2 Test Items

The objective of this test is to ensure that the short queries are performing as expected and establish a timing baseline benchmark for these types of queries.

4.216.3 Predecessors

4.216.4 Environment Needs

4.216.4.1 Software

4.216.4.2 Hardware

4.216.5 Input Specification

QSERV has been set-up following procedure at LVV-T1017.

4.216.6 Output Specification

4.216.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Execute single object selection: **SELECT** * **FROM** Object **WHERE** deepSourceId = 9292041530376264 and record execution time.
	Test Data	No data.
	Expected Result	Query runs in less than 10 seconds.
2	Description	Execute spatial area selection from Object: **SELECT COUNT(*) FROM** Object **WHERE** qserv_areaspec_box(316.582327, −6.839078, 316.653938, −6.781822) and record execution time.
	Test Data	No data.
	Expected Result	Query runs in less than 10 seconds.

4.217   LVV-T1086 - Full Table Scans Functional Test

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1086 in Jira

4.217.1   Verification Elements

• LVV-33 - DMS-REQ-0075-V-01: Catalog Queries

• LVV-188 - DMS-REQ-0357-V-01: Result latency for high-volume full-sky queries on the Object table

• LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries

Rubin Observatory

4.217.2   Test Items

The objective of this test is to ensure that the full table scan queries are performing as expected and establish a timing baseline benchmark for these types of queries.

4.217.3   Predecessors

4.217.4   Environment Needs

4.217.4.1   Software

4.217.4.2   Hardware

4.217.5   Input Specification

QSERV has been set-up following procedure at LVV-T1017.

4.217.6   Output Specification

4.217.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute query: **SELECT** ra , decl , u_psfFlux , g_psfFlux , r_psfFlux **FROM** Object **WHERE** y_shapeIxx **BETWEEN** 20 **AND** 20.1 and record execution time and output size.
	Test Data	No data.
	Expected Result	Query expected to run in less than 1 hour.

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Execute query: **SELECT** COUNT(*) **FROM** Source **WHERE** flux_sinc **BETWEEN** 1 **AND** 1.1 and record the execution time
	Test Data	No data.
	Expected Result	Query expected to run in less than 12 hours.
3	Description	Execute query: **SELECT** COUNT(*) **FROM** ForcedSource **WHERE** psfFlux **BETWEEN** 0.1 **AND** 0.2 and record the execution time
	Test Data	No data.
	Expected Result	Query expected to run in less than 12 hours.

4.218   LVV-T1087 - Full Table Joins Functional Test

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1087 in Jira

4.218.1   Verification Elements

• LVV-33 - DMS-REQ-0075-V-01: Catalog Queries

• LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries

Rubin Observatory

4.218.2   Test Items

The objective of this test is to ensure that the full table join queries are performing as expected and establish a timing baseline benchmark for these types of queries.

4.218.3   Predecessors

4.218.4   Environment Needs

4.218.4.1   Software

4.218.4.2   Hardware

4.218.5   Input Specification

QSERV has been set-up following procedure at LVV-T1017.

4.218.6   Output Specification

4.218.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute query: **SELECT** o.deepSourceId, s.objectId, s.id, o.ra, o.decl **FROM** Object o, Source s WHERE o.deepSourceId=s.objectId **AND** s . flux_sinc **BETWEEN** 0.3 **AND** 0.31 and record execution time.
	Test Data	No data.
	Expected Result	Query expected to run in less than 12 hours.

Rubin Observatory

Step	Description, Input Data and Expected Result	
2	Description	Execute query: **SELECT** o.deepSourceId, f.psfFlux **FROM** Object o, ForcedSource f **WHERE** o.deepSourceId=f.deepSourceId **AND** f . psfFlux **BETWEEN** 0.13 **AND** 0.14 and record execution time.
	Test Data	No data.
	Expected Result	Query expected to run in less than 12 hours.

4.219   LVV-T1088 - Concurrent Scans Scaling Test

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1088 in Jira

4.219.1   Verification Elements

- LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries

- LVV-188 - DMS-REQ-0357-V-01: Result latency for high-volume full-sky queries on the Object table

- LVV-3403 - DMS-REQ-0361-V-01: Simultaneous users for high-volume queries

4.219.2   Test Items

This test will show that average completion-time of full-scan queries of the Object catalog table grows sub-linearly with respect to the number of simultaneously active full-scan queries, within the limits of machine resource exhaustion.

Rubin Observatory

4.219.3   Predecessors

4.219.4   Environment Needs

4.219.4.1   Software

4.219.4.2   Hardware

4.219.5   Input Specification

1. A test catalog of appropriate size (see schedule detail in LDM-552, section 2.2.1), pre-
   pared and ingested into the Qserv instance under test as detailed in LVV-T1017.
2. The concurrency load execution script, runQueries.py, maintained in the LSST Qserv
   github repository here: https://github.com/lsst/qserv/blob/master/admin/tools/docker/deployment/ir

4.219.6   Output Specification

4.219.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Repeat steps 2 through 5 below, where "pool of interest" is taken first to be "FTSObj" and subsequently "FTSSrc":
	Test Data	No data.
	Expected Result	At end of each pass, a graph indicating scan scaling rate and machine resource exhaustion cutoff.
2	Description	Inspect and modify the CONCURRENCY and TARGET_RATES dictionaries in the run-Queries.py script. Set CONCURRENCY initially to 1 for the query pool of interest, and to 0 for all other query pools. Set TARGET_RATES for the query pool of interest to the yearly value per table in LDM-552, section 2.2.1.
	Test Data	No data.
	Expected Result	rueQueries.py script updated with appropriate values for test iteration
3	Description	Execute the runQueries.py script and let it run for at least one, but preferably several, query cycles.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Test script executes producing log file.
4	Description	Examine log file output and compile performance statistics to obtain a growth curve point for the pool of interest for the test report.
	Test Data	No data.
	Expected Result	Logs indicate either successful test run, providing another growth point for curve, or errors indicating machine resource exhaustion cutoff has been reached.
5	Description	Adjust the CONCURRENCY value for the pool of interest and repeat from step 3 to establish the growth trend and machine resource exhaustion cutoff for the query pool of interest to an acceptable degree of accuracy.
	Test Data	No data.
	Expected Result	Average query execution time for full scan queries of each class should be demonstrated to grow sub-linearly in the number of concurrent queries to the limits of machine resource exhaustion.

4.220   LVV-T1089 - Load Test

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1089 in Jira

4.220.1   Verification Elements

- LVV-9786 - DMS-REQ-0356-V-03: Min number of simultaneous low-volume query users

- LVV-9787 - DMS-REQ-0356-V-04: Max time to retrieve low-volume query results

- LVV-188 - DMS-REQ-0357-V-01: Result latency for high-volume full-sky queries on the Object table

- LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries

- LVV-3403 - DMS-REQ-0361-V-01: Simultaneous users for high-volume queries

Rubin Observatory

4.220.2   Test Items

This test will check that Qserv is able to meet average query completion time targets per query class under a representative load of simultaneous high and low volume queries while running against an appropriately scaled test catalog.

4.220.3   Predecessors

4.220.4   Environment Needs

4.220.4.1   Software

4.220.4.2   Hardware

4.220.5   Input Specification

QSERV has been set-up following procedure at LVV-T1017

4.220.6   Output Specification

4.220.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inspect and modify the CONCURRENCY and TARGET_RATES dictionaries in the run-Queries.py script. Set CONCURRENCY and TARGET_RATES for all pools to the yearly value per table in LDM-552, section 2.2.1.
	Test Data	No data.
	Expected Result	Script updated with appropriate values.
2	Description	Execute the runQueries.py script and let it run for 24 hours.
	Test Data	No data.
	Expected Result	Script runs without error and produces output log.

Step	Description, Input Data and Expected Result	
3	Description	Examine log file output and compile average query execution times per query type; and compare to yearly target values per table in LDM-552, section 2.2.1.
	Test Data	No data.
	Expected Result	Average query times per query type equal or less than corresponding yearly target values in LDM-552, section 2.2.1.

4.221 LVV-T1090 - Heavy Load Test

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Fritz Mueller

Open LVV-T1090 in Jira

4.221.1 Verification Elements

- LVV-9786 - DMS-REQ-0356-V-03: Min number of simultaneous low-volume query users

- LVV-9787 - DMS-REQ-0356-V-04: Max time to retrieve low-volume query results

- LVV-188 - DMS-REQ-0357-V-01: Result latency for high-volume full-sky queries on the Object table

- LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries

- LVV-3403 - DMS-REQ-0361-V-01: Simultaneous users for high-volume queries

4.221.2 Test Items

This test will check that Qserv is able to meet average query completion time targets per query class under a higher than average load of simultaneous high and low volume queries while running against an appropriately scaled test catalog.

4.221.3 Predecessors

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

396

Rubin Observatory

4.221.4   Environment Needs

4.221.4.1   Software

4.221.4.2   Hardware

4.221.5   Input Specification

QSERV has been set-up following procedure at LVV-T1017

4.221.6   Output Specification

4.221.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Inspect and modify the CONCURRENCY and TARGET_RATES dictionaries in the run-Queries.py script. Set CONCURRENCY and TARGET_RATES for LV query pool to 2020 value per table in LDM-552, section 2.2.1. Set CONCURRENCY and TARGET_RATES for all other query pools to values in next column over from current year column (or to 2020 values +10% if year is 2020) per table in LDM-552, section 2.2.1.
	Test Data	No data.
	Expected Result	Script updated with appropriate values.
2	Description	Execute the runQueries.py script and let it run for 24 hrs.
	Test Data	No data.
	Expected Result	Script runs without error and produces output log.
3	Description	Examine log file output and compile average query execution times per query type.
	Test Data	No data.
	Expected Result	Average query times per query type equal or less than corresponding yearly target values in LDM-552, section 2.2.1.

4.222   LVV-T1097 - Verify Summit Facility Network Implementation

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeff Kantor

Open LVV-T1097 in Jira

4.222.1   Verification Elements

- LVV-71 - DMS-REQ-0168-V-01: Summit Facility Data Communications

4.222.2   Test Items

Verify that data acquired by a AuxTel DAQ can be transferred to Summit DWDM and loaded in the EFD without problems.

4.222.3   Predecessors

PMCS DMTC-7400-2400 Complete
PMCS T&SC-2600-1545 Complete

4.222.4   Environment Needs

4.222.4.1   **Software**   See pre-conditions

4.222.4.2   **Hardware**   See pre-conditions.

4.222.5   Input Specification

1. Summit Control Network and Camera Data Backbone installed and operating properly.
2. Summit - Base Network installed and operating properly.

Rubin Observatory

3. EITHER: AuxTel hardware and control systems are functional with LATISS. AuxTel TCS, AuxTel EFD, AuxTel CCS, AuxTel DAQ are connected via Control Network on Summit to Rubin Observatory DWDM (with at least 2 x 10 Gbps ethernet port client cards) OR: high-quality DAQ application-level simulators that match the form, volume, file paths, compressibility, and cadence of the expected instrument data, running on end node computers that are the production hardware or equivalent to it. Scientific validity of the data content is not essential.

4. AuxTel Archiver/forwarders installed in Summit and operating properly running on end node computers that are the production hardware or equivalent to it.

5. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume. After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.222.6   Output Specification

4.222.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Verify the pre-conditions have been satisfied
	Test Data	NA
	Expected Result	Pre-conditions are satisfied.
2	Description	Control the AuxTel through a night of Observing. While observing, read out LATISS data and transfer to Rubin Observatory Summit DWDM while monitoring latency.
	Test Data	LATISS images and metadata
	Expected Result	Data is fed to DWDM without delays or errors.
3	Description	Verify that data acquired by a AuxTel DAQ can be transferred and loaded in EFD without problems.
	Test Data	LATISS images and metadata

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Examine the EFD to ensure that the data has been loaded properly.

4.223 LVV-T1168 - Verify Summit - Base Network Integration

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Inspection	Jeff Kantor

Open LVV-T1168 in Jira

4.223.1 Verification Elements

- LVV-73 - DMS-REQ-0171-V-01: Summit to Base Network

4.223.2 Test Items

Verify the integration of the summit to base network by demonstrating a sustained and uninterrupted transfer of data between summit and base over 1 day period at or exceeding rates specified in LDM-142. Done in 3 phases in collaboration with equipment/installation vendors (see test procedure).

4.223.3 Predecessors

See pre-conditions by phase above.

4.223.4 Environment Needs

4.223.4.1 Software   perfsonar on DTN.

4.223.4.2 Hardware   OTDR, DTN.

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

400

4.223.5   Input Specification

PMCS DMTC-7400-2330 COMPLETE

By phase:

1. Posts from Cerro Pachon to AURA Gatehouse repaired/improved.   Fiber installed on posts from Cerro Pachon to AURA Gatehouse. Fiber installed from AURA Gatehouse to AURA compound in La Serena. OTDR purchased.
2. AURA DWDM installed in caseta on Cerro Pachon and in existing computer room in La Serena. DTN installed in La Serena. DTN loaded with software and test data staged.
3. Base Data Center (BDC) ready for installation of LSST DWDM. Fiber connecting existing computer room to BDC. LSST DWDM equipment installed in Summit Computer Room and BDC.

4.223.6   Output Specification

Fiber tested to within acceptable Db. Bandwidth, latency within specifications.

4.223.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Test optical fiber with OTDR: Installation of fiber optic cables and Optical Time Domain Reflector (OTDR) fiber testing (completed 20170602 REUNA deliverable RD10)
	Test Data	OTDR generated optical data
	Expected Result	Fiber tested to within acceptable Db.
2	Description	Test AURA DWDM: Installation of AURA DWDM and Data Transfer Node (DTN) (completed 20171218 DMTR-82)
	Test Data	DTN perfSonar generated data
	Expected Result	Summit - Base bandwidth and latency within specifications
3	Description	Test LSST DWDM: Installation of LSST DWDM and Bit Error Rate Tester (BERT) data (completed 20190505 collection-7743, 20191108 DAQ DWDM Connection Tests)

Step	Description, Input Data and Expected Result	
	Test Data	BERT generated data
	Expected Result	Summit - Base bandwidth, latency, bit error rate within specifications

4.224 LVV-T1232 - Verify Implementation of Catalog Export Formats From the Portal Aspect

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Colin Slater

Open LVV-T1232 in Jira

4.224.1 Verification Elements

- LVV-35 - DMS-REQ-0078-V-01: Catalog Export Formats

4.224.2 Test Items

Verify that catalog data is exportable from the portal aspect in a variety of community-standard formats.

4.224.3 Predecessors

4.224.4 Environment Needs

4.224.4.1 Software

4.224.4.2 Hardware

4.224.5 Input Specification

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the
Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

402

4.224.6 Output Specification

4.224.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T849	Description	Navigate to the Portal Aspect endpoint. The stable version should be used for this test and is currently located at: https://lsst-lsp-stable.ncsa.illinois.edu/portal/app/ .
	Test Data	
	Expected Result	A credential-entry screen should be displayed.
1-2 from LVV-T849	Description	Enter a valid set of credentials for an LSST user with LSP access on the instance under test.
	Test Data	
	Expected Result	The Portal Aspect UI should be displayed following authentication.
2	Description	Select query type "ADQL".
	Test Data	No data.
	Expected Result	
3	Description	Execute the example query given in the example code below by entering the text in the ADQL Query box, then clicking "Search" at the lower left corner of the page.
	Test Data	No data.
	Example Code	SELECT cntr, ra, decl, w1mpro_ep, w2mpro_ep, w3mpro_ep FROM wise_00.allwise_p3as_mep WHERE CONTAINS(POINT('ICRS', ra, decl), CIRCLE('ICRS', 192.85, 27.13, .2)) = 1
	Expected Result	A new page will load with the search results as a table, with some plots as well.
4	Description	Click the icon that looks like a floppy disk (it says "Save the content as an IPAC, CSV, or TSV table" when you mouse over it).
	Test Data	No data.
	Expected Result	
5	Description	• Select "CSV", then specify a destination to save the file on your local computer. • Select "VOTable", then specify a destination to save the file on your local computer. • Select "FITS", then specify a destination to save the file on your local computer.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	
6	Description	Open each of the files (either in TOPCAT, or using Astropy io tools). Confirm that the data tables are well-formed, and that each table contains the same columns and the same number of rows.
	Test Data	No data.
	Expected Result	
7-1 from LVV-T850	Description	Currently, there is no logout mechanism on the portal. This should be updated as the system matures. Simply close the browser window.
	Test Data	
	Expected Result	Closed browser window. When navigating to the portal endpoint, expect to execute the steps in LVV-T849.

4.225 LVV-T1240 - Verify implementation of minimum astrometric standards per CCD

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jim Bosch

Open LVV-T1240 in Jira

4.225.1 Verification Elements

• LVV-9741 - DMS-REQ-0030-V-02: Minimum astrometric standards per CCD

Rubin Observatory

4.225.2 Test Items

Verify that each CCD in a processed dataset had its astrometric solution determined by at least **astrometricMinStandards = 5** astrometric standards.

4.225.3 Predecessors

4.225.4 Environment Needs

4.225.4.1 Software

4.225.4.2 Hardware

4.225.5 Input Specification

4.225.6 Output Specification

4.225.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify an appropriate processed dataset for this test.
	Test Data	No data.
	Expected Result	A dataset with Processed Visit Images.
2-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
3	Description	Select a single visit from the dataset, and extract its calibration data. For a subset of CCDs, check how many astrometric standards contributed to the solution. Confirm that this number is at least **astrometricMinStandards = 5.**
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
Expected Result	At least **astrometricMinStandards** from each CCD were used in determining the WCS solution.	

4.226   LVV-T1250 - Verify implementation of minimum number of simultaneous DM EFD query users

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1250 in Jira

4.226.1   Verification Elements

- LVV-3400 - DMS-REQ-0358-V-01: Min number of simultaneous DM EFD query users

4.226.2   Test Items

Verify that the DM EFD can support **dmEfdQueryUsers = 5** simultaneous queries. The additional requirement that each query must last no more than **dmEfdQueryTime = 10 seconds** will be verified separately in LVV-T1251, but these must be satisfied together.

4.226.3   Predecessors

4.226.4   Environment Needs

4.226.4.1   Software

4.226.4.2   Hardware

4.226.5   Input Specification

4.226.6 Output Specification

4.226.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Send multiple (at least 5) simultaneous queries to the DM EFD.
	Test Data	No data.
	Expected Result	
2	Description	Confirm that (a) the queries executed successfully, and that (b) they return reasonable results.
	Test Data	No data.
	Expected Result	
3	Description	Repeat the above steps for different queries, and different numbers of simultaneous queries, to confirm that the expected performance is met regardless of the query being executed.
	Test Data	No data.
	Expected Result	

4.227 LVV-T1251 - Verify implementation of maximum time to retrieve DM EFD query results

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1251 in Jira

4.227.1 Verification Elements

- LVV-9788 - DMS-REQ-0358-V-02: Max time to retrieve DM EFD query results

Rubin Observatory

4.227.2   Test Items

Verify that the DM EFD can support **dmEfdQueryUsers = 5** simultaneous queries, with each query must executing in no more than **dmEfdQueryTime = 10 seconds.** The requirement on at least 5 simultaneous queries will be verified separately in LVV-T1250, but these must be satisfied together.

4.227.3   Predecessors

4.227.4   Environment Needs

4.227.4.1   Software

4.227.4.2   Hardware

4.227.5   Input Specification

4.227.6   Output Specification

4.227.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Send multiple (at least 5) simultaneous queries to the DM EFD.
	Test Data	No data.
	Expected Result	
2	Description	Confirm that (a) the queries executed successfully, and that (b) they return reasonable results. Check that the time of execution for all queries was less than 10 seconds.
	Test Data	No data.
	Expected Result	
3	Description	Repeat the above steps for different queries, and different numbers of simultaneous queries, to confirm that the expected performance is met regardless of the query being executed.

Rubin Observatory

Step	Description, Input Data and Expected Result
	Test Data No data.
	Expected
	Result

4.228   LVV-T1252 - Verify number of simultaneous alert filter users

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Eric Bellm

Open LVV-T1252 in Jira

4.228.1   Verification Elements

- LVV-9748 - DMS-REQ-0343-V-02: Number of simultaneous users

4.228.2   Test Items

Verify that the DMS alert filter service supports **numBrokerUsers = 100** simultaneous brokers.

4.228.3   Predecessors

4.228.4   Environment Needs

4.228.4.1   Software

4.228.4.2   Hardware

4.228.5   Input Specification

Rubin Observatory

4.228.6 Output Specification

4.228.7 Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Create a simulated alert stream.
	Test Data	No data.
	Expected Result	
2	Description	Simultaneously execute user-defined alert filters for at least **numBrokerUsers = 100** users, and confirm that the system successfully filters the stream as requested. Confirm that the bandwidth requirement of **numBrokerAlerts = 20** per user was met.Simultaneously execute user-defined alert filters for at least 100 users, and confirm that the system successfully filters the stream as requested.
	Test Data	No data.
	Expected Result	All of the (simulated) **numBrokerUsers = 100** users successfully receive their requested filtered alerts.

4.229 LVV-T1264 - Verify implementation of archiving camera test data

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Robert Gruendl

Open LVV-T1264 in Jira

4.229.1 Verification Elements

• LVV-9637 - DMS-REQ-0372-V-01: Archiving Camera Test Data

4.229.2 Test Items

Verify that a subset of camera test data has been ingested into Butler repos and is available through standard data access tools.

Rubin Observatory

4.229.3   Predecessors

4.229.4   Environment Needs

4.229.4.1   Software

4.229.4.2   Hardware

4.229.5   Input Specification

4.229.6   Output Specification

4.229.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Obtain some data on a camera test stand.
	Test Data	No data.
	Expected Result	
2	Description	Wait a sufficient amount of time, then confirm that automatic transfer/ingest of the data has occurred, and a repo is available at NCSA.
	Test Data	No data.
	Expected Result	The data is present at NCSA in non-empty repos.
3	Description	Identify the relevant Butler repo of ingested camera test stand data.
	Test Data	No data.
	Expected Result	
4-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.

Rubin Observatory

Step	Description, Input Data and Expected Result	

5	Description	Read various repo data products with the Butler, and confirm that they contain the expected data.
	Test Data	No data.
	Expected Result	Camera test stand data that is well-formed.

4.230 LVV-T1276 - Verify implementation of latency of reporting optical transients

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Eric Bellm

Open LVV-T1276 in Jira

4.230.1 Verification Elements

- LVV-9740 - DMS-REQ-0004-V-02: Latency of reporting optical transients

4.230.2 Test Items

Verify that alerts are generated for optical transients within **OTT1 = 1 minute** of the completion of the readout of the last image.

4.230.3 Predecessors

4.230.4 Environment Needs

4.230.4.1 Software

4.230.4.2 Hardware

Rubin Observatory

4.230.5   Input Specification

4.230.6   Output Specification

4.230.7   Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Identify a precursor dataset containing raw images (and templates), that is suitable for testing the Alert Production.
	Test Data	No data.
	Expected Result	
2-1 from LVV-T866	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2-2 from LVV-T866	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	
3	Description	Time processing of data starting from (pre-ingested) raw files until an alert is available for distribution; verify that this time is less than OTT1.
	Test Data	No data.
	Expected Result	Alerts are received via the alert stream within OTT1=1 minute from the time the Alert Production payload was executed.

4.231   LVV-T1277 - Verify processing of maximum number of calibration exposures

Version	Status	Priority	Verification Type	Owner

1	Draft	Normal	Test	Kian-Tat Lim

Open LVV-T1277 in Jira

4.231.1 Verification Elements

- LVV-9745 - DMS-REQ-0131-V-02: Max number of calibs to be processed

4.231.2 Test Items

Verify that as many as **nCalExpProc = 25** calibration exposures can be processed together within time calProcTime.

4.231.3 Predecessors

4.231.4 Environment Needs

4.231.4.1 Software

4.231.4.2 Hardware

4.231.5 Input Specification

4.231.6 Output Specification

4.231.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset of raw calibration exposures containing at least **nCalExpProc = 25** exposures. (If it contains more than 25 exposures, use only 25 for the test.)
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
2-1 from LVV-T1059	Description	Execute the Daily Calibration Products Update payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1059	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Confirm that the processing completed successfully within **calProcTime = 1200 seconds.**
	Test Data	No data.
	Expected Result	Calibration products resulting from processed raw calibration exposures are present within calProcTime, and are well-formed images.
4	Description	Perform the test again with *more than* nCalExpProc = 25 images, and confirm that the processing completes within **calProcTime = 1200 seconds.**
	Test Data	No data.
	Expected Result	Calibration products resulting from processed raw calibration exposures are present within calProcTime, and are well-formed images. (To verify that the test with 25 images was not at the limits of what the software can handle – should be able to exceed that bare minimum.)

4.232 LVV-T1332 - Verify implementation of maximum time for retrieval of CCD-sized coadd cutouts

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Test	Leanne Guy

Open LVV-T1332 in Jira

Rubin Observatory

4.232.1   Verification Elements

- LVV-9797 - DMS-REQ-0377-V-02: Max time to retrieve single-CCD coadd cutout image

4.232.2   Test Items

Verify that at least **ccdRetrievalUsers = 20** users can retrieve CCD-sized coadd cutouts using the IVOA SODA protocol within a maximum retrieval time of **ccdRetrievalTime = 15 seconds**.

4.232.3   Predecessors

4.232.4   Environment Needs

4.232.4.1   Software

4.232.4.2   Hardware

4.232.5   Input Specification

4.232.6   Output Specification

4.232.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Confirm that CCD-sized cutouts from coadds, also containing mask and variance planes, are available on the SODA server. If none are available, copy an image (or some images) to the server.
	Test Data	No data.
	Expected Result	At least one CCD-sized coadd cutout is available, and is a well-formed image.
2	Description	Simulate SODA queries by at least **ccdRetrievalUsers = 20** users at the same time.
	Test Data	No data.
	Expected Result	

Rubin Observatory

Step	Description, Input Data and Expected Result	
3	Description	Monitor the time that each query takes to complete, and confirm that all simulated users retrieved the desired image(s) within **ccdRetrievalTime = 15 seconds.**
	Test Data	No data.
	Expected Result	All of the simulated **ccdRetrievalUsers = 20** users retrieved images within **ccdRetrieval-Time = 15 seconds.**

4.233   LVV-T1524 - Verify Implementation of Exporting MOCs as FITS

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1524 in Jira

4.233.1   Verification Elements

• LVV-18222 - DMS-REQ-0384-V-01: Export MOCs As FITS_1

4.233.2   Test Items

Verify that the Data Management system provides a means for exporting the LSST-generated MOCs in the FITS serialization form defined in the IVOA MOC Recommendation.

4.233.3   Predecessors

4.233.4   Environment Needs

4.233.4.1   Software

4.233.4.2   Hardware

4.233.5   Input Specification

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

417

Rubin Observatory

4.233.6 Output Specification

4.233.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.234 LVV-T1525 - Verify Implementation of Linkage Between HiPS Maps and Coadded Images

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1525 in Jira

4.234.1 Verification Elements

• LVV-18223 - DMS-REQ-0381-V-01: HiPS Linkage to Coadds_1

4.234.2 Test Items

Verify that the HiPS maps produced by the Data Management system provide for straightforward linkage from the HiPS data to the underlying LSST coadded images, and that this has been implemented using a mechanism supported by both the LSST Science Platform and by community tools.

4.234.3 Predecessors

4.234.4 Environment Needs

4.234.4.1 Software

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

418

4.234.4.2 Hardware

4.234.5 Input Specification

4.234.6 Output Specification

4.234.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.235 LVV-T1526 - Verify Availability of Secure and Authenticated HiPS Service

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1526 in Jira

4.235.1 Verification Elements

• LVV-18224 - DMS-REQ-0380-V-01: HiPS Service_1

4.235.2 Test Items

Verify that the Data Management system includes a secure and authenticated Internet end-point for an IVOA-compliant HiPS service. Confirm that this service is advertised via Registry as well as in the HiPS community mechanism operated by CDS, or whatever equivalent mechanism may exist in the LSST operations era.

4.235.3 Predecessors

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. **– DRAFT NOT YET APPROVED**

419

Rubin Observatory

4.235.4 Environment Needs

4.235.4.1 Software

4.235.4.2 Hardware

4.235.5 Input Specification

4.235.6 Output Specification

4.235.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.236 LVV-T1527 - Verify Support for HiPS Visualization

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1527 in Jira

4.236.1 Verification Elements

- LVV-18225 - DMS-REQ-0382-V-01: HiPS Visualization_1

Rubin Observatory

4.236.2   Test Items

Verify that the LSST Science Platform supports the visualization of LSST-generated HiPS image maps as well as other HiPS maps which satisfy the IVOA HiPS Recommendation. Also verify that integrated behavior is available, such as the overplotting of catalog entries, comparable to that provided for individual source images (e.g., PVIs and coadd tiles).

4.236.3   Predecessors

4.236.4   Environment Needs

4.236.4.1   Software

4.236.4.2   Hardware

4.236.5   Input Specification

4.236.6   Output Specification

4.236.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.237   LVV-T1528 - Verify Visualization of MOCs via Science Platform

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1528 in Jira

4.237.1   Verification Elements

- LVV-18226 - DMS-REQ-0385-V-01: MOC Visualization_1

4.237.2   Test Items

Verify that the LSST Science Platform supports the visualization of the LSST-generated MOCs as well as other MOCs which satisfy the IVOA MOC Recommendation.

4.237.3   Predecessors

4.237.4   Environment Needs

4.237.4.1   Software

4.237.4.2   Hardware

4.237.5   Input Specification

4.237.6   Output Specification

4.237.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.238   LVV-T1529 - Verify Production of All-Sky HiPS Map

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1529 in Jira

4.238.1 Verification Elements

- LVV-18227 - DMS-REQ-0379-V-01: Produce All-Sky HiPS Map_1

4.238.2 Test Items

Verify that Data Release Production includes the production of an all-sky image map for the existing coadded image area in each filter band, and at least one pre-defined all-sky color image map, following the IVOA HiPS Recommendation.

4.238.3 Predecessors

4.238.4 Environment Needs

4.238.4.1 Software

4.238.4.2 Hardware

4.238.5 Input Specification

4.238.6 Output Specification

4.238.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.239   LVV-T1530 - Verify Production of Multi-Order Coverage Maps for Survey Data

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1530 in Jira

4.239.1   Verification Elements

- LVV-18228 - DMS-REQ-0383-V-01: Produce MOC Maps_1

4.239.2   Test Items

Verify that Data Release Production includes the production of Multi-Order Coverage maps for the survey data, conformant with the IVOA MOC recommendation. Confirm that separate MOC are produced for each filter band for the main survey, and additional MOCs are produced to represent special-programs datasets and other collections of on-sky data.

4.239.3   Predecessors

4.239.4   Environment Needs

4.239.4.1   Software

4.239.4.2   Hardware

4.239.5   Input Specification

4.239.6   Output Specification

4.239.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.240 LVV-T1549 - LDM-503-6 Comcam verification readiness

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Demonstration	Michelle Butler

Open LVV-T1549 in Jira

4.240.1 Verification Elements

- LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly

- LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS

4.240.2 Test Items

Verify that Comcam has all the services running and verified working for retrieving an image from the comcam DAQ and store it on file systems at the LDF for viewing by LSP.

4.240.3 Predecessors

4.240.4 Environment Needs

4.240.4.1 Software

Rubin Observatory

4.240.4.2 Hardware

4.240.5 Input Specification

Comcam must be In LaSerena and producing images with proper headers.

4.240.6 Output Specification

4.240.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	CC-DAQ produces an image
	Test Data	DAQ produces a SAL message that a image has been created
	Expected Result	in memory file created in DAQ
2	Description	Archiver and Forwarder build image with proper header from header service
	Test Data	Good image file with proper header with all 9 CCDs
	Expected Result	9 image files all with individual headers and then 1 header for all 9 images too.
3	Description	AT-archiver/forwarder transfers the file to the l1-handoff machine.
	Test Data	l1-handoff machine has image file now on local disk.
	Expected Result	image file now found on disk on L1-handoff with hardlinks to 2 different file systems (OODS and DBB) services.
4	Description	OODS service running on L1-handoff machine ingests the image file into Butler/G3 and readies the file systems for the commissioning cluster at the Base to be able to mount and see the new files.
	Test Data	Image file ingested to local butler for Base
	Expected Result	Image file ingested

Rubin Observatory

Step	Description, Input Data and Expected Result	
5	Description	DBB transfers the file to NCSA thorough the DBB-gateway machines and DTN nodes at the base.
	Test Data	No data.
	Expected Result	data file arrives at file systems at NCSA

Step	Description, Input Data and Expected Result	
6	Description	Files are ingested into the butler/G3 at NCSA and moved to file systems that are viewable by the LSP.
	Test Data	No data.
	Expected Result	data can be seen and retrieved by LSP.

4.241   LVV-T1550 - LDM-503-10 DAQ Validation

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Demonstration	Michelle Butler

Open LVV-T1550 in Jira

4.241.1   Verification Elements

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition

- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly

4.241.2   Test Items

Verify that the DAQ can talk to test machines at the BDC through the DWDM network.

Rubin Observatory

4.241.3   Predecessors

DAQ network at the base; forwarders and L1 handoff machine must be available to the DAQ COB at the summit, and forwarders and other test machines must be configured and set up on the BDC networks.

4.241.4   Environment Needs

4.241.4.1   Software

4.241.4.2   Hardware

4.241.5   Input Specification

DAQ at the Summit and machines on networks at the base.

4.241.6   Output Specification

4.241.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	have DAQ produce image at the summit
	Test Data	No data.
	Expected Result	Image on At-archiver
2	Description	The forwarder at the BDC should be able to have communication with the DAQ that the image was taken, and be able to see the file.
	Test Data	No data.
	Expected Result	Image available for the forwarder at the base.
3	Description	Communication between the forwarder and the DAQ are in place with messages being exchanged.

Rubin Observatory

Step	Description, Input Data and Expected Result	
Test Data	No data.	
Expected Result	if messages can be exchanged, the communication has been established.	

4.242 LVV-T1556 - LDM-503-10B Large Scale CCOB Data Access

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Michelle Butler

Open LVV-T1556 in Jira

4.242.1 Verification Elements

- LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition
- LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition
- LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly
- LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS
- LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata

4.242.2 Test Items

Demonstrate the ability to transfer data from the SLAC test stand or CCOB with 21 rafts from SLAC and ingested at NCSA and make available through an instance of the LSP

4.242.3 Predecessors

4.242.4 Environment Needs

4.242.4.1 Software

4.242.4.2   Hardware

4.242.5   Input Specification

SLAC or some other test stand needs to have produced 21 rafts of data that has some env-
iornment for transferring the data to NCSA.

4.242.6   Output Specification

4.242.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Have a system at SLAC that has the 21 raft data that needs to be transferred to NCSA, and all accounts and scripts installed on environment that can read that data.
	Test Data	21 rafts of data with proper headers
	Expected Result	scripts are able to transfer the data to NCSA though rsync or bbcp.
2	Description	Data is transferred to NCSA and ingested into Butler
	Test Data	21 rafts of data
	Expected Result	Data is transferred to NCSA, and can now be see in file systems by the LSP.
3	Description	using the LSP view the data in the ingested directory
	Test Data	21 rafts of data with proper headers and available with Butler.get
	Expected Result	data can be viewed.

4.243   LVV-T1560 - Verify archiving of processing provenance

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Jeffrey Carlin

Open LVV-T1560 in Jira

Rubin Observatory

4.243.1 Verification Elements

- LVV-18230 - DMS-REQ-0386-V-01: Archive Processing Provenance_1

4.243.2 Test Items

Verify that provenance information related to data processing, including relevant data from other subsystems, has been archived.

4.243.3 Predecessors

4.243.4 Environment Needs

4.243.4.1 Software

4.243.4.2 Hardware

4.243.5 Input Specification

4.243.6 Output Specification

4.243.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.244 LVV-T1561 - Verify provenance availability to science users

Version	Status	Priority	Verification Type	Owner

Rubin Observatory

1	Draft	Normal	Inspection	Jeffrey Carlin

Open LVV-T1561 in Jira

4.244.1 Verification Elements

- LVV-18231 - DMS-REQ-0387-V-01: Serve Archived Provenance_1

4.244.2 Test Items

Verify that archived provenance data is available to science users together with the associated science data products.

4.244.3 Predecessors

4.244.4 Environment Needs

4.244.4.1 Software

4.244.4.2 Hardware

4.244.5 Input Specification

4.244.6 Output Specification

4.244.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

Rubin Observatory

4.245   LVV-T1562 - Verify availability of re-run tools

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1562 in Jira

4.245.1   Verification Elements

- LVV-18232 - DMS-REQ-0388-V-01: Provide Re-Run Tools_1

4.245.2   Test Items

Verify that tools are provided to use the archived provenance data to re-run a data processing operation under the same conditions (including LSST software version, its configuration parameters, and supporting data such as calibration frames) as a previous run of that operation.

4.245.3   Predecessors

4.245.4   Environment Needs

4.245.4.1   Software

4.245.4.2   Hardware

4.245.5   Input Specification

4.245.6   Output Specification

4.245.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected	
	Result	

4.246 LVV-T1563 - Verify re-run on different system produces the same results

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1563 in Jira

4.246.1 Verification Elements

- LVV-18233 - DMS-REQ-0390-V-01: Re-Runs on Other Systems_1

4.246.2 Test Items

Verify that tools are provided to use the archived provenance data to re-run a data processing operation on different systems, and that the results produced are the same to the extent computationally feasible.

4.246.3 Predecessors

4.246.4 Environment Needs

4.246.4.1 Software

4.246.4.2 Hardware

4.246.5 Input Specification

Rubin Observatory

4.246.6 Output Specification

4.246.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.247 LVV-T1564 - Verify re-run on similar system produces the same results

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1564 in Jira

4.247.1 Verification Elements

- LVV-18234 - DMS-REQ-0389-V-01: Re-Runs on Similar Systems_1

4.247.2 Test Items

Verify that a provenance-based re-run that is run on the same system, or a system with identically configured hardware and system software, produces the same results.

4.247.3 Predecessors

4.247.4 Environment Needs

4.247.4.1 Software

4.247.4.2   Hardware

4.247.5   Input Specification

4.247.6   Output Specification

4.247.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.248   LVV-T1612 - Verify Summit - Base Network Integration (System Level)

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Jeff Kantor

Open LVV-T1612 in Jira

4.248.1   Verification Elements

• LVV-73 - DMS-REQ-0171-V-01: Summit to Base Network

4.248.2   Test Items

Verify ISO Layer 3 full (22 x 10 Gbps ethernet ports on DAQ side with test data from DAQ test stand, AURA, Camera DAQ team do test). Demonstrate transfer of data at or exceeding rates specified in LDM-142.

Rubin Observatory

4.248.3   Predecessors

See pre-conditions.

4.248.4   Environment Needs

4.248.4.1   Software   See pre-conditions.

4.248.4.2   Hardware   See pre-conditions.

4.248.5   Input Specification

1. PMCS DMTC-7400-2400 COMPLETE
2. LVV-T1168 Passed
3. EITHER: Full Camera DAQ installed on summit and loaded with data OR: high-quality DAQ application-level simulators that match the form, volume, file paths, compressibility, and cadence of the expected instrument data, running on end node computers that are the production hardware or equivalent to it. Scientific validity of the data content is not essential.
4. Archiver/forwarders installed at Base running on end node computers that are the production hardware or equivalent to it.
5. As-built documentation for all of the above is available.

NOTE: This test will be repeated at increasing data volumes as additional observatory capabilities (e.g. ComCAM, FullCam) become available. Final verification will be tested at full operational volume.After the initial test, the corresponding verification elements will be flagged as "Requires Monitoring" such that those requirements will be closed out as having been verified but will continue to be monitored throughout commissioning to ensure they do not drop out of compliance.

4.248.6   Output Specification

4.248.7   Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Verify Pre-conditions are satisfied.
	Test Data	NA
	Expected Result	Pre-conditions are satisfied.
2	Description	Transfer data between summit and base over uninterrupted 1 day period. Monitor transfer of data at or exceeding rates specified in LDM-142.
	Test Data	DAQ pre-loaded data
	Expected Result	Data transfers at or exceeding rates specified in LDM-142.

4.249 LVV-T1745 - Verify calculation of median relative astrometric measurement error on 20 arcminute scales

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1745 in Jira

4.249.1 Verification Elements

• LVV-3402 - DMS-REQ-0360-V-01: Median astrometric error on 20 arcmin scales

4.249.2 Test Items

Verify that the DM system has provided the code to calculate the median relative astrometric measurement error on 20 arcminute scales and assess whether it meets the requirement that it shall be no more than AM2 = 10 milliarcseconds.

4.249.3 Predecessors

4.249.4   Environment Needs

4.249.4.1   Software

4.249.4.2   Hardware

4.249.5   Input Specification

4.249.6   Output Specification

4.249.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AM2 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AM2 has been calculated.

4.250 LVV-T1746 - Verify calculation of fraction of relative astrometric measurement error on 5 arcminute scales exceeding outlier limit

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1746 in Jira

4.250.1 Verification Elements

- LVV-9767 - DMS-REQ-0360-V-02: Max fraction exceeding limit on 5 arcmin scales

- LVV-9773 - DMS-REQ-0360-V-07: Outlier limit on 5 arcmin scales

4.250.2 Test Items

Verify that the DM system has provided the code to calculate the maximum fraction of relative astrometric measurements on 5 arcminute scales that exceed the 5 arcminute outlier limit **AD1 = 20 milliarcseconds**, and assess whether it meets the requirement that it shall be less than **AF1 = 10 percent.**

4.250.3 Predecessors

4.250.4   Environment Needs

4.250.4.1   Software

4.250.4.2   Hardware

4.250.5   Input Specification

4.250.6   Output Specification

4.250.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):

Step	Description, Input Data and Expected Result	
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AF1 has been calculated using the outlier limit AD1, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AF1 has been calculated (and used the limit AD1).

4.251   LVV-T1747 - Verify calculation of relative astrometric measurement error on 5 arcminute scales

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1747 in Jira

4.251.1   Verification Elements

• LVV-9768 - DMS-REQ-0360-V-03: Median astrometric error on 5 arcmin scales

4.251.2   Test Items

Verify that the DM system has provided the code to calculate the relative astrometric measurement error on 5 arcminute scales, and assess whether it meets the requirement that it shall be less than **AM1 = 10 milliarcseconds.**

4.251.3   Predecessors

Rubin Observatory

4.251.4   Environment Needs

4.251.4.1   Software

4.251.4.2   Hardware

4.251.5   Input Specification

4.251.6   Output Specification

4.251.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AM1 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AM1 has been calculated.

4.252   LVV-T1748 - Verify calculation of median error in absolute position for RA, Dec axes

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1748 in Jira

4.252.1   Verification Elements

- LVV-9769 - DMS-REQ-0360-V-04: Median absolute error in RA, Dec

4.252.2   Test Items

Verify that the DM system has provided the code to calculate the median error in absolute position for each axis, RA and DEC, and assess whether it meets the requirement that it shall be less than **AA1 = 50 milliarcseconds**.

4.252.3   Predecessors

4.252.4   Environment Needs

4.252.4.1   Software

Rubin Observatory

4.252.4.2 Hardware

4.252.5 Input Specification

4.252.6 Output Specification

4.252.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Confirm that the metric AA1 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AA1 has been calculated.

4.253 LVV-T1749 - Verify calculation of fraction of relative astrometric measurement error on 20 arcminute scales exceeding outlier limit

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1749 in Jira

4.253.1 Verification Elements

- LVV-9776 - DMS-REQ-0360-V-10: Max fraction exceeding limit on 20 arcmin scales

- LVV-9770 - DMS-REQ-0360-V-05: Outlier limit on 20 arcmin scales

4.253.2 Test Items

Verify that the DM system has provided the code to calculate the maximum fraction of relative astrometric measurements on 20 arcminute scales that exceed the 20 arcminute outlier limit **AD2 = 20 milliarcseconds**, and assess whether it meets the requirement that it shall be less than **AF2 = 10 percent.**

4.253.3 Predecessors

4.253.4 Environment Needs

4.253.4.1 Software

4.253.4.2 Hardware

4.253.5 Input Specification

4.253.6 Output Specification

4.253.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Confirm that the metric AF2 has been calculated using the outlier limit AD2, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AF2 has been calculated (and used the limit AD2).

4.254 LVV-T1750 - Verify calculation of separations relative to r-band exceeding color difference outlier limit

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1750 in Jira

4.254.1 Verification Elements

- LVV-9771 - DMS-REQ-0360-V-06: Color difference outlier limit relative to r-band

- LVV-9777 - DMS-REQ-0360-V-11: Max fraction of r-band color difference outliers

4.254.2 Test Items

Verify that the DM system has provided the code to calculate the separations measured relative to the r-band that exceed the color difference outlier limit **AB2 = 20 milliarcseconds**, and assess whether it meets the requirement that it shall be less than **ABF1 = 10 percent.**

4.254.3 Predecessors

4.254.4 Environment Needs

4.254.4.1 Software

Rubin Observatory

4.254.4.2   Hardware

4.254.5   Input Specification

4.254.6   Output Specification

4.254.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits, and including at least one visit in r-band.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."

Rubin Observatory

Step	Description, Input Data and Expected Result	
4	Description	Confirm that the metric ABF1 has been calculated using the outlier limit AB2, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that ABF1 has been calculated (and used the limit AB2).

4.255 LVV-T1751 - Verify calculation of median relative astrometric measurement error on 200 arcminute scales

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1751 in Jira

4.255.1 Verification Elements

- LVV-9774 - DMS-REQ-0360-V-08: Median astrometric error on 200 arcmin scales

4.255.2 Test Items

Verify that the DM system has provided the code to calculate the median relative astrometric measurement error on 200 arcminute scales and assess whether it meets the requirement that it shall be no more than AM3 = 15 milliarcseconds.

4.255.3 Predecessors

4.255.4 Environment Needs

4.255.4.1 Software

4.255.4.2 Hardware

Rubin Observatory

4.255.5   Input Specification

4.255.6   Output Specification

4.255.7   Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Identify a dataset containing at least one field with multiple overlapping visits, and that covers an area larger than 200 arcminutes.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AM3 has been calculated, and that its values are reasonable.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AM3 has been calculated.	

4.256 LVV-T1752 - Verify calculation of fraction of relative astrometric measurement error on 200 arcminute scales exceeding outlier limit

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1752 in Jira

4.256.1 Verification Elements

- LVV-9779 - DMS-REQ-0360-V-13: Max fraction exceeding limit on 200 arcmin scales

4.256.2 Test Items

Verify that the DM system has provided the code to calculate the maximum fraction of relative astrometric measurements on 200 arcminute scales that exceed the 200 arcminute outlier limit **AD3 = 30 milliarcseconds**, and assess whether it meets the requirement that it shall be less than **AF3 = 10 percent.**

4.256.3 Predecessors

4.256.4 Environment Needs

4.256.4.1 Software

4.256.4.2 Hardware

4.256.5 Input Specification

Rubin Observatory

4.256.6   Output Specification

4.256.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits, and that covers an area larger than 200 arcminutes.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AF3 has been calculated using the outlier limit AD3, and that its values are reasonable.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result	
Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AF3 has been calculated (and used the limit AD3).	

4.257 LVV-T1753 - Verify calculation of RMS difference of separations relative to r-band

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1753 in Jira

4.257.1 Verification Elements

- LVV-9778 - DMS-REQ-0360-V-12: RMS difference between r-band and other filter separation

4.257.2 Test Items

Verify that the DM system has provided the code to calculate the separations measured relative to the r-band, and assess whether it meets the requirement that it shall be less than **AB1 = 10 milliarcseconds.**

4.257.3 Predecessors

4.257.4 Environment Needs

4.257.4.1 Software

4.257.4.2 Hardware

4.257.5 Input Specification

Rubin Observatory

4.257.6   Output Specification

4.257.7   Test Procedure

Step		Description, Input Data and Expected Result
1	Description	Identify a dataset containing at least one field with multiple overlapping visits, and including at least one visit in r-band.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric AB1 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that AB1 has been calculated.

Rubin Observatory

Step	Description, Input Data and Expected Result

4.258   LVV-T1754 - Verify calculation of residual PSF ellipticity correlations for separations less than 5 arcmin

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1754 in Jira

4.258.1   Verification Elements

- LVV-3404 - DMS-REQ-0362-V-01: Median residual PSF ellipticity correlations on 5 arcmin scales

4.258.2   Test Items

Verify that the DM system has provided the code to calculate the median residual PSF ellipticity correlations averaged over an arbitrary field of view for separations less than 5 arcmin, and assess whether it meets the requirement that it shall be no greater than **TE2 = 1.0e-7[arcminuteSeparationCorrelation].**

4.258.3   Predecessors

4.258.4   Environment Needs

4.258.4.1   Software

4.258.4.2   Hardware

4.258.5   Input Specification

Rubin Observatory

4.258.6 Output Specification

4.258.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric TE2 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that TE2 has been calculated.

Rubin Observatory

4.259 LVV-T1755 - Verify calculation of residual PSF ellipticity correlations for separations less than 1 arcmin

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1755 in Jira

4.259.1 Verification Elements

- LVV-9782 - DMS-REQ-0362-V-04: Median residual PSF ellipticity correlations on 1 arcmin scales

4.259.2 Test Items

Verify that the DM system has provided the code to calculate the median residual PSF ellipticity correlations averaged over an arbitrary field of view for separations less than 1 arcmin, and assess whether it meets the requirement that it shall be no greater than **TE1 = 2.0e-5[arcminuteSeparationCorrelation].**

4.259.3 Predecessors

4.259.4 Environment Needs

4.259.4.1 Software

4.259.4.2 Hardware

4.259.5 Input Specification

4.259.6 Output Specification

4.259.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric TE1 has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that TE1 has been calculated.

4.260   LVV-T1756 - Verify calculation of photometric repeatability in uzy filters

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1756 in Jira

4.260.1 Verification Elements

- LVV-3401 - DMS-REQ-0359-V-01: RMS photometric repeatability in uzy

4.260.2 Test Items

Verify that the DM system has provided the code to calculate the RMS photometric repeatability of bright non-saturated unresolved point sources in the u, z, and y filters, and assess whether it meets the requirement that it shall be less than **PA1uzy = 7.5 millimagnitudes**.

4.260.3 Predecessors

4.260.4 Environment Needs

4.260.4.1 Software

4.260.4.2 Hardware

4.260.5 Input Specification

4.260.6 Output Specification

4.260.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field in each of the u, z, and y filters with multiple overlapping visits.

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
3	Description	Confirm that the metric PA1uzy has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that PA1uzy has been calculated.

4.261 LVV-T1757 - Verify calculation of photometric repeatability in gri filters

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1757 in Jira

4.261.1 Verification Elements

- LVV-9759 - DMS-REQ-0359-V-10: RMS photometric repeatability in gri

4.261.2 Test Items

Verify that the DM system has provided the code to calculate the RMS photometric repeatability of bright non-saturated unresolved point sources in the g, r, and i filters, and assess whether it meets the requirement that it shall be less than **PA1gri = 5.0 millimagnitudes**.

4.261.3 Predecessors

4.261.4 Environment Needs

4.261.4.1 Software

4.261.4.2 Hardware

4.261.5 Input Specification

4.261.6 Output Specification

4.261.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field in each of the g, r, and i filters with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
3	Description	Confirm that the metric PA1gri has been calculated, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that PA1gri has been calculated.

4.262 LVV-T1758 - Verify calculation of photometric outliers in uzy bands

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1758 in Jira

4.262.1 Verification Elements

- LVV-9758 - DMS-REQ-0359-V-09: Repeatability outlier limit in uzy

- LVV-9752 - DMS-REQ-0359-V-03: Max fraction of outliers among non-saturated sources

4.262.2 Test Items

Verify that the DM system has provided the code to calculate the photometric repeatability in the u, z, and y filters, and assess whether it meets the requirement that no more than **PF1 = 10[percent]** of the repeatability outliers exceed the outlier limit of **PA2uzy = 22.5 millimagnitudes**.

4.262.3 Predecessors

4.262.4 Environment Needs

4.262.4.1 Software

4.262.4.2 Hardware

4.262.5 Input Specification

4.262.6 Output Specification

4.262.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field in each of the u, z, and y filters with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric PA2uzy has been calculated using the threshold PF1, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that PA2uzy has been calculated (and that it used PF1).

Rubin Observatory

4.263 LVV-T1759 - Verify calculation of photometric outliers in gri bands

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1759 in Jira

4.263.1 Verification Elements

- LVV-9752 - DMS-REQ-0359-V-03: Max fraction of outliers among non-saturated sources
- LVV-9754 - DMS-REQ-0359-V-05: Repeatability outlier limit in gri

4.263.2 Test Items

Verify that the DM system has provided the code to calculate the photometric repeatability in the g, r, and i filters, and assess whether it meets the requirement that no more than **PF1 = 10[percent]** of the repeatability outliers exceed the outlier limit of **PA2gri = 15 millimagnitudes**.

4.263.3 Predecessors

4.263.4 Environment Needs

4.263.4.1 Software

4.263.4.2 Hardware

4.263.5 Input Specification

4.263.6 Output Specification

4.263.7 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Identify a dataset containing at least one field in each of the g, r, and i filters with multiple overlapping visits.
	Test Data	No data.
	Expected Result	A dataset that has been ingested into a Butler repository.
2-1 from LVV-T860	Description	The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:
	Test Data	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary. To check versions in use, type: eups list -s
3-1 from LVV-T1744	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."
4	Description	Confirm that the metric PA2gri has been calculated using the threshold PF1, and that its values are reasonable.
	Test Data	No data.
	Expected Result	A JSON file (and/or a report generated from that JSON file) demonstrating that PA2gri has been calculated (and that it used PF1).

Rubin Observatory

4.264   LVV-T1830 - Verify Implementation of Scientific Visualization of Camera Image Data

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Inspection	Jeffrey Carlin

Open LVV-T1830 in Jira

4.264.1   Verification Elements

- LVV-18465 - DMS-REQ-0395-V-01: Scientific Visualization of Camera Image Data_1

4.264.2   Test Items

Verify that all scientific visualization of camera image data uses the coordinate systems defined in LSE-349.

4.264.3   Predecessors

4.264.4   Environment Needs

4.264.4.1   Software

4.264.4.2   Hardware

4.264.5   Input Specification

4.264.6   Output Specification

4.264.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.265   LVV-T1831 - Verify Implementation of Data Management Nightly Reporting

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Demonstration	Jeffrey Carlin

Open LVV-T1831 in Jira

4.265.1   Verification Elements

- LVV-18295 - DMS-REQ-0394-V-01: Data Management Nightly Reporting_1

4.265.2   Test Items

Verify that the LSST Data Management subsystem produces a searchable - interactive nightly report(s), from information published in the EFD by each subsystem, summarizing performance and behavior over a user defined period of time (e.g. the previous 24 hours).

4.265.3   Predecessors

4.265.4   Environment Needs

4.265.4.1   Software

4.265.4.2   Hardware

Rubin Observatory

4.265.5   Input Specification

4.265.6   Output Specification

4.265.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.266   LVV-T1836 - Verify calculation of resolved-to-unresolved flux ratio errors

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1836 in Jira

4.266.1   Verification Elements

- LVV-9766 - DMS-REQ-0359-V-17: Max RMS of resolved/unresolved flux ratio

4.266.2   Test Items

Verify that the DM system has provided code to assess whether the maximum RMS of the ratio of the error in integrated flux measurement between bright, isolated, resolved sources less than 10 arcsec in diameter and bright, isolated unresolved point sources is less than **ResSource = 2**.

4.266.3   Predecessors

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – **DRAFT NOT YET APPROVED**

469

4.266.4   Environment Needs

4.266.4.1   Software

4.266.4.2   Hardware

4.266.5   Input Specification

4.266.6   Output Specification

4.266.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.267   LVV-T1837 - Verify calculation of band-to-band color zero-point accuracy

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1837 in Jira

4.267.1   Verification Elements

- LVV-9765 - DMS-REQ-0359-V-16: Accuracy of zero point for colors without u-band

Rubin Observatory

4.267.2   Test Items

Verify that the DM system provides code to assess whether the accuracy of absolute band-to-band color zero-points for all colors constructed from any filter pair, excluding the u-band, is less than **PA5 = 5 millimagnitudes**.

4.267.3   Predecessors

4.267.4   Environment Needs

4.267.4.1   Software

4.267.4.2   Hardware

4.267.5   Input Specification

4.267.6   Output Specification

4.267.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.268   LVV-T1838 - Verify calculation of image fraction affected by ghosts

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin
		Open LVV-T1838 in Jira		

4.268.1 Verification Elements

- LVV-9764 - DMS-REQ-0359-V-15: Percentage of image area with ghosts

4.268.2 Test Items

Verify that the DM system provides code to assess whether the percentage of image area that has ghosts with surface brightness gradient amplitude of more than 1/3 of the sky noise over 1 arcsec is less than **GhostAF = 1 percent**.

4.268.3 Predecessors

4.268.4 Environment Needs

4.268.4.1 Software

4.268.4.2 Hardware

4.268.5 Input Specification

4.268.6 Output Specification

4.268.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.269 LVV-T1839 - Verify calculation of RMS width of photometric zeropoint

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

472

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1839 in Jira

4.269.1 Verification Elements

- LVV-9763 - DMS-REQ-0359-V-14: RMS width of zero point in all bands except u

4.269.2 Test Items

Verify that the DM system provides code to assess whether the RMS width of the internal photometric zero-point (precision of system uniformity across the sky) for all bands except u-band is less than **PA3 = 10 millimagnitudes**.

4.269.3 Predecessors

4.269.4 Environment Needs

4.269.4.1 Software

4.269.4.2 Hardware

4.269.5 Input Specification

4.269.6 Output Specification

4.269.7 Test Procedure

Step	Description, Input Data and Expected Result
1	Description
	Test Data No data.

Step	Description, Input Data and Expected Result
	Expected
	Result

4.270 LVV-T1840 - Verify calculation of sky brightness precision

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1840 in Jira

4.270.1 Verification Elements

- LVV-9762 - DMS-REQ-0359-V-13: Max sky brightness error

4.270.2 Test Items

Verify that the DM system provides software to assess whether the maximum error in the precision of the sky brightness determination is less than **SBPrec = 1 percent.**

4.270.3 Predecessors

4.270.4 Environment Needs

4.270.4.1 Software

4.270.4.2 Hardware

4.270.5 Input Specification

4.270.6 Output Specification

Rubin Observatory

4.270.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected	
	Result	

4.271   LVV-T1841 - Verify calculation of scientifically unusable pixel fraction

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1841 in Jira

4.271.1   Verification Elements

- LVV-9761 - DMS-REQ-0359-V-12: Max fraction of unusable pixels per sensor

4.271.2   Test Items

Verify that the DM system provides software to assess whether the maximum fraction of pixels scientifically unusable per sensor out of the total allowable fraction of sensors meeting this performance is less than **PixFrac = 1 percent**.

4.271.3   Predecessors

4.271.4   Environment Needs

4.271.4.1   Software

4.271.4.2   Hardware

4.271.5 Input Specification

4.271.6 Output Specification

4.271.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.272 LVV-T1842 - Verify calculation of zeropoint error fraction exceeding the outlier limit

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1842 in Jira

4.272.1 Verification Elements

- LVV-9760 - DMS-REQ-0359-V-11: Fraction of zero point outliers

4.272.2 Test Items

Verify that the DM system provides software to calculate the fraction of zeropoint errors that exceed the zero point error outlier limit, and confirm that it is less than **PF2 = 10 percent.**

4.272.3 Predecessors

Rubin Observatory

4.272.4   Environment Needs

4.272.4.1   Software

4.272.4.2   Hardware

4.272.5   Input Specification

4.272.6   Output Specification

4.272.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.273   LVV-T1843 - Verify calculation of significance of imperfect crosstalk corrections

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1843 in Jira

4.273.1   Verification Elements

- LVV-9757 - DMS-REQ-0359-V-08: Max cross-talk imperfections

Rubin Observatory

4.273.2   Test Items

Verify that the DM system provides software to assess whether the maximum local significance integrated over the PSF of imperfect crosstalk corrections is less than **Xtalk = 3 sigma**.

4.273.3   Predecessors

4.273.4   Environment Needs

4.273.4.1   Software

4.273.4.2   Hardware

4.273.5   Input Specification

4.273.6   Output Specification

4.273.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.274   LVV-T1844 - Verify calculation of u-band photometric zero-point RMS

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1844 in Jira

Rubin Observatory

4.274.1   Verification Elements

• LVV-9756 - DMS-REQ-0359-V-07: RMS width of zero point in u-band

4.274.2   Test Items

Verify that the DM system provides software to assess whether the RMS width of internal photometric zero-point (precision of system uniformity across the sky) in the u-band is less than **PA3u = 20 millimagnitudes**.

4.274.3   Predecessors

4.274.4   Environment Needs

4.274.4.1   Software

4.274.4.2   Hardware

4.274.5   Input Specification

4.274.6   Output Specification

4.274.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.275   LVV-T1845 - Verify accuracy of photometric transformation to physical scale

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1845 in Jira

4.275.1 Verification Elements

- LVV-9755 - DMS-REQ-0359-V-06: Accuracy of photometric transformation

4.275.2 Test Items

Verify that the DM system provides software to assess whether the accuracy of the transformation of internal LSST photometry to a physical scale (e.g. AB magnitudes) is less than **PA6 = 10 millimagnitudes**.

4.275.3 Predecessors

4.275.4 Environment Needs

4.275.4.1 Software

4.275.4.2 Hardware

4.275.5 Input Specification

4.275.6 Output Specification

4.275.7 Test Procedure

Step	Description, Input Data and Expected Result
1	Description
	Test Data No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
	Expected Result

4.276 LVV-T1846 - Verify calculation of band-to-band color zero-point accuracy including u-band

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1846 in Jira

4.276.1 Verification Elements

- LVV-9753 - DMS-REQ-0359-V-04: Accuracy of zero point for colors with u-band

4.276.2 Test Items

Verify that the DM system provides software to assess whether the accuracy of absolute band-to-band color zero-points for all colors constructed from any filter pair, including the u-band, is less than **PA5u = 10 millimagnitudes**.

4.276.3 Predecessors

4.276.4 Environment Needs

4.276.4.1 Software

4.276.4.2 Hardware

4.276.5 Input Specification

4.276.6   Output Specification

4.276.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.277   LVV-T1847 - Verify calculation of sensor fraction with unusable pixels

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1847 in Jira

4.277.1   Verification Elements

• LVV-9751 - DMS-REQ-0359-V-02: Max fraction of sensors with excess unusable pixels

4.277.2   Test Items

Verify that the DM system provides software to assess whether the maximum allowable fraction of sensors with **PixFrac > 1** percent scientifically unusable pixels is less than **SensorFraction = 15 percent.**

4.277.3   Predecessors

4.277.4   Environment Needs

4.277.4.1   Software

Rubin Observatory

4.277.4.2 Hardware

4.277.5 Input Specification

4.277.6 Output Specification

4.277.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.278 LVV-T1862 - Verify determining effectiveness of dark current frame

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1862 in Jira

4.278.1 Verification Elements

• LVV-18881 - DMS-REQ-0282-V-02: Dark Current Correction Frame Effectiveness

4.278.2 Test Items

Verify that the DMS can determine the effectiveness of a dark correction and determine how often it should be updated.

4.278.3 Predecessors

Execution of LVV-T90.

Rubin Observatory

4.278.4   Environment Needs

4.278.4.1   Software

4.278.4.2   Hardware

4.278.5   Input Specification

4.278.6   Output Specification

4.278.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify the path to a dataset containing dark frames (i.e., exposures taken with the shutter closed).
	Test Data	No data.
	Expected Result	
2-1 from LVV-T1060	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2-2 from LVV-T1060	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	
3	Description	Determining whether the dark correction is being done properly will require on-sky science data. The dark correction can be applied to these frames and the results inspected to ensure that the correction was correctly measured and applied.
	Test Data	No data.

Rubin Observatory

Step	Description, Input Data and Expected Result
Expected Result	Applying the dark correction to a dataset produces noticeable differences between the original frame(s) and the corrected outputs.

4.279 LVV-T1863 - Verify ability to process Special Programs data alongside normal processing

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1863 in Jira

4.279.1 Verification Elements

- LVV-18847 - DMS-REQ-0397-V-01: Prompt/DR Processing of Data from Special Programs_1

4.279.2 Test Items

Verify that Special Programs data can be processed alongside either prompt-products or data-release processing with little or no extra effort by DM staff.

4.279.3 Predecessors

4.279.4 Environment Needs

4.279.4.1 Software

4.279.4.2 Hardware

4.279.5 Input Specification

Rubin Observatory

4.279.6   Output Specification

4.279.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.280   LVV-T1865 - Verify implementation of time to L1 public release for Special Programs

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1865 in Jira

4.280.1   Verification Elements

• LVV-18229 - DMS-REQ-0344-V-01: Time to L1 public release

4.280.2   Test Items

Verify that data from Special Programs are made available via public release within **L1PublicT = 24[hour]** from the acquisition of science data.

4.280.3   Predecessors

4.280.4   Environment Needs

4.280.4.1   Software

Rubin Observatory

4.280.4.2   Hardware

4.280.5   Input Specification

4.280.6   Output Specification

4.280.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.281   LVV-T1866 - Verify latency of reporting optical transients from Special Programs

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1866 in Jira

4.281.1   Verification Elements

• LVV-9744 - DMS-REQ-0344-V-02: Latency of reporting optical transients

4.281.2   Test Items

Verify that optical transients (Level 1 data products) are reported within OTT1 = 1 minute of last image readout for Special Programs.

4.281.3   Predecessors

4.281.4   Environment Needs

4.281.4.1   Software

4.281.4.2   Hardware

4.281.5   Input Specification

4.281.6   Output Specification

4.281.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.282   LVV-T1867 - Verify implementation of at least numStreams alert streams supported

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1867 in Jira

4.282.1   Verification Elements

• LVV-18297 - DMS-REQ-0391-V-01: Alert Stream Distribution nStreams

4.282.2   Test Items

Verify that the LSST system supports the transmission of at least **numStreams=5** full alert streams out of the alert distribution system within **OTT1=1 minute**.

4.282.3   Predecessors

4.282.4   Environment Needs

4.282.4.1   Software

4.282.4.2   Hardware

4.282.5   Input Specification

4.282.6   Output Specification

4.282.7   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.283   LVV-T1868 - Verify implementation of alert streams distributed within latency limit

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin
		Open LVV-T1868 in Jira		

Rubin Observatory

4.283.1 Verification Elements

- LVV-18911 - DMS-REQ-0391-V-02: Alert Stream Distribution Latency

4.283.2 Test Items

Verify that the LSST system supports the transmission of full alert streams out of the alert distribution system within **OTT1=1 minute**.

4.283.3 Predecessors

4.283.4 Environment Needs

4.283.4.1 Software

4.283.4.2 Hardware

4.283.5 Input Specification

4.283.6 Output Specification

4.283.7 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	
	Test Data	No data.
	Expected Result	

4.284 LVV-T1946 - Verify implementation of measurements in catalogs from coadds

Rubin Observatory

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1946 in Jira

4.284.1 Verification Elements

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

4.284.2 Test Items

Verify that source measurements in catalogs containing measurements from coadd images are in flux units.

4.284.3 Predecessors

4.284.4 Environment Needs

4.284.4.1 Software

4.284.4.2 Hardware

4.284.5 Input Specification

4.284.6 Output Specification

4.284.7 Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Butler repo available for reading.

Step		
2	Description	Identify and read an appropriate processed precursor dataset containing coadds with the Butler.
	Test Data	No data.
	Expected Result	
3	Description	Verify that the coadd catalog provides measurements in flux units.
	Test Data	No data.
	Expected Result	Confirmation of measurements in catalogs encoded in flux units.

4.285 LVV-T1947 - Verify implementation of measurements in catalogs from difference images

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Jeffrey Carlin

Open LVV-T1947 in Jira

4.285.1 Verification Elements

- LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs

4.285.2 Test Items

Verify that source measurements in catalogs containing measurements from difference images are in flux units.

4.285.3 Predecessors

Rubin Observatory

4.285.4   Environment Needs

4.285.4.1   Software

4.285.4.2   Hardware

4.285.5   Input Specification

4.285.6   Output Specification

4.285.7   Test Procedure

Step	Description, Input Data and Expected Result	
1-1 from LVV-T987	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Expected Result	Butler repo available for reading.
2	Description	Identify and read an appropriate processed precursor dataset containing difference images with the Butler.
	Test Data	No data.
	Expected Result	
3	Description	Verify that the difference image source catalog provides measurements in flux units.
	Test Data	No data.
	Expected Result	Confirmation of measurements in catalogs encoded in flux units.

5 Reusable Test Cases

Test cases in this section are made up of commonly encountered steps that have been factored out into modular, reusable scripts. These test cases are meant solely for the building of actual tests used for verification, to be inserted in test scripts via the "Call to Test" functionality in Jira/ATM. They streamline the process of writing test scripts by providing pre-designed steps, while also ensuring homogeneity throughout the test suite. These reusable modules are not themselves verifying requirements. Also, these test cases shall not call other reusable test cases in their script.

5.1 LVV-T216 - Installation of the Alert Distribution payloads.

Version	Status	Priority	Verification Type	Owner
1	Approved	Normal	Test	Eric Bellm

Open LVV-T216 in Jira

5.1.1 Test Items

This test will check:

- That the Alert Distribution payloads are available from documented channels.
- That the Alert Distribution payloads can be installed on LSST Data Facility-managed systems.
- That the Alert Distribution payloads can be executed by LSST Data Facility-managed systems.

5.1.2 Environment Needs

5.1.2.1 Hardware This test case shall be executed on the Kubernetes Commons at the LDF. As discussed in https://dmtn-028.lsst.io/ and https://dmtn-081.lsst.io/, the test machine should have at least 16 cores, 64 GB of memory and access to at least 1.5 TB of shared storage.

Rubin Observatory

5.1.3 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Download Kafka Docker image from https://github.com/lsst-dm/alert_stream.
	Test Data	
	Expected Result	Runs without error

2	Description	Change to the alert_stream directory and build the docker image. `docker build -t "lsst-kub001:5000/alert_stream"`
	Test Data	
	Expected Result	Runs without error

3	Description	Register it with Kubernetes docker push lsst-kub001:5000/alert_stream
	Test Data	
	Expected Result	Runs without error

4	Description	From the alert_stream/kubernetes directory, start Kafka and Zookeeper:

```
kubectl create -f zookeeper-service.yaml
kubectl create -f zookeeper-deployment.yaml
kubectl create -f kafka-deployment.yaml
kubectl create -f kafka-service.yaml
```

(use kubectl get pods/services between each command to check status; wait until each is "Running" before starting the next command)

Test Data

DRAFT NOT YET APPROVED – **The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED**

495

Step	Description, Input Data and Expected Result	
	Expected Result	Runs without error
5	Description	Confirm Kafka and Zookeeper are listed when running kubectl get pods and kubectl get services
	Test Data	
	Expected Result	Output should be similar to:

```
kubectl get pods
NAME                    READY   STATUS   RESTARTS  AGE
kafka-768ddf5564-xwgvh   1/1    Running  0        31s
zookeeper-f798cc548-mgkpn 1/1    Running  0        1m


kubectl get services
NAME       TYPE      CLUSTER-IP     EXTERNAL-IP  PORT(S)   AGE
kafka      ClusterIP 10.105.19.124  <none>       9092/TCP  6s
zookeeper  ClusterIP 10.97.110.124  <none>       32181/TCP 2m
```

5.2   LVV-T837 - Authenticate to Notebook Aspect

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T837 in Jira

5.2.1   Test Items

Not specifically a test – modular script to be used in multiple other Test Scripts.

Rubin Observatory

5.2.2   Input Specification

Must have a user account on the LSP.

5.2.3   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Authenticate to the notebook aspect of the LSST Science Platform (NB-LSP). This is currently at https://lsst-lsp-stable.ncsa.illinois.edu/nb.
	Test Data	
	Expected Result	Redirection to the spawner page of the NB-LSP allowing selection of the containerized stack version and machine flavor.
2	Description	Spawn a container by: 1) choosing an appropriate stack version: e.g. the latest weekly. 2) choosing an appropriate machine flavor: e.g. medium 3) click "Spawn"
	Test Data	
	Expected Result	Redirection to the JupyterLab environment served from the chosen container containing the correct stack version.

5.3   LVV-T838 - Access an empty notebook in the Notebook Aspect

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T838 in Jira

5.3.1   Test Items

The steps here cover just those necessary to gain access to an empty notebook after authentication is complete.

Rubin Observatory

5.3.2 Input Specification

Authentication to the Notebook aspect.

5.3.3 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Open a new launcher by navigating in the top menu bar "File" -> "New Launcher"
	Test Data	
	Expected Result	A launcher window with several sections, potentially with several kernel versions for each.
2	Description	Select the option under "Notebook" labeled "LSST" by clicking on the icon.
	Test Data	
	Expected Result	An empty notebook with a single empty cell. The kernel show up as "LSST" in the top right of the notebook.

5.4 LVV-T849 - Authenticate to the portal aspect of the LSP

Version	Status	Priority	Verification Type	Owner
2	Draft	Normal	Test	Simon Krughoff

Open LVV-T849 in Jira

5.4.1 Test Items

Obtain an authenticated session in the portal aspect of the LSST Science Platform

5.4.2 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Navigate to the Portal Aspect endpoint. The stable version should be used for this test and is currently located at: https://lsst-lsp-stable.ncsa.illinois.edu/portal/app/ .
	Test Data	
	Expected Result	A credential-entry screen should be displayed.

Step	Description, Input Data and Expected Result	
2	Description	Enter a valid set of credentials for an LSST user with LSP access on the instance under test.
	Test Data	
	Expected Result	The Portal Aspect UI should be displayed following authentication.

5.5   LVV-T850 - Log out of the portal aspect of the LSP

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T850 in Jira

5.5.1   Test Items

Leave the portal aspect of the LSST Science Platform in a clean state

5.5.2   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Currently, there is no logout mechanism on the portal. This should be updated as the system matures. Simply close the browser window.
	Test Data	
	Expected Result	Closed browser window. When navigating to the portal endpoint, expect to execute the steps in LVV-T849.

Rubin Observatory

Step	Description, Input Data and Expected Result

5.6   LVV-T860 - Initialize science pipelines

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T860 in Jira

5.6.1   Test Items

Initialize the science pipelines software for use.

5.6.2   Input Specification

An installed software stack, either locally, on 'lsst-dev', or through the Notebook aspect.

5.6.3   Test Procedure

Step	Description, Input Data and Expected Result
1	**Description** The 'path' that you will use depends on where you are running the science pipelines. Options: • local (newinstall.sh - based install):[path_to_installation]/loadLSST.bash • development cluster ("lsst-dev"): /software/lsstsw/stack/loadLSST.bash • LSP Notebook aspect (from a terminal): /opt/lsst/software/stack/loadLSST.bash From the command line, execute the commands below in the example code:

Test Data

Example Code	source 'path' setup lsst_distrib

Rubin Observatory

Step	Description, Input Data and Expected Result	
	Expected Result	Science pipeline software is available for use. If additional packages are needed (for example, 'obs' packages such as 'obs_subaru'), then additional 'setup' commands will be necessary.
		To check versions in use, type: eups list -s

5.7 LVV-T866 - Run Alert Production Payload

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T866 in Jira

5.7.1 Test Items

Execute Alert Production payload on a dataset. Generate all (or a subset of) Prompt science data products including Alerts (with the exception of Solar System object orbits) and load them into the Data Backbone and Prompt Products Database.

5.7.2 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Perform the steps of Alert Production (including, but not necessarily limited to, single frame processing, ISR, source detection/measurement, PSF estimation, photometric and astrometric calibration, difference imaging, DIASource detection/measurement, source association). During Operations, it is presumed that these are automated for a given dataset.
	Test Data	
	Expected Result	An output dataset including difference images and DIASource and DIAObject measurements.
2	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	

Step	Description, Input Data and Expected Result	
	Expected Result	

5.8   LVV-T901 - Run MOPS payload

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T901 in Jira

5.8.1   Test Items

Run MOPS payload on a dataset (for example, one night's data). Generate entries in the MOPS Database and the Prompt Products Database, including Solar System Object records, measurements, and orbits. Perform precovery forced photometry of transients.

5.8.2   Predecessors

Uses results loaded into Prompt Products database and Data Backbone services in LVV-T866.

5.8.3   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Perform the steps of Moving Object Pipeline (MOPS) processing on newly detected DIASources, and generate Solar System data products including Solar System objects with associated Keplerian orbits, errors, and detected DIASources. This includes running processes to link DIASource detections within a night (called tracklets), to link these tracklets across multiple nights (into tracks), to fit the tracks with an orbital model to identify those tracks that are consistent with an asteroid orbit, to match these new orbits with existing SSObjects, and to update the SSObject table.
	Test Data	
	Expected Result	An output dataset consisting of an updated SSObject database with SSObjects both added and pruned as the orbital fits have been refined, and an updated DIASource database with DIASources assigned and unassigned to SSObjects.

Step	Description, Input Data and Expected Result	
2	Description	Verify that the expected data products have been produced, and that catalogs contain reasonable values for measured quantities of interest.
	Test Data	
	Expected Result	

5.9 LVV-T987 - Instantiate the Butler for reading data

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T987 in Jira

5.9.1 Test Items

Create a Butler client to read data from an input repository.

5.9.2 Input Specification

LVV-T860 must be executed to initialize the science pipelines.

5.9.3 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Identify the path to the data repository, which we will refer to as 'DATA/path', then execute the following:
	Test Data	
	Example Code	`import lsst.daf.persistence as dafPersist` `butler = dafPersist.Butler(inputs='DATA/path')`
	Expected Result	Butler repo available for reading.

Rubin Observatory

5.10 LVV-T1059 - Run Daily Calibration Products Update Payload

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1059 in Jira

5.10.1 Test Items

Execute the Daily Calibration Products Update payload to create a subset of Master Calibration images and Calibration Database entries.

5.10.2 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute the Daily Calibration Products Update payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	

5.11 LVV-T1060 - Run Periodic Calibration Products Production Payload

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1060 in Jira

Rubin Observatory

5.11.1 Test Items

Execute the Calibration Products Production payload to create a subset of Master Calibration images and Calibration Database entries.

5.11.2 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute the Calibration Products Production payload. The payload uses raw calibration images and information from the Transformed EFD to generate a subset of Master Calibration Images and Calibration Database entries in the Data Backbone.
	Test Data	
	Expected Result	
2	Description	Confirm that the expected Master Calibration images and Calibration Database entries are present and well-formed.
	Test Data	
	Expected Result	

5.12 LVV-T1064 - Run Data Release Production Payload

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1064 in Jira

5.12.1 Test Items

Execute the Data Release Production payload, starting from raw images and producing science data products.

5.12.2 Test Procedure

Rubin Observatory

Step	Description, Input Data and Expected Result	
1	Description	Process data with the Data Release Production payload, starting from raw science images and generating science data products, placing them in the Data Backbone.
	Test Data	
	Expected Result	

5.13 LVV-T1207 - Execute a simple ADQL query using the TAP service in the notebook aspect

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Jeffrey Carlin

Open LVV-T1207 in Jira

5.13.1 Test Items

Extract a small amount of data from a catalog via the LSST TAP service.

5.13.2 Input Specification

One must have access to the LSST Notebook Aspect, and have logged in and opened an empty notebook.

5.13.3 Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute a query in a notebook to select a small number of stars. In the example code below, we query the WISE catalog, then extract the results to an Astropy table.
	Test Data	

Rubin Observatory

Step	Description, Input Data and Expected Result
| Example Code | ```
import pandas
import pyvo
service = pyvo.dal.TAPService('http://lsst-lsp-stable.ncsa.illinois.edu/api/tap')

results = service.search("SELECT ra, decl, w1mpro_ep, w2mpro_ep, w3mpro_ep FROM wise_00.allwise_p3as_mep WHERE CONTAINS(POINT('ICRS', ra, decl), CIRCLE('ICRS', 192.85, 27.13, .2)) = 1")
tab = results.to_table()
``` |
| Expected Result | |

5.14   LVV-T1208 - Log out of the notebook aspect of the LSP

Version	Status	Priority	Verification Type	Owner
1	Draft	Normal	Test	Simon Krughoff

Open LVV-T1208 in Jira

5.14.1   Test Items

Leave the notebook aspect of the LSST Science Platform in a clean state

5.14.2   Test Procedure

Step	Description, Input Data and Expected Result
1	**Description** Under the 'File' menu at the top of your Jupyter notebook session, select one of the following: • Save All, Exit, and Log Out • Exit and Log Out Without Saving
	Test Data
	Expected Result You will be returned to the LSP landing page: `https://lsst-lsp-stable.ncsa.illinois.edu/` It is now safe to close the browser window.

Step	Description, Input Data and Expected Result

5.15   LVV-T1744 - Run validate_drp on precursor data

Version	Status	Priority	Verification Type	Owner
1	Defined	Normal	Analysis	Jeffrey Carlin

Open LVV-T1744 in Jira

5.15.1   Test Items

Run the validate_drp code on a precursor dataset to evaluate the metrics that have been implemented in validate_drp.

5.15.2   Test Procedure

Step	Description, Input Data and Expected Result	
1	Description	Execute 'validate_drp' on a repository containing precursor data. Identify the path to the data, which we will call 'DATA/path', then execute the following (with additional flags specified as needed):
	Test Data	
	Example Code	validateDrp.py 'DATA/path'
	Expected Result	JSON files (and associated figures) containing the Measurements and any associated "extras."

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED

508

Rubin Observatory

6 Deprecated Test Cases

This section includes all test cases that have been marked as deprecated. These test cases will never be executed again, but have been in the past. For this reason it is important to keep them in the baseline as a reference.

No deprecated test cases found.

Rubin Observatory

A Traceability

Verification Elements	High Level Requirements	Test Cases
LVV-139 - DMS-REQ-0308-V-01: Software Architecture to Enable Community Re-Use	OSS-REQ-0121	LVV-T10 LVV-T17 LVV-T124 LVV-T216 LVV-T216 LVV-T362 LVV-T363
LVV-46 - DMS-REQ-0106-V-01: Coadded Image Provenance	OSS-REQ-0122 DMS-REQ-0104	LVV-T11 LVV-T64
LVV-124 - DMS-REQ-0293-V-01: Selection of Datasets	OSS-REQ-0176 OSS-REQ-0118	LVV-T11 LVV-T98
LVV-134 - DMS-REQ-0303-V-01: Production Monitoring	OSS-REQ-0004 OSS-REQ-0038 OSS-REQ-0034	LVV-T11 LVV-T141
LVV-133 - DMS-REQ-0302-V-01: Production Orchestration	OSS-REQ-0004 OSS-REQ-0038 OSS-REQ-0117	LVV-T11 LVV-T140
LVV-136 - DMS-REQ-0305-V-01: Task Specification	OSS-REQ-0122 OSS-REQ-0121	LVV-T11 LVV-T144
LVV-137 - DMS-REQ-0306-V-01: Task Configuration	OSS-REQ-0122 OSS-REQ-0121	LVV-T11 LVV-T145
LVV-62 - DMS-REQ-0158-V-01: Provide Pipeline Construction Services		LVV-T11
LVV-165 - DMS-REQ-0334-V-01: Persisting Data Products	OSS-REQ-0136	LVV-T12 LVV-T13 LVV-T14 LVV-T15 LVV-T16 LVV-T78
LVV-98 - DMS-REQ-0267-V-01: Source Catalog	OSS-REQ-0137	LVV-T12 LVV-T13 LVV-T65 LVV-T362
LVV-99 - DMS-REQ-0268-V-01: Forced-Source Catalog	OSS-REQ-0137	LVV-T12 LVV-T66
LVV-106 - DMS-REQ-0275-V-01: Object Catalog	OSS-REQ-0137	LVV-T12 LVV-T14 LVV-T67
LVV-110 - DMS-REQ-0279-V-01: Deep Detection Coadds	OSS-REQ-0136	LVV-T12 LVV-T16 LVV-T73
LVV-125 - DMS-REQ-0294-V-01: Processing of Datasets	OSS-REQ-0120 OSS-REQ-0119 OSS-REQ-0118 OSS-REQ-0117	LVV-T12 LVV-T99

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-178 - DMS-REQ-0347-V-01: Measurements in catalogs	OSS-REQ-0391	LVV-T13 LVV-T14 LVV-T21 LVV-T22 LVV-T28 LVV-T1946 LVV-T1947
LVV-162 - DMS-REQ-0331-V-01: Computing Derived Quantities	OSS-REQ-0391	LVV-T13 LVV-T14 LVV-T21 LVV-T22 LVV-T24
LVV-29 - DMS-REQ-0069-V-01: Processed Visit Images	OSS-REQ-0129 OSS-REQ-0349 OSS-REQ-0348 OSS-REQ-0328	LVV-T15 LVV-T18 LVV-T19 LVV-T38 LVV-T362
LVV-158 - DMS-REQ-0327-V-01: Background Model Calculation	OSS-REQ-0056	LVV-T15 LVV-T19 LVV-T43
LVV-12 - DMS-REQ-0029-V-01: Generate Photometric Zeropoint for Visit Image	DMS-REQ-0090 OSS-REQ-0056 OSS-REQ-0152	LVV-T15 LVV-T19 LVV-T39
LVV-30 - DMS-REQ-0070-V-01: Generate PSF for Visit Images	OSS-REQ-0056 DMS-REQ-0116	LVV-T15 LVV-T19 LVV-T41
LVV-13 - DMS-REQ-0030-V-01: Absolute accuracy of WCS	DMS-REQ-0090 DMS-REQ-0104 OSS-REQ-0149 OSS-REQ-0162	LVV-T15 LVV-T19 LVV-T40
LVV-31 - DMS-REQ-0072-V-01: Processed Visit Image Content	OSS-REQ-0129 DMS-REQ-0066	LVV-T15 LVV-T19 LVV-T42
LVV-109 - DMS-REQ-0278-V-01: Coadd Image Method Constraints	OSS-REQ-0136	LVV-T16 LVV-T72
LVV-20 - DMS-REQ-0047-V-01: Provide PSF for Coadded Images	OSS-REQ-0153 DMS-REQ-0041 OSS-REQ-0136 OSS-REQ-0316	LVV-T16 LVV-T62
LVV-7 - DMS-REQ-0010-V-01: Difference Exposures	DMS-REQ-0011 DMS-REQ-0033 OSS-REQ-0129	LVV-T18 LVV-T20 LVV-T36
LVV-100 - DMS-REQ-0269-V-01: DIASource Catalog	OSS-REQ-0130 DMS-REQ-0270	LVV-T18 LVV-T21 LVV-T49
LVV-102 - DMS-REQ-0271-V-01: Max nearby galaxies associated with DIA-Source	OSS-REQ-0130	LVV-T18 LVV-T22 LVV-T51

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-32 - DMS-REQ-0074-V-01: Difference Exposure Attributes	OSS-REQ-0122 DMS-REQ-0066	LVV-T20 LVV-T37
LVV-101 - DMS-REQ-0270-V-01: Faint DIASource Measurements	OSS-REQ-0166	LVV-T21 LVV-T50
LVV-18 - DMS-REQ-0043-V-01: Provide Calibrated Photometry	OSS-REQ-0130 OSS-REQ-0275 OSS-REQ-0137	LVV-T21 LVV-T22 LVV-T129
LVV-116 - DMS-REQ-0285-V-01: Level 1 Source Association	OSS-REQ-0130 OSS-REQ-0160 OSS-REQ-0159	LVV-T22 LVV-T108
LVV-103 - DMS-REQ-0272-V-01: DIAObject Attributes	OSS-REQ-0130	LVV-T22 LVV-T52
LVV-157 - DMS-REQ-0326-V-01: Storing Approximations of Per-pixel Metadata	OSS-REQ-0391	LVV-T23
LVV-163 - DMS-REQ-0332-V-01: Denormalizing Database Tables	OSS-REQ-0133	LVV-T25
LVV-164 - DMS-REQ-0333-V-01: Maximum Likelihood Values and Covariances	OSS-REQ-0391	LVV-T26
LVV-177 - DMS-REQ-0346-V-01: Data Availability	OSS-REQ-0004 OSS-REQ-0167 OSS-REQ-0313	LVV-T27 LVV-T286
LVV-8 - DMS-REQ-0018-V-01: Raw Science Image Data Acquisition	OSS-REQ-0114	LVV-T29 LVV-T283 LVV-T284 LVV-T1549 LVV-T1550 LVV-T1556
LVV-9 - DMS-REQ-0020-V-01: Wavefront Sensor Data Acquisition	OSS-REQ-0316	LVV-T30 LVV-T283 LVV-T284 LVV-T1549 LVV-T1556
LVV-10 - DMS-REQ-0022-V-01: Crosstalk Corrected Science Image Data Acquisition	OSS-REQ-0114 OSS-REQ-0127	LVV-T31
LVV-11 - DMS-REQ-0024-V-01: Raw Image Assembly	OSS-REQ-0114 OSS-REQ-0129	LVV-T32 LVV-T283 LVV-T284 LVV-T1549 LVV-T1550 LVV-T1556
LVV-28 - DMS-REQ-0068-V-01: Raw Science Image Metadata	OSS-REQ-0122 DMS-REQ-0320 DMS-REQ-0066 OSS-REQ-0171	LVV-T33 LVV-T283 LVV-T284 LVV-T286 LVV-T1549 LVV-T1550 LVV-T1556

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-1234 - OSS-REQ-0122-V-01: Provenance	OSS-REQ-0123	LVV-T33 LVV-T37 LVV-T64 LVV-T89 LVV-T119
LVV-96 - DMS-REQ-0265-V-01: Guider Calibration Data Acquisition	OSS-REQ-0194	LVV-T34 LVV-T283 LVV-T284
LVV-175 - DMS-REQ-0004-V-01: Time to L1 public release	DMS-REQ-0003 OSS-REQ-0127	LVV-T35 LVV-T95
LVV-159 - DMS-REQ-0328-V-01: Documenting Image Characterization	OSS-REQ-0391	LVV-T44
LVV-39 - DMS-REQ-0097-V-01: Level 1 Data Quality Report Definition	OSS-REQ-0131 DMS-REQ-0096	LVV-T45
LVV-41 - DMS-REQ-0099-V-01: Level 1 Performance Report Definition	DMS-REQ-0098 OSS-REQ-0131	LVV-T46
LVV-43 - DMS-REQ-0101-V-01: Level 1 Calibration Report Definition	OSS-REQ-0131 DMS-REQ-0100	LVV-T47
LVV-97 - DMS-REQ-0266-V-01: Exposure Catalog	OSS-REQ-0130	LVV-T48
LVV-104 - DMS-REQ-0273-V-01: SSObject Catalog	OSS-REQ-0130	LVV-T53
LVV-105 - DMS-REQ-0274-V-01: Alert Content	OSS-REQ-0128	LVV-T54
LVV-148 - DMS-REQ-0317-V-01: DIAForcedSource Catalog	OSS-REQ-0130	LVV-T55
LVV-150 - DMS-REQ-0319-V-01: Characterizing Variability	OSS-REQ-0126	LVV-T56
LVV-154 - DMS-REQ-0323-V-01: Calculating SSObject Parameters	OSS-REQ-0126	LVV-T57
LVV-155 - DMS-REQ-0324-V-01: Matching DIASources to Objects	OSS-REQ-0126	LVV-T58
LVV-156 - DMS-REQ-0325-V-01: Regenerating L1 Data Products During Data Release Processing	OSS-REQ-0135	LVV-T59
LVV-184 - DMS-REQ-0353-V-01: Publishing predicted visit schedule	OSS-REQ-0378	LVV-T60
LVV-16 - DMS-REQ-0034-V-01: Associate Sources to Objects	DMS-REQ-0081 OSS-REQ-0339	LVV-T61
LVV-45 - DMS-REQ-0103-V-01: Produce Images for EPO	OSS-REQ-0136	LVV-T63
LVV-19 - DMS-REQ-0046-V-01: Provide Photometric Redshifts of Galaxies	OSS-REQ-0133 DMS-REQ-0040	LVV-T68
LVV-107 - DMS-REQ-0276-V-01: Object Characterization	OSS-REQ-0137	LVV-T69
LVV-180 - DMS-REQ-0349-V-01: Detecting extended low surface brightness objects	OSS-REQ-0133	LVV-T71
LVV-111 - DMS-REQ-0280-V-01: Template Coadds	OSS-REQ-0158 OSS-REQ-0136	LVV-T74
LVV-112 - DMS-REQ-0281-V-01: Multi-band Coadds	OSS-REQ-0136	LVV-T75
LVV-160 - DMS-REQ-0329-V-01: All-Sky Visualization of Data Releases	OSS-REQ-0136	LVV-T76
LVV-161 - DMS-REQ-0330-V-01: Best Seeing Coadds	OSS-REQ-0136	LVV-T77
LVV-166 - DMS-REQ-0335-V-01: PSF-Matched Coadds	OSS-REQ-0133	LVV-T79
LVV-168 - DMS-REQ-0337-V-01: Detecting faint variable objects	OSS-REQ-0136	LVV-T80
LVV-169 - DMS-REQ-0338-V-01: Targeted Coadds	LSR-REQ-0040 OSS-REQ-0136	LVV-T81
LVV-170 - DMS-REQ-0339-V-01: Tracking Characterization Changes Between Data Releases	LSR-REQ-0040	LVV-T82

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-22 - DMS-REQ-0059-V-01: Bad Pixel Map	OSS-REQ-0271 DMS-REQ-0058 OSS-REQ-0129	LVV-T83
LVV-23 - DMS-REQ-0060-V-01: Bias Residual Image	DMS-REQ-0055 OSS-REQ-0271 OSS-REQ-0046	LVV-T84 LVV-T368
LVV-24 - DMS-REQ-0061-V-01: Crosstalk Correction Matrix	OSS-REQ-0329 OSS-REQ-0330 DMS-REQ-0056 OSS-REQ-0349	LVV-T85
LVV-25 - DMS-REQ-0062-V-01: Illumination Correction Frame	OSS-REQ-0271 OSS-REQ-0046 DMS-REQ-0058	LVV-T86
LVV-26 - DMS-REQ-0063-V-01: Monochromatic Flatfield Data Cube	OSS-REQ-0271 OSS-REQ-0046 DMS-REQ-0058 DMS-REQ-0057	LVV-T87
LVV-57 - DMS-REQ-0130-V-01: Calibration Data Products	DMS-REQ-0076 OSS-REQ-0271 OSS-REQ-0194 OSS-REQ-0129	LVV-T88
LVV-59 - DMS-REQ-0132-V-01: Calibration Image Provenance	OSS-REQ-0122 OSS-REQ-0123 DMS-REQ-0130	LVV-T89
LVV-113 - DMS-REQ-0282-V-01: Dark Current Correction Frame Creation	OSS-REQ-0271 OSS-REQ-0046	LVV-T90
LVV-114 - DMS-REQ-0283-V-01: Fringe Correction Frame	OSS-REQ-0271 OSS-REQ-0046	LVV-T91
LVV-151 - DMS-REQ-0320-V-01: Processing of Data From Special Programs	LSR-REQ-0075 OSS-REQ-0392	LVV-T92
LVV-152 - DMS-REQ-0321-V-01: Level 1 Processing of Special Programs Data	OSS-REQ-0392	LVV-T93
LVV-153 - DMS-REQ-0322-V-01: Special Programs Database	OSS-REQ-0392	LVV-T94
LVV-1276 - OSS-REQ-0127-V-01: Level 1 Data Product Availability	LSR-REQ-0104 LSR-REQ-0117 LSR-REQ-0118 LSR-REQ-0126	LVV-T95 LVV-T102
LVV-122 - DMS-REQ-0291-V-01: Query Repeatability	OSS-REQ-0181	LVV-T96
LVV-123 - DMS-REQ-0292-V-01: Uniqueness of IDs Across Data Releases	OSS-REQ-0130 OSS-REQ-0137	LVV-T97
LVV-126 - DMS-REQ-0295-V-01: Transparent Data Access	OSS-REQ-0176	LVV-T100
LVV-3 - DMS-REQ-0002-V-01: Transient Alert Distribution	OSS-REQ-0184 OSS-REQ-0127	LVV-T101 LVV-T217
LVV-36 - DMS-REQ-0089-V-01: Solar System Objects Available Within Specified Time	DMS-REQ-0086 DMS-REQ-0004 OSS-REQ-0127	LVV-T102
LVV-9803 - DMS-REQ-0004-V-03: Time to availability of Solar System Object orbits	DMS-REQ-0003 OSS-REQ-0127	LVV-T102

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-38 - DMS-REQ-0096-V-01: Generate Data Quality Report Within Specified Time	OSS-REQ-0131	LVV-T103
LVV-40 - DMS-REQ-0098-V-01: Generate DMS Performance Report Within Specified Time	OSS-REQ-0131	LVV-T104
LVV-42 - DMS-REQ-0100-V-01: Generate Calibration Report Within Specified Time	OSS-REQ-0131	LVV-T105
LVV-58 - DMS-REQ-0131-V-01: Time allowed to process calibs	OSS-REQ-0046 OSS-REQ-0021 OSS-REQ-0194 DMS-REQ-0130	LVV-T106
LVV-115 - DMS-REQ-0284-V-01: Level-1 Production Completeness	OSS-REQ-0052	LVV-T107 LVV-T283 LVV-T284 LVV-T286
LVV-117 - DMS-REQ-0286-V-01: SSObject Precovery	OSS-REQ-0159	LVV-T109
LVV-118 - DMS-REQ-0287-V-01: Max look-back time for precovery	OSS-REQ-0130	LVV-T110
LVV-119 - DMS-REQ-0288-V-01: Use of External Orbit Catalogs	OSS-REQ-0159	LVV-T111
LVV-173 - DMS-REQ-0342-V-01: Alert Filtering Service	LSR-REQ-0025	LVV-T112 LVV-T218
LVV-174 - DMS-REQ-0343-V-01: Number of full-size alerts	OSS-REQ-0193 OSS-REQ-0184	LVV-T113 LVV-T218
LVV-179 - DMS-REQ-0348-V-01: Pre-defined alert filters	LSR-REQ-0026	LVV-T114 LVV-T218
LVV-120 - DMS-REQ-0289-V-01: Calibration Production Processing	OSS-REQ-0004 OSS-REQ-0170	LVV-T115
LVV-181 - DMS-REQ-0350-V-01: Associating Objects across data releases		LVV-T116
LVV-47 - DMS-REQ-0119-V-01: DAC resource allocation for Level 3 processing	OSS-REQ-0143	LVV-T117
LVV-48 - DMS-REQ-0120-V-01: Level 3 Data Product Self Consistency	OSS-REQ-0120 OSS-REQ-0118	LVV-T118
LVV-49 - DMS-REQ-0121-V-01: Provenance for Level 3 processing at DACs	OSS-REQ-0122	LVV-T119
LVV-53 - DMS-REQ-0125-V-01: Software framework for Level 3 catalog processing	OSS-REQ-0122 DMS-REQ-0120 OSS-REQ-0121	LVV-T120
LVV-56 - DMS-REQ-0128-V-01: Software framework for Level 3 image processing	OSS-REQ-0122 DMS-REQ-0120 OSS-REQ-0121	LVV-T121
LVV-121 - DMS-REQ-0290-V-01: Level 3 Data Import	OSS-REQ-0140	LVV-T122
LVV-171 - DMS-REQ-0340-V-01: Access Controls of Level 3 Data Products	OSS-REQ-0176 OSS-REQ-0187 OSS-REQ-0142	LVV-T123
LVV-6 - DMS-REQ-0009-V-01: Simulated Data	OSS-REQ-0353 DMS-REQ-0007 OSS-REQ-0351 OSS-REQ-0354	LVV-T125
LVV-14 - DMS-REQ-0032-V-01: Image Differencing	OSS-REQ-0121 OSS-REQ-0129	LVV-T126

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-15 - DMS-REQ-0033-V-01: Provide Source Detection Software	OSS-REQ-0130 OSS-REQ-0137 OSS-REQ-0121 DMS-REQ-0080	LVV-T127 LVV-T362
LVV-17 - DMS-REQ-0042-V-01: Provide Astrometric Model	OSS-REQ-0153 OSS-REQ-0149 OSS-REQ-0160 OSS-REQ-0162	LVV-T128
LVV-21 - DMS-REQ-0052-V-01: Enable a Range of Shape Measurement Approaches	OSS-REQ-0137	LVV-T130
LVV-63 - DMS-REQ-0160-V-01: Provide User Interface Services	OSS-REQ-0057	LVV-T131 LVV-T368
LVV-127 - DMS-REQ-0296-V-01: Pre-cursor, and Real Data		LVV-T132 LVV-T362
LVV-182 - DMS-REQ-0351-V-01: Provide Beam Projector Coordinate Calculation Software	OSS-REQ-0383	LVV-T133
LVV-27 - DMS-REQ-0065-V-01: Provide Image Access Services	OSS-REQ-0180 OSS-REQ-0176 OSS-REQ-0181 DMS-REQ-0066	LVV-T134
LVV-129 - DMS-REQ-0298-V-01: Data Product and Raw Data Access	OSS-REQ-0176	LVV-T136 LVV-T368 LVV-T374
LVV-130 - DMS-REQ-0299-V-01: Data Product Ingest	OSS-REQ-0141 OSS-REQ-0004	LVV-T137 LVV-T374
LVV-131 - DMS-REQ-0300-V-01: Bulk Download Service	OSS-REQ-0178	LVV-T138
LVV-135 - DMS-REQ-0304-V-01: Production Fault Tolerance	OSS-REQ-0117	LVV-T142
LVV-128 - DMS-REQ-0297-V-01: DMS Initialization Component	OSS-REQ-0041 OSS-REQ-0122 OSS-REQ-0307 OSS-REQ-0121	LVV-T146
LVV-132 - DMS-REQ-0301-V-01: Control of Level-1 Production	OSS-REQ-0044	LVV-T147
LVV-138 - DMS-REQ-0307-V-01: Unique Processing Coverage	OSS-REQ-0120 OSS-REQ-0118	LVV-T148
LVV-33 - DMS-REQ-0075-V-01: Catalog Queries	DMS-REQ-0076 OSS-REQ-0176	LVV-T149 LVV-T1085 LVV-T1086 LVV-T1087
LVV-34 - DMS-REQ-0077-V-01: Maintain Archive Publicly Accessible	DMS-REQ-0076 OSS-REQ-0186	LVV-T150
LVV-35 - DMS-REQ-0078-V-01: Catalog Export Formats	DMS-REQ-0076 OSS-REQ-0176	LVV-T151 LVV-T1232
LVV-37 - DMS-REQ-0094-V-01: Keep Historical Alert Archive	DMS-REQ-0092 OSS-REQ-0128	LVV-T152
LVV-44 - DMS-REQ-0102-V-01: Provide Engineering & Facility Database Archive	OSS-REQ-0132	LVV-T153
LVV-140 - DMS-REQ-0309-V-01: Raw Data Archiving Reliability	OSS-REQ-0111	LVV-T154 LVV-T287 LVV-T454

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-141 - DMS-REQ-0310-V-01: Un-Archived Data Product Cache	OSS-REQ-0130	LVV-T155
LVV-142 - DMS-REQ-0311-V-01: Regenerate Un-archived Data Products	OSS-REQ-0129	LVV-T156
LVV-143 - DMS-REQ-0312-V-01: Level 1 Data Product Access	OSS-REQ-0185 OSS-REQ-0127	LVV-T157
LVV-144 - DMS-REQ-0313-V-01: Level 1 & 2 Catalog Access	OSS-REQ-0186	LVV-T158
LVV-167 - DMS-REQ-0336-V-01: Regenerating Data Products from Previous Data Releases	LSR-REQ-0049	LVV-T159
LVV-172 - DMS-REQ-0341-V-01: Max elapsed time for precovery results	OSS-REQ-0126	LVV-T160
LVV-176 - DMS-REQ-0345-V-01: Logging of catalog queries	OSS-REQ-0134	LVV-T161
LVV-189 - DMS-REQ-0363-V-01: Access to Previous Data Releases	OSS-REQ-0186	LVV-T162
LVV-190 - DMS-REQ-0364-V-01: Total number of data releases	OSS-REQ-0396	LVV-T163
LVV-191 - DMS-REQ-0365-V-01: Operations Subsets	OSS-REQ-0398	LVV-T164
LVV-192 - DMS-REQ-0366-V-01: Subsets Support	OSS-REQ-0400	LVV-T165
LVV-193 - DMS-REQ-0367-V-01: Access Services Performance	OSS-REQ-0394	LVV-T166
LVV-194 - DMS-REQ-0368-V-01: Implementation Provisions	OSS-REQ-0399	LVV-T167
LVV-195 - DMS-REQ-0369-V-01: Evolution	OSS-REQ-0395	LVV-T168
LVV-196 - DMS-REQ-0370-V-01: Older Release Behavior	OSS-REQ-0397	LVV-T169
LVV-197 - DMS-REQ-0371-V-01: Query Availability	OSS-REQ-0401	LVV-T170
LVV-5 - DMS-REQ-0008-V-01: Pipeline Availability		LVV-T171 LVV-T287
LVV-64 - DMS-REQ-0161-V-01: Optimization of Cost, Reliability and Availability in Order		LVV-T172
LVV-65 - DMS-REQ-0162-V-01: Pipeline Throughput	OSS-REQ-0020 OSS-REQ-0127	LVV-T173 LVV-T287
LVV-66 - DMS-REQ-0163-V-01: Re-processing Capacity	OSS-REQ-0134	LVV-T174
LVV-67 - DMS-REQ-0164-V-01: Temporary Storage for Communications Links	DMS-REQ-0162	LVV-T175
LVV-68 - DMS-REQ-0165-V-01: Infrastructure Sizing for "catching up"	OSS-REQ-0052 OSS-REQ-0051 DMS-REQ-0162 OSS-REQ-0050	LVV-T176 LVV-T287
LVV-994 - OSS-REQ-0051-V-01: Summit-Base Connectivity Loss		LVV-T176
LVV-69 - DMS-REQ-0166-V-01: Incorporate Fault-Tolerance	DMS-REQ-0161	LVV-T177
LVV-70 - DMS-REQ-0167-V-01: Incorporate Autonomics	DMS-REQ-0166	LVV-T178 LVV-T287
LVV-145 - DMS-REQ-0314-V-01: Compute Platform Heterogeneity	OSS-REQ-0177 OSS-REQ-0124	LVV-T179 LVV-T287
LVV-149 - DMS-REQ-0318-V-01: Data Management Unscheduled Downtime	OSS-REQ-0373	LVV-T180 LVV-T287
LVV-18491 - DMS-REQ-0352-V-02: Base Voice Over IP (VOIP)	OSS-REQ-0003	LVV-T181
LVV-72 - DMS-REQ-0170-V-01: Prefer Computing and Storage Down	DMS-REQ-0161	LVV-T182
LVV-146 - DMS-REQ-0315-V-01: DMS Communication with OCS	OSS-REQ-0003	LVV-T183 LVV-T283 LVV-T284 LVV-T1549 LVV-T1556
LVV-74 - DMS-REQ-0172-V-01: Summit to Base Network Availability	OSS-REQ-0373 DMS-REQ-0161	LVV-T185

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-75 - DMS-REQ-0173-V-01: Summit to Base Network Reliability	OSS-REQ-0373 DMS-REQ-0161	LVV-T186
LVV-76 - DMS-REQ-0174-V-01: Summit to Base Network Secondary Link	DMS-REQ-0173 OSS-REQ-0049 DMS-REQ-0172	LVV-T187
LVV-77 - DMS-REQ-0175-V-01: Summit to Base Network Ownership and Operation	DMS-REQ-0173 OSS-REQ-0036 DMS-REQ-0172	LVV-T188
LVV-78 - DMS-REQ-0176-V-01: Base Facility Infrastructure	OSS-REQ-0003	LVV-T189
LVV-80 - DMS-REQ-0178-V-01: Base Facility Co-Location with Existing Facility	DMS-REQ-0161 OSS-REQ-0006	LVV-T190
LVV-147 - DMS-REQ-0316-V-01: Commissioning Cluster		LVV-T191
LVV-183 - DMS-REQ-0352-V-01: Base Wireless LAN (WiFi)	OSS-REQ-0003	LVV-T192
LVV-81 - DMS-REQ-0180-V-01: Base to Archive Network	OSS-REQ-0053 OSS-REQ-0055 DMS-REQ-0162	LVV-T193
LVV-82 - DMS-REQ-0181-V-01: Base to Archive Network Availability	OSS-REQ-0053 DMS-REQ-0162 DMS-REQ-0161	LVV-T194
LVV-83 - DMS-REQ-0182-V-01: Base to Archive Network Reliability	OSS-REQ-0053 DMS-REQ-0161	LVV-T195
LVV-84 - DMS-REQ-0183-V-01: Base to Archive Network Secondary Link	DMS-REQ-0181 DMS-REQ-0182 OSS-REQ-0049	LVV-T196
LVV-85 - DMS-REQ-0185-V-01: Archive Center	OSS-REQ-0004 DMS-REQ-0163	LVV-T197
LVV-86 - DMS-REQ-0186-V-01: Archive Center Disaster Recovery	OSS-REQ-0176 DMS-REQ-0161	LVV-T198
LVV-87 - DMS-REQ-0187-V-01: Archive Center Co-Location with Existing Facility	OSS-REQ-0022 DMS-REQ-0161	LVV-T199
LVV-88 - DMS-REQ-0188-V-01: Archive to Data Access Center Network	OSS-REQ-0004	LVV-T200
LVV-89 - DMS-REQ-0189-V-01: Archive to Data Access Center Network Availability	DMS-REQ-0161	LVV-T201
LVV-90 - DMS-REQ-0190-V-01: Archive to Data Access Center Network Reliability	DMS-REQ-0161	LVV-T202
LVV-91 - DMS-REQ-0191-V-01: Archive to Data Access Center Network Secondary Link	DMS-REQ-0189 DMS-REQ-0190	LVV-T203
LVV-50 - DMS-REQ-0122-V-01: Access to catalogs for external Level 3 processing	OSS-REQ-0180 OSS-REQ-0140	LVV-T204
LVV-51 - DMS-REQ-0123-V-01: Access to input catalogs for DAC-based Level 3 processing	OSS-REQ-0140	LVV-T205
LVV-52 - DMS-REQ-0124-V-01: Federation with external catalogs	OSS-REQ-0140 DMS-REQ-0125	LVV-T206
LVV-54 - DMS-REQ-0126-V-01: Access to images for external Level 3 processing	OSS-REQ-0180 OSS-REQ-0140	LVV-T207

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-55 - DMS-REQ-0127-V-01: Access to input images for DAC-based Level 3 processing	OSS-REQ-0140	LVV-T208
LVV-92 - DMS-REQ-0193-V-01: Data Access Centers	OSS-REQ-0004	LVV-T209
LVV-93 - DMS-REQ-0194-V-01: Data Access Center Simultaneous Connections		LVV-T210
LVV-94 - DMS-REQ-0196-V-01: Data Access Center Geographical Distribution	DMS-REQ-0193 OSS-REQ-0021 OSS-REQ-0022	LVV-T211
LVV-95 - DMS-REQ-0197-V-01: No Limit on Data Access Centers	DMS-REQ-0193 OSS-REQ-0021 OSS-REQ-0022	LVV-T212
LVV-3402 - DMS-REQ-0360-V-01: Median astrometric error on 20 arcmin scales	OSS-REQ-0388	LVV-T363 LVV-T1745
LVV-3404 - DMS-REQ-0362-V-01: Median residual PSF ellipticity correlations on 5 arcmin scales	OSS-REQ-0403 OSS-REQ-0404 OSS-REQ-0405	LVV-T376 LVV-T1754
LVV-9780 - DMS-REQ-0362-V-02: Max fraction of excess ellipticity residuals on 1 and 5 arcmin scales	OSS-REQ-0403 OSS-REQ-0404 OSS-REQ-0405	LVV-T376
LVV-9751 - DMS-REQ-0359-V-02: Max fraction of sensors with excess unusable pixels	OSS-REQ-0387	LVV-T377 LVV-T1847
LVV-9757 - DMS-REQ-0359-V-08: Max cross-talk imperfections	OSS-REQ-0387	LVV-T377 LVV-T1843
LVV-9755 - DMS-REQ-0359-V-06: Accuracy of photometric transformation	OSS-REQ-0387	LVV-T377 LVV-T1845
LVV-9756 - DMS-REQ-0359-V-07: RMS width of zero point in u-band	OSS-REQ-0387	LVV-T377 LVV-T1844
LVV-9753 - DMS-REQ-0359-V-04: Accuracy of zero point for colors with u-band	OSS-REQ-0387	LVV-T377 LVV-T1846
LVV-9762 - DMS-REQ-0359-V-13: Max sky brightness error	OSS-REQ-0387	LVV-T377 LVV-T1840
LVV-9760 - DMS-REQ-0359-V-11: Fraction of zero point outliers	OSS-REQ-0387	LVV-T377 LVV-T1842
LVV-9761 - DMS-REQ-0359-V-12: Max fraction of unusable pixels per sensor	OSS-REQ-0387	LVV-T377 LVV-T1841
LVV-9764 - DMS-REQ-0359-V-15: Percentage of image area with ghosts	OSS-REQ-0387	LVV-T377 LVV-T1838
LVV-9766 - DMS-REQ-0359-V-17: Max RMS of resolved/unresolved flux ratio	OSS-REQ-0387	LVV-T377 LVV-T1836
LVV-9763 - DMS-REQ-0359-V-14: RMS width of zero point in all bands except u	OSS-REQ-0387	LVV-T377 LVV-T1839
LVV-9765 - DMS-REQ-0359-V-16: Accuracy of zero point for colors without u-band	OSS-REQ-0387	LVV-T377 LVV-T1837
LVV-9778 - DMS-REQ-0360-V-12: RMS difference between r-band and other filter separation	OSS-REQ-0388	LVV-T378 LVV-T1753

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-9777 - DMS-REQ-0360-V-11: Max fraction of r-band color difference outliers	OSS-REQ-0388	LVV-T378 LVV-T1750
LVV-9779 - DMS-REQ-0360-V-13: Max fraction exceeding limit on 200 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1752
LVV-9773 - DMS-REQ-0360-V-07: Outlier limit on 5 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1746
LVV-9770 - DMS-REQ-0360-V-05: Outlier limit on 20 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1749
LVV-9775 - DMS-REQ-0360-V-09: Outlier limit on 200 arcmin scales	OSS-REQ-0388	LVV-T378
LVV-9769 - DMS-REQ-0360-V-04: Median absolute error in RA, Dec	OSS-REQ-0388	LVV-T378 LVV-T1748
LVV-9774 - DMS-REQ-0360-V-08: Median astrometric error on 200 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1751
LVV-9768 - DMS-REQ-0360-V-03: Median astrometric error on 5 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1747
LVV-9771 - DMS-REQ-0360-V-06: Color difference outlier limit relative to r-band	OSS-REQ-0388	LVV-T378 LVV-T1750
LVV-9776 - DMS-REQ-0360-V-10: Max fraction exceeding limit on 20 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1749
LVV-9767 - DMS-REQ-0360-V-02: Max fraction exceeding limit on 5 arcmin scales	OSS-REQ-0388	LVV-T378 LVV-T1746
LVV-3394 - DMS-REQ-0377-V-01: Min number of simultaneous single-CCD coadd cutout image users	OSS-REQ-0181	LVV-T385
LVV-9787 - DMS-REQ-0356-V-04: Max time to retrieve low-volume query results	OSS-REQ-0181	LVV-T1085 LVV-T1089 LVV-T1090
LVV-188 - DMS-REQ-0357-V-01: Result latency for high-volume full-sky queries on the Object table	OSS-REQ-0181	LVV-T1086 LVV-T1088 LVV-T1089 LVV-T1090
LVV-185 - DMS-REQ-0354-V-01: Result latency for high-volume complex queries	OSS-REQ-0181	LVV-T1086 LVV-T1087 LVV-T1088 LVV-T1089 LVV-T1090
LVV-3403 - DMS-REQ-0361-V-01: Simultaneous users for high-volume queries	OSS-REQ-0181	LVV-T1088 LVV-T1089 LVV-T1090
LVV-9786 - DMS-REQ-0356-V-03: Min number of simultaneous low-volume query users	OSS-REQ-0181	LVV-T1089 LVV-T1090
LVV-71 - DMS-REQ-0168-V-01: Summit Facility Data Communications	OSS-REQ-0002	LVV-T1097
LVV-73 - DMS-REQ-0171-V-01: Summit to Base Network	OSS-REQ-0003 OSS-REQ-0127	LVV-T1168 LVV-T1612

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-9741 - DMS-REQ-0030-V-02: Minimum astrometric standards per CCD	DMS-REQ-0090 DMS-REQ-0104 OSS-REQ-0149 OSS-REQ-0162	LVV-T1240
LVV-3400 - DMS-REQ-0358-V-01: Min number of simultaneous DM EFD query users	OSS-REQ-0181	LVV-T1250
LVV-9788 - DMS-REQ-0358-V-02: Max time to retrieve DM EFD query results	OSS-REQ-0181	LVV-T1251
LVV-9748 - DMS-REQ-0343-V-02: Number of simultaneous users	OSS-REQ-0193 OSS-REQ-0184	LVV-T1252
LVV-9637 - DMS-REQ-0372-V-01: Archiving Camera Test Data		LVV-T1264
LVV-9740 - DMS-REQ-0004-V-02: Latency of reporting optical transients	DMS-REQ-0003 OSS-REQ-0127	LVV-T1276
LVV-9745 - DMS-REQ-0131-V-02: Max number of calibs to be processed	OSS-REQ-0046 OSS-REQ-0021 OSS-REQ-0194 DMS-REQ-0130	LVV-T1277
LVV-9797 - DMS-REQ-0377-V-02: Max time to retrieve single-CCD coadd cutout image	OSS-REQ-0181	LVV-T1332
LVV-18222 - DMS-REQ-0384-V-01: Export MOCs As FITS_1	OSS-REQ-0391	LVV-T1524
LVV-18223 - DMS-REQ-0381-V-01: HiPS Linkage to Coadds_1	OSS-REQ-0122 OSS-REQ-0061	LVV-T1525
LVV-18224 - DMS-REQ-0380-V-01: HiPS Service_1	OSS-REQ-0176	LVV-T1526
LVV-18225 - DMS-REQ-0382-V-01: HiPS Visualization_1	OSS-REQ-0061	LVV-T1527
LVV-18226 - DMS-REQ-0385-V-01: MOC Visualization_1	OSS-REQ-0033 OSS-REQ-0061	LVV-T1528
LVV-18227 - DMS-REQ-0379-V-01: Produce All-Sky HiPS Map_1	OSS-REQ-0391 OSS-REQ-0136	LVV-T1529
LVV-18228 - DMS-REQ-0383-V-01: Produce MOC Maps_1	OSS-REQ-0391 OSS-REQ-0033	LVV-T1530
LVV-18230 - DMS-REQ-0386-V-01: Archive Processing Provenance_1	OSS-REQ-0172	LVV-T1560
LVV-18231 - DMS-REQ-0387-V-01: Serve Archived Provenance_1	OSS-REQ-0172	LVV-T1561
LVV-18232 - DMS-REQ-0388-V-01: Provide Re-Run Tools_1	OSS-REQ-0122 OSS-REQ-0123 OSS-REQ-0172	LVV-T1562
LVV-18233 - DMS-REQ-0390-V-01: Re-Runs on Other Systems_1	OSS-REQ-0122 OSS-REQ-0169 OSS-REQ-0123 OSS-REQ-0172	LVV-T1563
LVV-18234 - DMS-REQ-0389-V-01: Re-Runs on Similar Systems_1	OSS-REQ-0122 OSS-REQ-0169 OSS-REQ-0123 OSS-REQ-0172	LVV-T1564
LVV-9782 - DMS-REQ-0362-V-04: Median residual PSF ellipticity correlations on 1 arcmin scales	OSS-REQ-0403 OSS-REQ-0404 OSS-REQ-0405	LVV-T1755
LVV-3401 - DMS-REQ-0359-V-01: RMS photometric repeatability in uzy	OSS-REQ-0387	LVV-T1756
LVV-9759 - DMS-REQ-0359-V-10: RMS photometric repeatability in gri	OSS-REQ-0387	LVV-T1757
LVV-9758 - DMS-REQ-0359-V-09: Repeatability outlier limit in uzy	OSS-REQ-0387	LVV-T1758

Rubin Observatory

Verification Elements	High Level Requirements	Test Cases
LVV-9752 - DMS-REQ-0359-V-03: Max fraction of outliers among non-saturated sources	OSS-REQ-0387	LVV-T1758 LVV-T1759
LVV-9754 - DMS-REQ-0359-V-05: Repeatability outlier limit in gri	OSS-REQ-0387	LVV-T1759
LVV-18465 - DMS-REQ-0395-V-01: Scientific Visualization of Camera Image Data_1	OSS-REQ-0408	LVV-T1830
LVV-18295 - DMS-REQ-0394-V-01: Data Management Nightly Reporting_1	OSS-REQ-0406	LVV-T1831
LVV-18881 - DMS-REQ-0282-V-02: Dark Current Correction Frame Effectiveness	OSS-REQ-0271 OSS-REQ-0046	LVV-T1862
LVV-18847 - DMS-REQ-0397-V-01: Prompt/DR Processing of Data from Special Programs_1	OSS-REQ-0392	LVV-T1863
LVV-18229 - DMS-REQ-0344-V-01: Time to L1 public release	OSS-REQ-0392	LVV-T1865
LVV-9744 - DMS-REQ-0344-V-02: Latency of reporting optical transients	OSS-REQ-0392	LVV-T1866
LVV-18297 - DMS-REQ-0391-V-01: Alert Stream Distribution nStreams	OSS-REQ-0184 OSS-REQ-0127	LVV-T1867
LVV-18911 - DMS-REQ-0391-V-02: Alert Stream Distribution Latency	OSS-REQ-0184 OSS-REQ-0127	LVV-T1868